## Alinta Energy Transmission (Roy Hill) Pty Ltd

## 2019 Electricity Integrated Regional Licence (EIRL6) Asset Management System Review

## Report

1 October 2016 to 30 September 2019



Deloitte Touche Tohmatsu ABN 74 490 121 060

Tower 2, Brookfield Place 123 St Georges Terrace Perth WA 6000 GPO Box A46 Perth WA 6837 Australia

Tel: +61 8 9365 7000 Fax: +61 8 9365 7001 www.deloitte.com.au

Ms Catherine Rousch Manager Regulatory Compliance Alinta Sales Pty Ltd, trading as Alinta Energy Level 18 Raine Square 300 Murray Street Perth WA 6000

17 December 2019

Dear Catherine

#### Alinta Energy Transmission (Roy Hill) Pty Ltd – 2019 EIRL6 Asset Management System Review

We have completed the limited assurance engagement on the 2019 EIRL6 Asset Management System review for Alinta Energy Transmission (Roy Hill) Pty Ltd for the period 1 October 2016 to 30 September 2019 and are pleased to submit our report to you.

I confirm that this report is an accurate presentation of the findings and conclusions from our review procedures.

If you have any questions or wish to discuss anything raised in the report, please contact me on 0456 585 247.

Yours sincerely

### DELOITTE TOUCHE TOHMATSU

Vincent Snijders Partner Chartered Accountants Perth

# Contents

1	Independent assurance practitioner's report	4	
2	Executive summary	7	
3	Summary of ratings	13	
4	Detailed findings, recommendations and action plans	17	
5	Follow-up of previous review action plans	47	
App	endix A - Review plan	49	
Арре	Appendix B - References 5		

## 1 Independent assurance practitioner's report

### Conclusion

We have undertaken a limited assurance engagement on the compliance of Alinta Energy Transmission (Roy Hill) Pty Ltd's (**AETRH or Alinta**) Asset Management System (**AMS**) effectiveness and performance, in all material respects, as evaluated against its effectiveness criteria in the Electricity Integrated Regional Licence (EIRL6) (the **Licence**) and applicable obligations from the *Audit and Review Guidelines: Electricity and Gas Licences* (the **Guidelines**) released in March 2019, for the period 1 October 2016 to 30 September 2019, for the purpose of assisting AETRH comply with its reporting obligations to the Economic Regulation Authority (the **ERA**).

Based on the procedures we have performed and the evidence we have obtained, except for the effects of the matters described in the 'Basis for qualified conclusion' paragraph below, nothing has come to our attention that causes us to believe AETRH has not established and maintained, in all material respects, an effective AMS for assets subject to the Licence, as measured by the effectiveness criteria in the March 2019 Guidelines issued by the ERA, and the systems have not operated effectively for the review period.

#### **Basis for qualified conclusion**

During the period from 1 October 2016 to 30 September 2019, AETRH did not comply with the effectiveness criteria in the following instances:

AMS key process and effectiveness criteria	Issue
Asset planning 1.1 Asset Management Plan covers key requirements	The Asset Management Plan ( <b>AMP</b> ) did not contain all the key requirements tailored to Alinta's purposes.
<ul> <li>1.9 Plans are regularly reviewed and updated <i>Review of AMS</i></li> <li>12.1 A review process is in place to ensure that the AMP and the AMS described therein are kept current</li> </ul>	In response to recommendation 1/2016 of the previous AMS review, Alinta has included several key requirements but is yet to include a reference to contingency plans in the Newman AMP. The Newman AMP for FY2019 to FY2023 was last reviewed on 2 July 2018, is in draft, with key sections still to be completed.
Risk Management 8.1 Risk management policies and procedures exist and are being applied to minimise internal and external risks associated with the AMS. 8.2 Risks are documented in a risk register and treatment plans are actioned and monitored	There are outdated risks in the InControl Risk Management System (two out of seven samples), as well as risks that require updates, amendments or review (one out of seven samples).
Contingency planning 9.1 Contingency plans are documented, understood and tested to confirm their operability and to cover higher risks	<ul> <li>AETRH did not:</li> <li>Document the testing arrangements of its contingency plan</li> <li>Perform testing of the contingency plan.</li> </ul>

We conducted our engagement in accordance with Standard on Assurance Engagements ASAE 3500 *Performance Engagements* issued by the Auditing and Assurance Standards Board.

We believe that the evidence we have obtained is sufficient and appropriate to provide a basis for our conclusion.

#### **AETRH's responsibility for the AMS**

AETRH is responsible for ensuring that it has:

- Complied, in all material respects, with the requirements of its Licence as specified by the Guidelines
- Established and maintained an effective AMS for assets subject to its Licence, as measured by the effectiveness criteria detailed in the Guidelines.

#### Assurance practitioner's independence and quality control

We have complied with the independence and other relevant ethical requirements relating to assurance engagements, which are founded on fundamental principles of integrity, objectivity, professional competence and due care, confidentiality, and professional behaviour.

The firm applies Auditing Standard ASQC 1 *Quality Control for Firms that Perform Audits and Reviews of Financial Reports and Other Financial Information, and Other Assurance Engagements,* and accordingly maintains a comprehensive system of quality control including documented policies and procedures regarding compliance with ethical requirements, professional standards and applicable legal and regulatory requirements.

#### Assurance practitioner's responsibilities

Our responsibility is to express a limited assurance conclusion on AETRH's AMS for assets subject to its Licence, based on the procedures we have performed and the evidence we have obtained. We conducted our limited assurance engagement in accordance with Australian Standard on Assurance Engagements ASAE 3500 *Performance Engagements,* issued by the Australian Auditing and Assurance Standards Board, in order to express a conclusion whether, based on the procedures performed and the evidence obtained, anything has come to our attention that causes us to believe that AETRH's AMS for assets subject to its Licence, have not been established and maintained, in all material respects, in accordance with the Licence as measured by the effectiveness criteria in the Guidelines. That standard requires that we plan and perform this engagement to obtain limited assurance about whether the AMS for assets subject to the Licence is materially ineffective.

A limited assurance engagement conducted in accordance with ASAE 3500 involves identifying areas where the AMS for assets subject to a Licence is likely to be materially ineffective, addressing the areas identified and considering the process used to prepare the AMS for assets subject to the Licence. A limited assurance engagement is substantially less in scope than a reasonable assurance engagement in relation to both the risk assessment procedures, including an understanding of internal control, and the procedures performed in response to the assessed risks.

#### **Procedures performed**

The procedures we performed were based on our professional judgement and consisted primarily of:

- Utilising the Guidelines as a guide for development of a risk assessment, which involved discussions with key staff and review of documents to perform a preliminary controls assessment
- Development of a Review Plan for approval by the ERA and an associated work program
- Interviews with and representations from relevant AETRH staff to gain an understanding of the development and maintenance of policies and procedural type documentation (a full list of staff engaged has been provided at **Appendix B**)
- Examination of documented policies and procedures for key functional requirements and consideration of their relevance to AETRH's AMS requirements and standards
- Physical visits to operations in Newman
- Consideration of reports and references evidencing activity
- Consideration of activities performed by the AETRH that relate to operation of the assets.

The procedures performed in a limited assurance engagement vary in nature and timing from, and are less in extent than for, a reasonable assurance engagement. Consequently, the level of assurance obtained in a limited assurance engagement is substantially lower than the assurance that would have been obtained had we performed a reasonable assurance engagement. Accordingly, we do not express a reasonable assurance opinion on the effectiveness of AETRH's AMS for assets subject to the Licence.

#### **Inherent Limitations**

Because of the inherent limitations of an assurance engagement, together with the inherent limitation of any system of controls there is an unavoidable risk that fraud, error or non-compliance with the requirements of the Guidelines may occur and not be detected.

A limited assurance engagement relating to the period from 1 October 2016 to 30 September 2019 does not provide assurance on whether the effectiveness of AETRH's AMS for assets subject to the Licence will continue in the future.

#### **Restricted use**

This report has been prepared for use by AETRH for the purpose of satisfying its obligation under Section 14 of the Electricity Industry Act 2004. We disclaim any assumption of responsibility for any reliance on this report to any person other than AETRH, or for any purpose other than that for which it was prepared. We understand that a copy of the report will be provided to the ERA for the purpose of reporting on the effectiveness of AETRH'S AMS. We agree that a copy of this report will be given to the ERA in connection with this purpose, however we accept no responsibility to the ERA or to anyone who is provided with or obtains a copy of our report.

### **DELOITTE TOUCHE TOHMATSU**

Vincent Snijders Partner Chartered Accountant 17 December 2019, Perth

## 2 Executive summary

## 2.1 Introduction and background

The Economic Regulation Authority (the **ERA**) has under the provisions of the *Electricity Industry Act* 2004 (the **Act**), issued to Alinta Energy Transmission (Roy Hill) Pty Ltd (**AETRH or Alinta**) the Electricity Integrated Regional Licence (EIRL6) (the **Licence**).

The Licence relates to AETRH's generation, transmission, and retail activity in relation to its Newman power station.

Section 14 of the Act requires Alinta to provide to the ERA an AMS review (the **review**) conducted by an independent expert acceptable to the ERA not less than once in every 24-month period (or any longer period that the ERA allows). The ERA set the period to be covered by the review as 1 October 2016 to 30 September 2019 (**review period**).

At the request of Alinta, Deloitte Touche Tohmatsu (**Deloitte**) has undertaken a limited assurance review of AETRH's AMS.

The review has been conducted in accordance with the March 2019 issue of the Guidelines.

## 2.2 Findings

In considering AETRH's internal control procedures, structure and environment, its compliance arrangements, and its information systems specifically relevant to those effectiveness criteria subject to review and with a focus on its electricity generation and transmission activity, we observed AETRH:

- Applies a continuous improvement approach to its asset management practices, with a number of incremental improvements introduced throughout the review period
- Maintained a stable asset management system and applied consistent asset management practices throughout the review period
- Is supported by corporate systems and functions maintained by its parent entity, Alinta Energy
- Partially actioned the four recommendations made in the 2016 AMS review. The remaining components of the 2016 recommendations have been incorporated into updated 2019 recommendations
- Needs to take corrective action in relation to:
  - $\circ$   $\:$  Updating and expanding the AMP to contain the required elements of an AMP tailored to AETRH's needs
  - Completing the sections in the AMP, which are incomplete and finalise the document.

The following tables summarise the assessments made during the review of AETRH's compliance and the adequacy of controls in place for AETRH to manage its compliance with the conditions of its Licence.

**Table 1** sets out the rating scale defined by the ERA in the Guidelines for the assessment of the level of compliance with the conditions of its Licence. For the highest possible compliance rating to be achieved, AETRH was required to demonstrate it has maintained mature processes and controls, which enable compliance with relevant obligations.

### Table 1: Control adequacy and compliance rating scale

	Adequacy of Controls Rating		Compliance Rating
Rating	Description	Rating	Description
А	Adequate controls – no improvement needed	1	Compliant
В	Generally adequate controls – improvement needed	2	Non-compliant – minor impact on customers or third parties
С	Inadequate controls – significant improvement required	3	Non-compliant – moderate impact on customers or third parties

D	No contr	ols evident	4	Non-compliant – major impact on customers or third parties
N/	P Not perfo was not	ormed – A controls rating required	N/R	Not rated – No activity took place during the audit period

**Table 5** at section 3 of this report provides further detail on the control adequacy and compliance rating scales. The above rating scale is defined by the Guidelines.

Audit	Co	ntrol ade	quacy rati	ing	<b>NP</b> <sup>1</sup>	Total
Priority	Α	В	С	D	NP	Total
Priority 1	1	-	-	-	-	1
Priority 2	1	3	-	-	-	4
Priority 3	-	-	-	-	-	-
Priority 4	31	-	1	-	-	32
Priority 5	18	2	-	-	1	21
Total:	51	5	1	-	1	58

Table 2: Summary of findings by review priority and control adequacy

Table 3:	Summarv	of find	linas by	/ review	priority	and	compliance	rating
Tuble 51	Summary		ings b,	I CVICIV	prioricy	ana	compliance	racing

Audit		Complian	ce rating			Total
Priority	1	2	3	4	NR	Total
Priority 1	1	-	-	-	-	1
Priority 2	1	3	-	-	-	4
Priority 3	-	-	-	-	-	-
Priority 4	31	-	1	-	-	32
Priority 5	18	2	-	-	1	21
Total:	51	6	-	-	1	58

Note that, in accordance with the Guidelines:

- Obligations assessed as being "not applicable" to AETRH's operations have not been included within this report
- A control rating is only provided for those obligations with a Priority 1, 2, or 3 rating, where an obligation is assessed as non-compliant, or where a control improvement opportunity is identified.

Specific assessments for each criterion are summarised at **Table 7** in section 3 "Summary of ratings" of this report. Detailed findings, including relevant observations, recommendations and action plans are located in section 4 "Detailed findings, recommendations and action plans" of this report.

## 2.3 AETRH's response to previous review recommendations

This review considered AETRH's progress in completing the action plans detailed in the 2016 AMS report.

Based on our examination of relevant documents, discussion with staff and consideration of the results of this review's testing against the criteria, we determined that the four action plans from the 2016 AMS Review were partially completed and remain valid. The remaining elements from the 2016 findings requiring action have been included in and superseded by Action Plan 1/2019. Further recommendations were provided directly to AETRH.

<sup>&</sup>lt;sup>1</sup> Refers to the obligations for which a control assessment was not required to be performed (obligations with an audit priority of 4 or 5 and a compliance rating of 1, or which were not rateable).

Refer to section 5 of this report for further detail.

## 2.4 Recommendations and action plans

AMS Key Process and Effectiveness Criteria	Adequacy rating	Issue 1/2019
<b>Asset planning</b> 1.1 Asset Management Plan covers key requirements 1.9 Plans are regularly reviewed and updated	Requires significant improvement (C) Performance rating	<ul> <li>The AMP does not include the following mandatory elements of an effective AMP:</li> <li>Contingency arrangements</li> <li>Future demand and forecast (demand drivers highlighted)</li> </ul>
<b>Review of AMS</b> 12.1 A review process is in place to ensure that the asset management plan and the asset management system described therein are kept current	Corrective action required (3)	<ul> <li>Arrangements for review and update of the AMP.</li> <li>The Newman AMP for FY2019 - FY2023 was last reviewed on 2 July 2018, is still in a draft iteration with the following sections remaining to be completed:</li> <li>4.1.2 Basis of Operation and Maintenance Program - Asset Strategy</li> <li>4.1.3 Basis of Operation and Maintenance Program - Risk and Opportunities</li> <li>5.1 Key Assets</li> <li>5.2 Historical Asset Performance</li> </ul>
<ul> <li>Recommendation 1/2019</li> <li>Alinta should expand the AMP to</li> <li>1. The following elements: <ul> <li>a) Contingency arrangeme</li> <li>b) Future demand and fore</li> <li>c) Arrangements for review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP (Section 12)</li> <li>d) Ideally the AMP would review the AMP which are currently in a draft</li> </ul></li></ul>	nts (Section 9) ecast (Section 10). v and update of eference the 12 set management sed in the below y incomplete: a and Maintenance y and Maintenance ortunities ormance ns have been se and approve the	<ul> <li>Action Plan 1/2019</li> <li>Alinta will:</li> <ol> <li>Consider updating the AMP to reflect the 12 key processes in the asset management effectiveness criteria by referencing:</li> <li>a) Contingency arrangements (Section 9)</li> <li>b) Future demand and forecast (Section 10).</li> <li>c) Arrangements for review and update of the AMP (Section 12)</li> </ol> <li>Complete the following sections in the AMP which are currently not finalised: <ul> <li>a) 4.1.2 Basis of Operation and Maintenance Program - Asset Strategy</li> <li>b) 4.1.3 Basis of Operation and Maintenance Program - Risk and Opportunities</li> <li>c) 5.1 Key Assets</li> <li>d) 5.2. Historical Asset Performance</li> </ul> </li> <li>Endorse and approve the finalised iteration of the AMP.</li> <li>Responsible Person: <ul> <li>Head of Operations</li> <li>Target Date:</li> </ul> </li> </ul>

## 2.5 Scope and objectives

The objective of the review was to independently examine the effectiveness and performance of the AMS established for assets subject to AETRH's Licence during the review period.

In accordance with the Guidelines, the review considered the effectiveness of AETRH's existing control procedures within the following 12 key processes in the asset management life-cycle.

Table 4 – AMS key processes and effectiveness criteria

#	Key processes	Effectiveness criteria
1	Asset planning	1. Asset management plan covers the processes in this table
		2. Planning processes and objectives reflect the needs of all stakeholders and are integrated with business planning
		3. Service levels are defined in the asset management plan
		4. Non-asset options (e.g. demand management) are considered
		5. Lifecycle costs of owning and operating assets are assessed
		6. Funding options are evaluated
		7. Costs are justified and cost drivers identified
		8. Likelihood and consequences of asset failure are predicted
		9. Asset management plan is regularly reviewed and updated.
2	Asset creation and acquisition	<ol> <li>Full project evaluations are undertaken for new assets, including comparative assessment of non-asset options</li> </ol>
		2. Evaluations include all life-cycle costs
		3. Projects reflect sound engineering and business decisions
		4. Commissioning tests are documented and completed
		<ol> <li>Ongoing legal/environmental/safety obligations of the asset owner are assigned and understood.</li> </ol>
3	Asset disposal	<ol> <li>Under-utilised and under-performing assets are identified as part of a regular systematic review process</li> </ol>
		<ol> <li>The reasons for under-utilisation or poor performance are critically examined and corrective action or disposal undertaken</li> </ol>
		3. Disposal alternatives are evaluated
		4. There is a replacement strategy for assets.
4	Environmental analysis (all	1. Opportunities and threats in the asset management system environment are assessed
	external factors that affect the	<ol> <li>Performance standards (availability of service, capacity, continuity, emergency response, etc.) are measured and achieved</li> </ol>
	system)	3. Compliance with statutory and regulatory requirements
		4. Service standard (customer service levels etc) are measured and achieved.
5	Asset operations	1. Operational policies and procedures are documented and linked to service levels required
		2. Risk management is applied to prioritise operations tasks
		<ol> <li>Assets are documented in an asset register, including asset type, location, material, plans of components, and an assessment of assets' physical/structural condition</li> </ol>
		4. Accounting data is documented for assets
		5. Operational costs are measured and monitored
		<ol> <li>Staff resources are adequate and staff receive training commensurate with their responsibilities.</li> </ol>

#	Key processes	Effectiveness criteria
6	Asset maintenance	1. Maintenance policies and procedures are documented and linked to service levels required
		2. Regular inspections are undertaken of asset performance and condition
		<ol> <li>Maintenance plans (emergency, corrective and preventative) are documented and completed on schedule</li> </ol>
		4. Failures are analysed and operational/maintenance plans adjusted where necessary
		5. Risk management is applied to prioritise maintenance tasks
		6. Maintenance costs are measured and monitored.
7	Asset	1. Adequate system documentation for users and IT operators
	management information	<ol> <li>Input controls include appropriate verification and validation of data entered into the system</li> </ol>
	system	3. Security access controls appear adequate, such as passwords
		4. Physical security access controls appear adequate
		5. Data back-up procedures appear adequate and backups are tested
		6. Computations for licensee performance reporting are accurate
		<ol> <li>Management reports appear adequate for the licensee to monitor licence obligations</li> </ol>
		8. Adequate measures to protect asset management data from unauthorised access or theft by persons outside the organisation.
8	Risk management	1. Risk management policies and procedures exist and are being applied to minimise internal and external risks
		<ol> <li>Risks are documented in a risk register and treatment plans are implemented and monitored</li> </ol>
		3. The probability and consequences of asset failure are regularly assessed.
9	Contingency planning	1. Contingency plans are documented, understood and tested to confirm their operability and to cover higher risks.
10	Financial planning	1. The financial plan states the financial objectives and identifies strategies and actions to achieve the objectives
		2. The financial plan identifies the source of funds for capital expenditure and recurrent costs
		3. The financial plan provides projections of operating statements (profit and loss) and statement of financial position (balance sheets)
		4. The financial plan provide firm predictions on income for the next five years and reasonable predictions beyond this period
		5. The financial plan provides for the operations and maintenance, administration and capital expenditure requirements of the services
		6. Large variances in actual/budget income and expenses are identified and corrective action taken where necessary.
11	Capital expenditure	<ol> <li>There is a capital expenditure plan covering works to be undertaken, actions proposed, responsibilities and dates</li> </ol>
	planning	<ol> <li>The capital expenditure plan provides reasons for capital expenditure and timing of expenditure</li> </ol>
		3. The capital expenditure plan is consistent with the asset life and condition identified in the asset management plan
		4. There is an adequate process to ensure that the capital expenditure plan is regularly updated and implemented.
12	Review of AMS	1. A review process is in place to ensure that the asset management plan and the asset management system described therein are kept current
		<ol> <li>Independent reviews (e.g. internal audit) are performed of the asset management system.</li> </ol>

Each key process and effectiveness criterion is applicable to Alinta's Licence and as such was individually considered as part of the review. The Review Plan, set out at Appendix A, details the risk assessments made for and review priority assigned to each key process and effectiveness criterion.

## 2.6 Approach

Our approach for this review involved the following activities, which were undertaken during August to October 2019:

- Utilising the Guidelines, development of a risk assessment, which involved discussions with key staff and review of documents to undertake a preliminary assessment of relevant controls
- Development of a Review Plan (see **Appendix A**) for approval by the ERA
- Correspondence and interviews with Alinta staff to gain an understanding of process controls in place (see **Appendix B** for staff involved)
- Visited the power station operations with a focus on understanding the generation and transmission network assets, their function, normal mode of operation, age and an assessment of the facilities against the AMS review criteria
- Review of documents, processes and controls to assess the overall effectiveness of Alinta's AMS (see **Appendix B** for reference listing)
- Consideration of the resourcing applied to maintaining those controls and processes
- Reporting of findings to Alinta for review and response.

# 3 Summary of ratings

In accordance with the Guidelines, the assessment of both the process and policy definition adequacy rating (refer to **Table 2**) and the performance rating (refer to **Table 3**) for each of the key AMS processes is performed using the below ratings.

For the avoidance of doubt, these ratings do not provide reasonable assurance.

#### Table 5: Asset management process and policy definition adequacy ratings

Rating	Description	Criteria
A	Adequately defined	<ul> <li>Processes and policies are documented</li> <li>Processes and policies adequately document the required performance of the assets</li> <li>Processes and policies are subject to regular reviews, and updated where necessary</li> <li>The asset management information system(s) are adequate in relation to the assets that are being managed.</li> </ul>
В	Requires some improvement	<ul> <li>Process and policy documentation requires improvement</li> <li>Processes and policies do not adequately document the required performance of the assets</li> <li>Reviews of processes and policies are not conducted regularly enough</li> <li>The asset management information system(s) require minor improvements (taking into consideration the assets that are being managed).</li> </ul>
с	Requires significant improvement	<ul> <li>Process and policy documentation is incomplete or requires significant improvement</li> <li>Processes and policies do not document the required performance of the assets</li> <li>Processes and policies are significantly out of date</li> <li>The asset management information system(s) require significant improvements (taking into consideration the assets that are being managed).</li> </ul>
D	Inadequate	<ul> <li>Processes and policies are not documented</li> <li>The asset management information system(s) is not fit for purpose (taking into consideration the assets that are being managed).</li> </ul>

### Table 6: Asset management performance ratings

Rating	Description	Criteria
1	Performing effectively	<ul> <li>The performance of the process meets or exceeds the required levels of performance</li> <li>Process effectiveness is regularly assessed and corrective action taken where necessary.</li> </ul>
2	Opportunity for improvement	<ul> <li>The performance of the process requires some improvement to meet the required level</li> <li>Process effectiveness reviews are not performed regularly enough</li> <li>Process improvement opportunities are not actioned.</li> </ul>
3	Corrective action required	<ul> <li>The performance of the process requires significant improvement to meet the required level</li> <li>Process effectiveness reviews are performed irregularly, or not at all</li> <li>Process improvement opportunities are not actioned.</li> </ul>
4	Serious action required	<ul> <li>Process is not performed, or the performance is so poor that the process is considered to be ineffective.</li> </ul>

This report provides:

- A breakdown of each function of the AMS into sub-components as described in the Guidelines. This approach is taken to enable a more thorough review of key processes where individual components within a larger process can be of greater risk to the business therefore requiring different review treatment
- A summary of the ratings applied by the review (**Table 7**) for each of:
  - Asset management process and policy definition adequacy (definition adequacy rating)
  - Asset management performance (**performance rating**).
- Detailed findings, including relevant observations, recommendations and action plans (Section 4). Descriptions of the effectiveness criteria can be found in section 4 and the Review Plan at Appendix A.

#### Table 7: AMS effectiveness summary

			Rat	ings
Ref	Effectiveness criteria	Review Priority	Definition Adequacy	Performanc e
1. /	Asset planning		В	2
1.1	Asset management plan covers the processes in this table	Priority 4	С	3
1.2	Planning processes and objectives reflect the needs of all stakeholders and are integrated with business planning	Priority 5	А	1
1.3	Service levels are defined in the asset management plan	Priority 5	А	1
1.4	Non-asset options (e.g. demand management) are considered	Priority 5	А	1
1.5	Lifecycle costs of owning and operating assets are assessed	Priority 4	А	1
1.6	Funding options are evaluated	Priority 5	А	1
1.7	Costs are justified and cost drivers identified	Priority 4	А	1
1.8	Likelihood and consequences of asset failure are predicted	Priority 4	А	1
1.9	Asset management plan is regularly reviewed and updated	Priority 5	В	2
2. /	2. Asset creation and acquisition			1
2.1	Full project evaluations are undertaken for new assets, including comparative assessment of non-asset options	Priority 4	А	1
2.2	Evaluations include all life-cycle costs	Priority 4	А	1
2.3	Projects reflect sound engineering and business decisions	Priority 4	А	1
2.4	Commissioning tests are documented and completed	Priority 4	А	1
2.5	Ongoing legal/environmental/ safety obligations of the asset owner are assigned and understood	Priority 2	А	1
3. /	Asset disposal		A	1
3.1	Under-utilised and under-performing assets are identified as part of a regular systematic review process	Priority 5	А	1
3.2	The reasons for under-utilisation or poor performance are critically examined and corrective action or disposal undertaken	Priority 5	A	1
3.3	Disposal alternatives are evaluated	Priority 5	А	1
3.4	There is a replacement strategy for assets	Priority 4	А	1
4. E	Environmental analysis		A	1
4.1	Opportunities and threats in the asset management system environment are assessed	Priority 4	А	1

			Rati	ings
Ref	Effectiveness criteria	Review Priority	Definition Adequacy	Performanc e
4.2	Performance standards (availability of service, capacity, continuity, emergency response, etc.) are measured and achieved	Priority 4	А	1
4.3	Compliance with statutory and regulatory requirements	Priority 4	А	1
4.4	Service standard (customer service levels etc) are measured and achieved	Priority 4	А	1
5. A	sset operations		Α	1
5.1	Operational policies and procedures are documented and linked to service levels required	Priority 4	А	1
5.2	Risk management is applied to prioritise operations tasks	Priority 4	А	1
5.3	Assets are documented in an asset Register including asset type, location, material, plans of components, an assessment of assets' physical/structural condition and accounting data	Priority 4	A	1
5.4	Accounting data is documented for assets	Priority 4	А	1
5.5	Operational costs are measured and monitored	Priority 4	А	1
5.6	Staff resources are adequate and staff receive training commensurate with their responsibilities	Priority 4	А	1
6. A	sset maintenance		Α	1
6.1	Maintenance policies and procedures are documented and linked to service levels required	Priority 4	А	1
6.2	Regular inspections are undertaken of asset performance and condition	Priority 4	А	1
6.3	Maintenance plans (emergency, corrective and preventative) are documented and completed on schedule	Priority 4	А	1
6.4	Failures are analysed and operational/maintenance plans adjusted where necessary	Priority 4	А	1
6.5	Risk management is applied to prioritise maintenance tasks	Priority 1	А	1
6.6	Maintenance costs are measured and monitored	Priority 4	А	1
7. A	sset management information system		Α	1
7.1	Adequate system documentation for users and IT operators	Priority 5	А	1
7.2	Input controls include appropriate verification and validation of data entered into the system	Priority 4	А	1
7.3	Security access controls appear adequate, such as passwords	Priority 5	А	1
7.4	Physical security access controls appear adequate	Priority 5	А	1
7.5	Data backup procedures appear adequate	Priority 4	А	1
7.6	Computations for licensee performance reporting are accurate	Priority 5	NP	NR
7.7	Management reports appear adequate for the licensee to monitor licence obligations	Priority 5	А	1
7.8	Adequate measures to protect asset management data from unauthorised access or theft by persons outside the organisation	Priority 5	A	1
8. R	isk management		В	2
8.1	Risk management policies and procedures exist and are being applied to minimise internal and external risks	Priority 2	В	2

			Rat	ings
Ref	Effectiveness criteria	Review Priority	Definition Adequacy	Performanc e
8.2	Risks are documented in a risk register and treatment plans are implemented and monitored	Priority 2	В	2
8.3	The probability and consequences of asset failure are regularly assessed	Priority 4	А	1
9. C	Contingency planning		В	2
9.1	Contingency plans are documented, understood and tested to confirm their operability and to cover higher risks	Priority 2	В	2
10. F	inancial planning		Α	1
10.1	The financial plan states the financial objectives and identifies strategies and actions to achieve the objectives	Priority 4	А	1
10.2	The financial plan identifies the source of funds for capital expenditure and recurrent costs	Priority 5	А	1
10.3	The financial plan provides projections of operating statements (profit and loss) and statement of financial position (balance sheets)	Priority 5	A	1
10.4	The financial plan provides firm predictions on income for the next five years and reasonable predictions beyond this period	Priority 5	А	1
10.5	The financial plan provides for the operations and maintenance, administration and capital expenditure requirements of the services	Priority 4	A	1
10.6	Large variances in actual/budget income and expenses are identified and corrective action taken where necessary	Priority 4	A	1
11. C	Capital expenditure planning		Α	1
11.1	There is a capital expenditure plan covering works to be undertaken, actions proposed, responsibilities and dates	Priority 4	А	1
11.2	The capital expenditure plan provides reasons for capital expenditure and timing of expenditure	Priority 5	А	1
11.3	The capital expenditure plan is consistent with the asset life and condition identified in the asset management plan	Priority 4	А	1
11.4	There is an adequate process to ensure that the capital expenditure plan is regularly updated and implemented	Priority 5	А	1
12. R	12. Review of AMS			2
12.1	A review process is in place to ensure that the asset management plan and the asset management system described therein are kept current	Priority 5	В	2
12.2	Independent reviews (e.g. internal audit) are performed of the asset management system	Priority 5	А	1

# 4 Detailed findings, recommendations and action plans

The following tables contain:

- *Findings:* the reviewer's understanding of the process and any issues that have been identified during the review
- *Recommendations (where applicable):* recommendations for improvement or enhancement of the process or control
- Action plans (where applicable): Alinta's formal response to review recommendations, providing details of action to be implemented to address the specific issue raised by the review.

## 4.1 Asset Planning

**Key process:** Asset planning strategies are focused on meeting customer needs in the most effective and efficient manner (delivering the right service at the right price)

**Expected outcome:** Integration of asset strategies into operational or business plans will establish a framework for existing and new assets to be effectively utilised and their service potential optimised

#### **Overall Adequacy/Performance rating:** Requires some Improvement (B) / Opportunity for Improvement (2)

Effectiveness Criteria	Find	dings
1.1 Asset management plan covers the processes in this table	plans (overview of ERA auditing improvements and safet performance monitoring, and legislative and other compl However, we found the AMP:	hin the Newman operation and Alinta Energy's strategic f the power generation assets within Alinta's Newman scope and purpose, description of operations and assets, hents), Whole of Life (WOL) management plan, improvement ty management system), financial forecasts, service levels, liance obligations. hideline, including contingency arrangements, future demand ngements for review and update of the AMP. e completed: Asset Strategy (4.1.2)
	Adequacy Rating: Requires significant improvement (C)	Performance Rating: Corrective action required (3)
	<ul> <li>Recommendation 1/2019</li> <li>Alinta should finalise the AMP by including: <ol> <li>The following elements:</li> <li>Contingency arrangements (Section 9)</li> <li>Future demand and forecast (Section 10).</li> <li>Arrangements for review and update of the AMP (Section 12)</li> </ol> </li> <li>Ideally the AMP would reference the 12 key processes in the asset management lifecycle Guidance on processes utilised in the below sections, which are currently incomplete:</li> </ul>	<ul> <li>Action Plan 1/2019</li> <li>Alinta will:</li> <li>1. Consider updating the AMP to reflect the 12 key processes in the asset management effectiveness criteria by referencing: <ul> <li>a) Contingency arrangements (Section 9)</li> <li>b) Future demand and forecast (Section 10).</li> <li>c) Arrangements for review and update of the AMP (Section 12)</li> </ul> </li> <li>2. Complete the following sections in the AMP which are currently not finalised:</li> </ul>

Effectiveness Criteria Findings		
	<ul> <li>a) 4.1.2 Basis of Operation and Maintenance Program <ul> <li>Asset Strategy</li> </ul> </li> <li>b) 4.1.3 Basis of Operation and Maintenance Program <ul> <li>Risk and Opportunities</li> <li>c) 5.1 Key Assets</li> <li>d) 5.2. Historical Asset Performance</li> </ul> </li> <li>Once the above recommendations have been completed, <ul> <li>Alinta should endorse and approve the AMP which is currently in a draft iteration.</li> </ul> </li> </ul>	<ul> <li>a) 4.1.2 Basis of Operation and Maintenance Program <ul> <li>Asset Strategy</li> </ul> </li> <li>b) 4.1.3 Basis of Operation and Maintenance Program <ul> <li>Risk and Opportunities</li> <li>c) 5.1 Key Assets</li> <li>d) 5.2. Historical Asset Performance</li> </ul> </li> <li>3. Endorse and approve the finalised iteration of the AMP.</li> <li>Responsible Person: <ul> <li>Head of Operations</li> <li>Target Date:</li> <li>30 June 2020</li> </ul> </li> </ul>
1.2 Planning processes and objectives reflect the needs of all stakeholders and are integrated with business planning	1.2 Planning processes and objectives reflect the needs of all stakeholders and are integrated with business       Through discussions with the Head of Operations and consideration of Alinta's business planning processes, we determined Alinta's business planning model accommodates its operation and maintenance of the Newman power standard transmission assets considering its contractual arrangements and regulatory requirements.         From a business planning perspective, we determined that Alinta has established asset management processes and	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)
1.3 Service levels are defined in the asset management plan	<ul> <li>Through discussions with the Head of Operations and examination of Alinta's AMP and contractual documentation, we determined that the plant's required service levels have been:</li> <li>Summarised in the draft AMP, which are updated on a periodic basis to facilitate any changes of those service levels. The AMP references relevant operational information for each key item of equipment</li> <li>Defined in Alinta's maintenance standards (e.g. High Voltage Asset Maintenance Standard) maintained on SharePoint and integrated into the maintenance management system</li> <li>Programmed into the Ellipse asset management work order system to track routine maintenance requirements across all asset components.</li> </ul>	

Effectiveness Criteria	Find	lings	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
1.4 Non-asset options (e.g. demand management) are considered	Through discussions with the Head of Operations we determined that Alinta had considered non-asset options for the Newman Power Station, however those options are not relevant in the current circumstances where Alinta is contractually obliged to generate power to meet its customers' requirements.		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
1.5 Lifecycle costs of owning and operating assets are assessed	<ul> <li>Through discussions with the Head of Operations and examination of Alinta's draft AMP, SAMP, and Project Management Framework, we determined that assessment of lifecycle costs of owning and operating the assets is undertaken by means of Alinta's AMP that considers each major equipment component and provides specific details, including:</li> <li>Operating and maintaining philosophy</li> <li>Key life cycle issues and how they are addressed</li> <li>Life cycle plan and critical outages</li> <li>Performance improvement opportunities</li> <li>Critical reinvestments</li> <li>Retirement/disposal consideration at end of plant life</li> </ul>		
	Capex and Opex forecast for a five-year period.     Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
1.6 Funding options are evaluated	<ul> <li>Through discussions with the Head of Operations and examination of Alinta's AMP and contractual documentation, we determined that:</li> <li>Day-to-day operating expenses are funded from operating cash flows</li> <li>Funding options are considered and evaluated by means of the Request for Commitment on the AMP Expenditure Project Delivery Site (integrated within SharePoint), which details: <ul> <li>Expenditure description relative to plan (i.e. budget vs unbudgeted)</li> <li>Expenditure type (Opex / Capex).</li> </ul> </li> <li>A Delegated Financial Authority matrix and automated workflow system within the 'Request for Commitment' approval process (SharePoint) helps drive fund requests above specified levels are required to be authorised by the appropriate level of management.</li> </ul>		
	Adequacy Rating: Adequately defined (A)	<b>Performance Rating:</b> Performing effectively (1)	
1.7 Costs are justified and cost drivers identified	<ul> <li>Through discussions with the Head of Operations and consideration of Alinta's AMP strategy and model, we determined:</li> <li>The AMP includes a detailed life cycle plan that identifies and assesses all life cycle costs and cost drivers associated with the power station</li> <li>Power station assets are managed using Ellipse, which records maintenance tasks and associated costs. Financial reporting is generated from Ellipse with budget vs actual analysis performed quarterly.</li> </ul>		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	

Effectiveness Criteria	Findings		
1.8 Likelihood and consequences of asset failure are predicted	Through discussion with the Regulatory Compliance Manager and Head of Operations and examination of Alinta's AMP and relevant supporting documentation, we determined the SAMP and AMP are tools used for predicting the likelihood and consequences of asset failure. Specifically, we observed that:		
	The AMP considers:		
	<ul> <li>Previous historic maintenance issues of assets, and p as well as the risk mitigation actions</li> </ul>	rovides details of the operational and maintenance strategy,	
	<ul> <li>Primary and specific asset risk analysis, with risk mitigation action. This is supported by risk management system Incontrol, which contains risk treatment plans.</li> </ul>		
	Alinta's operations and maintenance staff operate the pla maintenance on a scheduled basis controlled by work ord		
	<ul> <li>Condition monitoring techniques are employed on a frequent basis to identify defects, including oil analysis, vibration analysis, and radiography and thermography to identify any surface or internal defects</li> </ul>		
	<ul> <li>During scheduled outages (e.g. long-term shutdowns), main components of the facility's plant are inspected for defects by site staff and external contractors.</li> </ul>		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
1.9 Asset management plan is regularly reviewed and updated	Through discussions with the Head of Operations, Plant Mana AMP and relevant supporting asset planning documentation,	5	
	• The Newman Power Station AMP has been reviewed and i	revised, but is still in draft format	
	<ul> <li>Alinta has a SAMP in place that was drafted in March 201 FY2020. This will then be updated for FY2021 – FY2025</li> </ul>	5. The SAMP covers a five-year period, from FY2016 -	
	• The detailed maintenance program is maintained as a forward-looking document to avoid unplanned outages and is revised in accordance with continuous improvement principles, with a view to maximising availability and aligning outages to coincide with off-peak and off-season periods		
	<ul> <li>Operational and capital expenditure budgets are tracked on a monthly and quarterly basis with any variances analysed to determine impact on the scheduled maintenance and outage plans.</li> </ul>		
	In response to recommendation 1/2016, Alinta has updated the draft AMP to include known and significant risks relating to the key assets and legal and compliance requirements. However, Alinta is yet to include contingency planning requirements into the document.		
	Refer to recommendation and action plan 1/2019.		
	Adequacy Rating: Requires some improvement (B)	Performance Rating: Opportunity for improvement (2)	

## 4.2 Asset Creation and acquisition

**Key process:** Asset creation/acquisition means the provision or improvement of an asset where the outlay can be expected to provide benefits beyond the year of outlay

**Expected outcome:** A more economic, efficient, and cost-effective asset acquisition framework, which will reduce demand for new assets, lower service costs, and improve service delivery.

### **Overall Adequacy/Performance rating:** Adequately defined (A) / Performing effectively (1)

Effectiveness Criteria	Find	ings	
2.1 Full project evaluations are undertaken for new assets, including comparative assessment of non-asset solutions	<ul> <li>with the Head of Operations, we determined Alinta has develor requirement for project evaluations to be undertaken prior to As part of the project evaluation process, Alinta requires the f</li> <li>A full business case, which provides approval criteria for in requirements, current state assessment, asset/non-asset</li> <li>Financial modelling in support of the business case. The n assumptions to assess the cost associated with the overal years of plant life</li> <li>Consideration of non-asset options where applicable.</li> </ul>	of the Project Management Framework, Procurement Standards, other relevant documents and discussion d of Operations, we determined Alinta has developed expenditure approval procedures, which outline the for project evaluations to be undertaken prior to seeking funds approval. e project evaluation process, Alinta requires the following to be completed: iness case, which provides approval criteria for instigating new projects including, financial and capital ents, current state assessment, asset/non-asset alternatives, and timeline modelling in support of the business case. The modelling utilises a standard set of high-level economic cons to assess the cost associated with the overall plant life and generate cost predictions over the 20-30 plant life ation of non-asset options where applicable. and examined an approved Request for Commitment ( <b>RFC</b> ) for warehouse and control room roof repairs ace during the period subject to review, and included: case ial sign-off impact analysis (costings and required Capex)	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
2.2 Evaluations include all life- cycle costs	Through discussions with the Head of Operations and an exam associated forms and templates, we determined Alinta has the owning and operating assets:	discussions with the Head of Operations and an examination of the procedures for expenditure approval and d forms and templates, we determined Alinta has the following process in place to assess lifecycle costs of nd operating assets: cle costs of owning and operating assets is detailed in the AMP and considers each major piece of equipment rovides specific details, including: perating and maintenance philosophy ey lifecycle issues and how they are addressed ifecycle plan and critical outages erformance improvement opportunities ritical reinvestments	

Effectiveness Criteria	eness Criteria Findings		
	<ul> <li>Financial modelling is also utilised as part of budgeting and forecasting process to assess the cost associated with the overall plant life and forecast expenditure up to FY 2040</li> <li>Project evaluations provide for estimates of the amount of investment required as well as identifying the source of funds.</li> <li>We obtained and examined an approved RFC from the period subject to review, which contained project documentation for the warehouse and control room roof repairs.</li> <li>Adequacy Rating: Adequately defined (A)</li> <li>Performance Rating: Performing effectively (1)</li> </ul>		
2.3 Projects reflect sound engineering and business decisions	Through discussions with the Head of Operations and contrac forms and templates, we determined Alinta has the following merits of projects:		
	• Project evaluations are performed with the input from both engineering and finance personnel and with evaluation results detailed and approved by relevant department stakeholders to ensure all engineering, finance, environmental, health and safety aspects are addressed		
	<ul> <li>Project modelling tools are applied to project evaluations,</li> </ul>	considering relevant economic measures	
	• Commercial sign off is required, which incorporates the above considerations and addresses any potential contract risks when engaging external parties.		
	We obtained and examined an approved RFC from the period subject to review, which contained project documentation for the warehouse and control room roof repairs.		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
2.4 Commissioning tests are documented and completed	<ul> <li>Through discussions with the Head of Operations and Plant M Project Management Framework, we observed commissioning SharePoint. Where Alinta engages external contractors to per</li> <li>Testing reports are prepared by the site engineering team</li> <li>Handover to operations only occurs when the requirement by the Project Manager. The Project Manager must then operations.</li> </ul>	tests form part of the project lifecycle, which is recorded on form commissioning tests: an and stored on SharePoint ts for practical completion have been met and are approved	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
<ul> <li>2.5 Ongoing legal/environmental/safety obligations of the asset owner are assigned and understood</li> <li>Processes to identify legal, environmental and safety obligations relating to its power station a network assets</li> <li>Applied the Alinta Energy (group-wide) Occupational Health and Safety Management Framewor Management Framework to its Newman and Roy Hill Power Station and transmission facilities</li> <li>Assigned responsibilities to staff on site and in the Perth office for managing Alinta's environmental obligations in accordance with OHS and Environmental management plans</li> </ul>		urpose of its ongoing asset management obligations, Alinta gations relating to its power station and transmission Ith and Safety Management Framework and Environmental er Station and transmission facilities office for managing Alinta's environmental and safety	

Effectiveness Criteria	Findings		
	<ul> <li>Implemented an organised document management system within SharePoint for housing regulatory obligations such as licences, related management plans and monitoring/compliance reports</li> <li>The Environmental Management Framework references the Alinta Energy Safety and Sustainability Committee (AESSC) and the Corporate Risk and Assurance Group are assigned responsibilities for monitoring any updates or changes to regulatory obligations and reporting requirements.</li> </ul>		
	We sighted evidence of:		
	<ul> <li>Alinta's identification, assessment and treatment of risks relating to its legal, environmental and safety obligations within the AMP</li> <li>Site skills and training matrix, which contains the relevant safety training staff need to complete</li> <li>Actions and reports prepared in accordance with the Environmental Management Plan.</li> <li>Adequacy Rating: Adequately defined (A)</li> <li>Performance Rating: Performing effectively (1)</li> </ul>		

## 4.3 Asset disposal

**Key process:** Effective asset disposal frameworks incorporate consideration of alternatives for the disposal of surplus, obsolete, under-performing or unserviceable assets. Alternatives are evaluated in cost-benefit terms.

**Expected outcome:** Effective management of the disposal process will minimise holdings of surplus and under-performing assets and will lower service costs. **Overall Adequacy/Performance rating:** Adequately defined (A) / Performing effectively (1)

Effectiveness Criteria	Findings		
3.1 Under-utilised and under- performing assets are identified as part of a regular systematic	fied documentation and walkthrough of the InControl risk management system for Newman, we determined Alinta has app		
review process	<ul> <li>The AMP considers each major item of equipment and provides specific details of the facility's operations and maintenance strategy, key life cycle issues and remedial plans</li> </ul>		
	<ul> <li>A detailed forward maintenance program in accordance with manufacturer's guidelines and expert experience is maintained for the plant that is reviewed daily</li> </ul>		
	The following review processes are in place:		
	<ul> <li>Condition monitoring techniques are employed on a frequent basis to identify defects and are stored in Ellipse including: Oil analysis, vibration analysis, and radiography and thermography to identify any surface or internal defects</li> </ul>		
	<ul> <li>During scheduled outages, main components of the facility's plant are inspected for defects by external consultants</li> </ul>		
	<ul> <li>The operational performance of the Newman facility is monitored through the Honeywell Experion system, with weekly and monthly performance dashboard reports presented to management for review, showing asset generational performance against benchmarked targets</li> </ul>		
	<ul> <li>Unexpected asset failures are logged in the InControl System which details:</li> </ul>		
	<ul> <li>Incident description</li> </ul>		
	<ul> <li>Relevant Workgroup responsible</li> </ul>		
<ul> <li>Incident Type (e.g. equipment, environmental etc.)</li> </ul>			
	<ul> <li>Incident Status.</li> </ul>		
	<ul> <li>Results of these assessments and inspections are included in the rolling five-year plans</li> </ul>		
	Adequacy Rating: Adequately defined (A)       Performance Rating: Performing effectively (1)		

Effectiveness Criteria	Find	ings	
3.2 The reasons for under- utilisation or poor performance are critically examined and	Through discussions with the Head of Operations and examin Alinta has applied the mechanisms at Asset Disposal (s.3.1) t performing assets by:		
corrective action or disposal undertaken	Undertaking root cause analyses of underutilisation or po Management System	or performance of power station assets in the InControl Risk	
	Applying a project evaluation approach as part of the cap justification of why the upgrade/purchase of equipment is		
	<ul> <li>Incorporating assessments into rolling five-year plans that detail the major capital projects planned for the coming financial year.</li> </ul>		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
3.3 Disposal alternatives are evaluated	Through discussions with the Head of Operations and examin processes require:		
	Consideration of alternatives for decommissioning, removal or storage of key plant     The AMD provide details of the major projects planned for each possible coming financial year including any		
	The AMP provide details of the major projects planned for each asset in the coming financial year, including any equipment replacement requirements		
	<ul> <li>Asset disposals to be performed in accordance with Project Management processes (including the Management of Change system process) and the AMP</li> </ul>		
	Spare parts are re-utilised or stored to be used again on	existing assets.	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
3.4 There is a replacement	Through discussions with the Head of Operations and consideration of Alinta's AMP and SAMP, we observed:		
strategy for assets	<ul> <li>The AMP considers each major item of equipment and provides specific details of the facility's of maintenance strategy, key life cycle issues and remedial plans</li> </ul>		
	Rolling five-year plans in the AMP provide details of the m year, including any equipment replacement requirements	najor projects planned for each asset in the coming financial	
	Adequacy Rating: Adequately defined (A)         Performance Rating: Performing effectively (1)		

## 4.4 Environmental analysis

**Key process:** Environmental analysis examines the asset system environment and assesses all external factors affecting the asset system.

**Expected outcome:** The AMS regularly assesses external opportunities and threats and takes corrective action to maintain performance requirements.

**Overall Adequacy/Performance rating:** Adequately defined (A) / Performing effectively (1)

Effectiveness Criteria	Findings		
4.1 Opportunities and threats in the asset management system environment are assessed	<ul> <li>Through discussion with the Head of Operations and consideration of relevant supporting documentation, we determined Alinta identifies and assesses opportunities and threats within its AMS through records of:</li> <li>Applicable legal and regulatory obligations are documented in the AMP under the Regulatory Compliance Summary</li> <li>Risks and threats to the asset's operations in the AMP</li> <li>Environmental and safety related incidents in its InControl Risk Management System.</li> </ul>		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
4.2 Performance standards (availability of service, capacity, continuity, emergency response, etc.) are measured and achieved	<ul> <li>Through discussion with the Head of Operations and supporting documentation, we determined that:</li> <li>The tracking of work orders and performance KPIs on site is controlled through Ellipse, which reports on the key performance aspects of the plant. The monthly reports include aspects such as availability and production losses, maintenance costs, Environmental Occupational Health and Safety (EOHS) incidents and Sulphur oxides (SOx) emission breaches. Any deviations from budget or contractual KPIs are highlighted and explained, where appropriate</li> <li>Alinta has emergency response processes in place in case of an environmental incident, with Site Managers being responsible for the investigation and analysis of the incident</li> <li>Alinta is required to report Nitrogen oxides (NOx) and Carbon Monoxide (CO) emissions quarterly. It must also provide NOx, CO and SOx emission sample readings annually. All non-continuous sampling and analysis is to be performed by a holder of a NATA accreditation.</li> </ul>		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
4.3 Compliance with statutory and regulatory requirements	<ul> <li>Through discussion with the Head of Operations and consideration of relevant supporting documentation, we determined that Alinta operates and monitors its operations in accordance with the following statutory and regulatory requirements:</li> <li>Newman Power Station AETRH Environmental Licence, which include NOx, CO and SOx emissions targets and requirements. Alinta is required to report NOx and CO emissions quarterly and annually. It must also provide an annual SOx emission sample reading</li> <li>All non-continuous sampling and analysis is to be performed by a holder of a NATA accreditation</li> <li>Alinta Energy's Environmental Management Framework accommodates Alinta's commitment to environmental protection</li> <li>Greenhouse gas emissions obligations under the National Greenhouse and Energy Reporting Act (NGER Act)</li> <li>The Occupational Safety and Health Act 1984 and supporting Regulations, enabled through Alinta Energy's groupwide health and safety management framework.</li> </ul>		
	Adequacy Rating: Adequately defined (A)       Performance Rating: Performing effectively (1)		

Effectiveness Criteria	Findings	
4.4 Service standard (customer service levels etc) are measured and achieved	Through discussion with the Head of Operations and consideration of the Purchase Power Agreement, we determined that Alinta's customer service levels and performance requirements are defined in the PPA. The service levels are monitored in the weekly and monthly performance reports that are provided to management. In relation to community obligations, Alinta operates and monitors its operations in accordance with 4.3 above.	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)

## 4.5 Asset operations

**Key process:** Operational functions relate to the day-to-day running of assets and directly affect service levels and costs.

**Expected outcome:** Operations plans adequately document the processes and knowledge of staff in the operation of assets so that service levels can be consistently achieved.

### **Overall Adequacy/Performance rating:** Adequately defined (A) / Performing effectively (1)

Effectiveness Criteria	Findings	
5.1 Operational policies and	Through discussion with the Head of Operations, inspection of relevant documentation and site visit, we determined that:	
procedures are documented and linked to service levels	<ul> <li>Operational policies and procedures are documented collectively through the AMP, the PPA, and the Power Generation Operational Plan</li> </ul>	
required	The service levels requirements are either defined explicitly (e.g. firm or non-firm purchase) or derived from these documents and documented in the AMP	
	Operational procedures and manuals are kept on site as	well as on the shared drive
	Reliability and maintenance requirements are also set up	o in the Operations FY20 Game Plan.
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)
5.2 Risk management is applied to prioritise operations tasks	• There is an established risk management framework and process i.e., prior to initiating changes in management of change, planned outages, as well as lower level (work order level) execution	
	<ul> <li>The risk management information is used to guide opera through management of change</li> </ul>	ational decisions e.g. dispatching, or any changes initiated
	• The Maintenance Work Process Manual document defines how the maintenance tasks are given priority ratings are assigned a priority from 1-5 based on a defined risk matrix	
	The timelines defined for maintenance task priorities are:	
	<ul> <li>Priority 1 (Extreme - Starts Immediately - Breaks Daily Schedule)</li> </ul>	
	<ul> <li>Priority 2 (High - Starts within 1 week - Breaks Weekly Schedule and Finishes within 2 weeks of start)</li> </ul>	
	<ul> <li>Priority 3 (Medium - Starts within 3 weeks - Finishes within 4 weeks of start)</li> </ul>	
	<ul> <li>Priority 4 (Low - Starts within 7 weeks - Finishes within 20 weeks of start)</li> </ul>	
	<ul> <li>Priority 5 (Planned Outage Activity included in the s</li> </ul>	cope of work).
	Adequacy Rating: Adequately defined (A)       Performance Rating: Performing effectively (1)	

Effectiveness Criteria	Findings	
5.3 Assets are documented in an asset Register including asset type, location, material, plans of components, an assessment of assets' physical/structural condition and accounting data	<ul> <li>has demonstrated:</li> <li>Assets are registered in fixed assets and equipment register in Ellipse, which details the asset type, location, ma and drawings</li> <li>Asset's physical and structural conditions are recorded in the plant condition dashboard</li> </ul>	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)
5.4 Accounting data is documented for assets	<ul> <li>Through discussion with the Head of Operations and the Finance Manager – Projects; and examination of a generated asset valuation report, we determined that Alinta has maintained an asset database that includes:</li> <li>Acquisition and retirement date</li> <li>Original, historic and current capital cost</li> <li>Depreciation rate</li> <li>The written down value after depreciation as at the start of the period</li> <li>Total depreciation in years previous</li> <li>Depreciation in the current year</li> <li>The closing written down value at the end of the year</li> <li>Book status describing if depreciation is capitalised or fully written down.</li> </ul>	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)
5.5 Operational costs are measured and monitored	Through discussion with the Head of Operations and the Plant Manager – Newman Power Station, examination of relevant documentation and site visit, we determined that Alinta has applied processes to measure and monitor operational costs, that include:         • Monthly profit and loss extracts provided to the Head of Operations, with analysis on total operational costs and variances between budgeted costs and actuals         • Costs are assigned to assets automatically based on allocated work orders, with external costs charged to associated cost centres         • Recording operational spending in Ellipse, the Computerised Maintenance Management System (CMMS).         Adequacy Rating: Adequately defined (A)	

Effectiveness Criteria	Findings	
5.6 Staff resources are adequate and staff receive	Through discussion with the Head of Operations and the Plant Manager – Newman Power Plant, examination of relevant documentation and site visit, we determined Alinta has demonstrated:	
training commensurate with	Staff have detailed job descriptions with defined responsibilities	
their responsibilities	Staff's mandatory training for work is registered in the skills/training matrix	
	Contractor training and competence is managed using Rapid Global system	
	<ul> <li>Alinta maintains records of all personnel and contractors inducted as appropriate to their role on site. For example, a maintenance contractor is required to undergo a more detailed induction than an escorted visitor to ensure they understand the procedures for working on site, such as work permit procedures</li> <li>The training officer plans the training together with the plant manager</li> </ul>	
There is a competency framework developed and implemented		ented
	Non-mandatory training is registered in staff personal development plans and KPIs	
	Staff resources are adequate for Alinta's current operational activities.	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)

## 4.6 Asset maintenance

**Key process:** Maintenance functions relate to the upkeep of assets and directly affect service levels and costs.

**Expected outcome:** Maintenance plans cover the scheduling and resourcing of the maintenance tasks so that work can be done on time and on cost. **Overall Adequacy/Performance rating:** Adequately defined (A) / Performing effectively (1)

Effectiveness Criteria	Findings	
6.1 Maintenance policies and procedures are documented	Through discussion with the Head of Operations and the Plant Manager – Newman Power Plant, inspection of relevant documentation and site visit, we determined:	
and linked to service levels required	<ul> <li>The maintenance policies and procedures are documented in the power station AMP, maintenance standards, work scheduling and ultimately in Ellipse. Ellipse is the main computerised Resource Planning tool used by Alinta. It consists of a database of information and a controlled front end that will manage Work Orders to specify what work must be done on a piece of equipment, how, who by and when</li> </ul>	
	The service levels requirements are either defined explicitly (e.g. firm or non-firm purchase) or derived from these documents	
	<ul> <li>The statutory work is dictated by the regulatory requirements</li> <li>Weekly and monthly performance reports have KPI's directly linked to service level requirements.</li> </ul>	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)
6.2 Regular inspections are undertaken of asset performance and condition	<ul> <li>Through discussion with the Head of Operations and the Plant Manager – Newman Power Plant, inspection of relevant documentation and site visit, we determined:</li> <li>Regular inspections are carried out at the plant in forms of daily rounds, statutory inspections and planned outages</li> <li>Any changes required on the inspections are implemented in the maintenance standards</li> <li>Condition-based inspection are carried out</li> <li>Regular reviews of plant/asset conditions are carried out and the plant condition dashboard updated.</li> </ul>	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)
<ul> <li>6.3 Maintenance plans</li> <li>(emergency, corrective and preventative) are documented and completed on schedule</li> <li>Through discussion with the Head of Operations and the Plant Manager – Newman Power Plant, inspection of documentation and site visit, we determined:</li> <li>Maintenance Plans for preventive tasks are well documented in the maintenance standards, AMP and Ellipse.</li> <li>Maintenance well work plan compliance is &gt;95%</li> <li>All work orders are registered in the Ellipse.</li> </ul>		cumented in the maintenance standards, AMP and Ellipse
	Adequacy Rating: Adequately defined (A)       Performance Rating: Performing effectively (1)	

Effectiveness Criteria	Findings		
6.4 Failures are analysed and operational/maintenance plans adjusted where necessary	<ul> <li>Through discussions with the Head of Operations and the Plant Manager – Newman Power Plant, inspection of documents received and site visits, we determined:</li> <li>Alinta has a function within InControl to record root cause analysis and key learnings on asset failures, such as corrective or emergency work</li> <li>An example of an abnormal incident file showed the process followed by staff to analyse the root cause of the malfunction, and how the maintenance and operation plans were adjusted to prevent any further malfunctions</li> <li>Alinta has demonstrated how results of failure analysis has been used to initiate changes on operation and maintenance, as well as engineering/asset renewal.</li> </ul>		
	Adequacy Rating: Adequately defined (A)Performance Rating: Performing effectively (1)		
6.5 Risk management is applied to prioritise maintenance tasks	Alinta has demonstrated how results of failure analysis has been used to initiate changes on operation and		

Effectiveness Criteria	Findings	
6.6 Maintenance costs are measured and monitored	Through discussion with the Head of Operations, inspection of relevant documentation and site visit, we determined that Alinta has demonstrated:	
	Operational spending is recorded in the Ellipse	
	The Head of Operations gets regular extracts from finance team on the Opex, Capex and EBITA	
	Project cost and standard costs (work orders) are accrued down to turbine and sublevels	
	Benchmarking is performed on maintenance costs.	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)

## 4.7 Asset Management Information System

Key process: An asset management information system is a combination of processes, data and software that support the asset management functions.

**Expected outcome:** The asset management information system provides authorised, complete and accurate information for the day-to-date running of the AMS. The focus of the review is the accuracy of performance information used by the licensee to monitor and report on service standards.

### **Overall Adequacy/Performance rating:** Adequately defined (A) / Performing effectively (1)

Effectiveness Criteria	F	indings
7.1 Adequate system documentation for users and IT operators	From our discussions with the Operations and Platforms Manager, and the Head of Operations, we determ	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)
7.2 Input controls include appropriate verification and validation of data entered into the system	<ul> <li>Through discussion with the Operations and Platforms Manager and consideration of Alinta's Cybersecurity Policy and Identity and Access Management Standard, we determined:</li> <li>Input controls are managed through built-in checks in Ellipse and aligned to Alinta's overall IT policy</li> <li>Processes are in place to verify and validate data entered into the system. This includes data reconciliation between old and new systems, checking data transferred between one system to another is accurate, timely and complete and validating data as close as possible to the point of origin, which includes the ability to trace data back to the source document</li> <li>Alinta's central IT helpdesk processes user requests, with user access is based on roles and positions. Access is granted only on receipt of a request form duly signed by relevant departmental head</li> <li>Ellipse has multiple points of security tied to user position. Employee IDs are attached to positions within a hierarchy within Ellipse</li> <li>Global profile security profiles are tied to positions</li> <li>Financial Delegations are tied to positions, are district specific, and requires approval from Alinta's finance function</li> <li>Within Ellipse, work functions can be restricted through menu visibility (i.e. programs will not appear without access)</li> <li>Site management approval is required for user profile updates</li> <li>A work order number is primary identifier in the Ellipse system that cannot be modified. Users have restricted access to the equipment register (limited to site personnel)</li> <li>District security settings requires a Newman login. Higher management have multiple level district access.</li> </ul>	

Effectiveness Criteria	Findings		
7.3 Security access controls appear adequate, such as	Through discussions with the Operations and Platforms Manager and consideration of Alinta's Cybersecurity Policy and Identity and Access Management Standard, we determined:		
passwords	• The process of granting and managing access is undertaken online through Alinta's IT helpdesk. Access requests are required to be approved by the relevant departmental head prior to being processed by IT		
	<ul> <li>End-users are granted the minimum level of access privileges required to perform their job function and to prevent segregation of duties conflicts</li> </ul>		
	<ul> <li>Password requirements are maintained to authenticate user access to the Alinta network and the Ellipse system, including a minimum number of characters and type of characters and restrictions on use of most recent passwords</li> </ul>		
	<ul> <li>An audit of management's email folders is undertaken periodically to ensure that only relevant personal assistants have access to those folders</li> </ul>		
	<ul> <li>Ellipse authenticates from the active employee directory and can track when users last logged in</li> <li>Remote user access requires RSA token authentication.</li> </ul>		
	We noted that the Cybersecurity policy outlines consequences for breach of policy and misuse of user privileges.		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
7.4 Physical security access controls appear adequate	Through discussions with the Operations and Platforms Manager and Head of Operations, consideration of the Identity and Access Management Standard and observations made during our visits to Alinta premises, we determined:		
	<ul> <li>Processes and procedures relating to the access of facilities and the physical protection of information assets and systems are in use, both at the head office as well as on site</li> </ul>		
	Site access is restricted by security fencing and swipe ca	ard entry to the premises	
	<ul> <li>Physical security for the head office location in Perth is maintained by the relevant building services company, including the provision of swipe card access to the building and restricted lift access.</li> </ul>		
	From discussions with Operations and Platforms Manager in the context of access to computer server rooms on site, we determined:		
	<ul> <li>Access swipe cards are used to restrict and record physical access to the computer server rooms. On employee termination, an exit checklist is completed whereby phones, cards, and laptops are required to be returned and access is revoked</li> </ul>		
	Visitors are required to sign in and out at reception and required to be accompanied by an Alinta employee		
	Access to the building is monitored by CCTV.		
	We also noted that general safety precautions appear to have been instigated to contain fire and other damaging events in computer rooms on site.		
	Adequacy Rating: Adequately defined (A)       Performance Rating: Performing effectively (1)		

Effectiveness Criteria	Findings		
7.5 Data backup procedures appear adequate and backups are tested	Through discussions with the Operations and Platforms Manager and consideration of the Business Continuity Management Standard, we determined procedures for managing data backup and data restore of servers have been established. We observed:		
	The main on-site data centre is in Adelaide		
	Nightly backups are performed through UNIX commands		
	<ul> <li>Regular backups are performed in accordance with defined schedules and media rotation rules. A full backup is performed every weekday and a weekly backup is performed each Friday</li> </ul>		
	Backup tapes are stored securely and protected from env	ironmental harm and unauthorised access	
	End of calendar year and end of financial year backups ar	e maintained indefinitely	
	Recall has been engaged to manage off-site backup tapes	s at a secure location	
	Testing of backups is performed on a quarterly basis with		
	We also noted that access to the backup tapes is limited to a	sub-set of IT Operations personnel and examined quarterly.	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
7.6 Computations related to licensee performance reporting are accurate	Alinta's asset management information system does not directly provide data used in any computation related to Alinta's licence performance reporting.		
	Adequacy Rating: Not performed	Performance Rating: Not rated	
7.7 Management reports appear adequate for the licensee to monitor licence obligations	Through discussions with the Operations and Platforms Manager, and consideration of relevant supporting documenta and management reporting procedures, we determined site management is undertaken by Alinta staff. We also obser the Experion and Ellipse systems can generate a variety of scheduled reports. We determined:		
	Management reports are generated to provide performance information on plant operations and routine and first line intervention maintenance in the form of a plant Condition Dashboard		
		are produced for management and contains relevant information on the volume of MW hours produced and the	
	The finance team also prepares a monthly management p	back to monitor costs from a financial perspective.	
	Adequacy Rating: Adequately defined (A) Performance Rating: Performing effectively (1)		

Effectiveness Criteria	Findings	
7.8 Adequate measures to protect asset management	Through discussions with the Operations and Platforms Manager, and consideration of the Cybersecurity policy and Identity and Access Management Standard, we determined:	
data from unauthorised access or theft by persons outside the	• Master service agreements and non-disclosure agreements are in place prior to sharing restricted or confidential data with third parties	
organisation	Unique identifier (UID) are created for an individual accessing a system or application	
	Permissions are assigned to personnel based on their position	
	Log and monitor vendor remote access accounts when in use.	
	The Cybersecurity policy outlines consequences for breach of policy and misuse of user privileges.	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)

#### 4.8 Risk management

**Key process:** Risk management involves the identification of risks and their management within an acceptable level of risk.

**Expected outcome:** An effective risk management framework is applied to manage risks related to the maintenance of service standards.

**Overall Adequacy/Performance rating:** Requires some improvement (B) / Opportunity for improvement (2)

Effectiveness Criteria	Findings		
<ul> <li>8.1 Risk management policies and procedures exist and are being applied to minimise internal and external risks</li> <li>8.2 Risks are documented in a risk register and treatment plans are implemented and monitored</li> </ul>	<ul> <li>Criteria 8.1 and 8.2</li> <li>Through discussion with the Head of Operations, Plant manager – Newman Power Station and consideration of relevant supporting documentation, we determined that:</li> <li>Alinta Energy's Enterprise Risk Management Framework applies throughout Alinta Energy's business structure, including Alinta Energy Transmission Roy Hill</li> <li>Application of Alinta's risk management policies and procedures to minimise internal and external risks associated with the AMS is evidenced in its use of the InControl system, which captures all key risks relating to Alinta's operations, including asset specific risks</li> <li>A risk register is maintained in the InControl risk management system. Details captured for each risk include:</li> </ul>		
	<ul> <li>Risk description</li> <li>Consequence/Impact</li> <li>Risk treatment plan</li> </ul>		
	<ul> <li>Scenario reporter</li> <li>Inherent risk rating</li> <li>Risk related documentation</li> <li>Person Responsible</li> <li>Current Controls</li> <li>Reviews</li> </ul>		
	<ul> <li>Person Responsible          Current Controls         Susiness objective         Residual risk rating         Additional actions         Additional actions     </li> </ul>		
	<ul> <li>All maintenance activities are based on a risk management approach, whereby the maintenance tasks addressing higher risk issues are performed first in order of high priority tasks, followed by lower priority tasks</li> </ul>		
	<ul> <li>The AMP is reviewed and revised if required, on an annual basis, using a risk based approach to prioritise medium to long term maintenance tasks, and associated capital expenditure projects. The tasks are listed and rated by risk in order to prioritise the urgency in which they are actioned</li> </ul>		
	• Daily meetings are used to arrange daily work plans, plans for upcoming work, and outage plans for major scheduled outages		
	<ul> <li>In March 2016, Alinta initiated an update of its risk assessment for maintenance activities. This update involved conversion of the previous excel model extracted from Ellipse (risk assessments were completed on an ad-hoc basis) to the InControl Risk Management System. The new risk management system, InControl, has been implemented and replaced the old KMI Incident Management System in 2017.</li> </ul>		
	Through testing a sample of seven risk treatments, we determined:		
	<ul> <li>One of the seven samples did not have evidence that it was monitored. This sample also had a status of "Adjustments required", meaning that the risk had not been reviewed in the recommended time frame.</li> </ul>		
	• Two of seven samples had no treatment plans. However, these risks had numerous controls and were documented in the risk register as not being relevant to the Newman Power Station.		
	In response to recommendation 2/2016, Alinta has built out its risk assessments in the InControl Risk Management System and continues to populate it as required. However, due to a sample scenario status being "Adjustment required",		

Effectiveness Criteria	Findings and two risks no longer being relevant to the Newman power station or Roy Hill transmission network, a more frequent review process may be required.		
	Adequacy Rating: Requires some improvement (B)	Performance Rating: Opportunity for improvement (2)	
8.3 The probability and consequences of asset failure are regularly assessed	d Through discussions with the Head of Operations, Plant Manager – Newman Power Station and consideration of Alinta asset planning and risk management practices, we determined that Alinta has applied the following mechanisms for		
	The management structures, skills and resources assigned to the asset management processes appear to be appropriate for enabling the regular assessment of the probability and consequences of asset failure.		
	Adequacy Rating: Adequately defined (A)     Performance Rating: Performing effectively (1)		

## 4.9 Contingency planning

Key process: Contingency plans document the steps to deal with the unexpected failure of an asset.

**Expected outcome:** Contingency plans have been developed and tested to minimise any significant disruptions to service standards.

#### **Overall Adequacy/Performance rating:** Requires some improvement (B) / Opportunity for improvement (2)

Effectiveness Criteria	Findings
Effectiveness Criteria 9.1 Contingency plans are documented, understood and tested to confirm their operability and to cover higher risks	<ul> <li>Through discussion with the Head of Operations and consideration of relevant supporting documentation we determined:</li> <li>Alinta has generated a Business Continuity Plan for its sites which encompasses the major risks and the strategies in place to address them. It outlines the testing that should be conducted. From discussions however, it was confirmed that no business continuity testing had been performed during the review period.</li> <li>Alinta maintains an emergency response plan for the Newman Power Station</li> <li>The emergency response plan incorporates training and drills that include:</li> <li>Emergency exercises that are undertaken twice each year; one a desktop exercise and a "live" exercise with emergency services involved. These simulate credible scenarios and the results of exercises are documented in Alinta's SharePoint system</li> <li>Monthly alarm testing</li> <li>Six monthly evacuation procedure testing</li> <li>Employee training.</li> <li>Duty officers (on a rolling schedule basis) are responsible for plant operations and addressing any alarms, including when onsite during office hours via the control system, and afterhours remotely by phone alarms. When the duty officer receives an alarm, they are required to investigate and take appropriate remedial action based on their understanding of the cause of the alarm the related risk. Minor alarms may be left to the next day shift, while high risk alarms require immediate attention. The plant manager would also be contacted as appropriate. Contingency planning is inherent in the design and setup of the plant, contractual agreements in place with third parties and as referenced in the Alinta Sites – Business Continuity plan, cottingencies are in place for major business operational risks of:</li> <li>Fuel supply:         <ul> <li>Gas is the primary fuel for the power station and is sourced via pipeline</li> <li>In the case of gas failure, the site uses diesel with the th</li></ul></li></ul>
	<ul> <li>small tank acting as a buffer</li> <li>Water is not a key input to the process as the plant is air cooled (i.e. not water cooled)</li> <li>Turbine failure/error:</li> <li>The Newman Power Station comprises four gas turbines (three GE units and one large Trent/Rolls Royce/Siemens unit) and three smaller diesel generators at the Roy Hill mine site</li> </ul>

Effectiveness Criteria	Find	ings	
	turbines and diesel generators combi should one turbine trip or have a failu The Newman Power Station has a lar	ge battery storage that assists in mitigating the loss of power	
	due to turbine failure, by picking up t $_{\circ}$ Transmission line failure	he load temporarily before other turbines can get online.	
	<ul> <li>Three smaller diesel generators locat Roy Hill.</li> </ul>	ed at the Roy Hill mine site can meet the essential load of	
	<ul> <li>Normal operation processes and procedures used to maintain, control and operate the plant include contingency aspects to allow the plant personnel to react to emergencies and implement necessary actions to limit the emergency's impact and recurrence.</li> </ul>		
	<ul> <li>In addition to the normal operational processes and procedures for the plant (as described above) risks relating to operational emergencies (such as catastrophic failure of plant) are managed by:         <ul> <li>Using regular inspections of key high-risk equipment (such as pressure vessels, and turbines, etc.) and undertaking preventative maintenance on those items, where required.</li> <li>Implementing a condition-based maintenance regime, whereby oil samples from key equipment are taken regularly and sent to an external lab for analysis. Any contaminants identified in the oil samples could indicate undue wear and tear of the item and a timely maintenance action is then initiated.</li> </ul> </li> <li>Alinta Energy also has a Cybersecurity Business Continuity Management Standard in place.</li> <li>In response to recommendation 3/2016, Alinta has prepared an over-arching "umbrella" document to capture all contingency plans in place for each of the key risks to each Unit's operations and availability. However, the document does not establish any testing arrangements, and no tests were planned.</li> </ul>		
	Adequacy Rating: Requires some improvement (B)	Performance Rating: Opportunity for improvement (2)	

### 4.10 Financial planning

**Key process:** The financial planning component of the AMP brings together the financial elements of the service delivery to ensure its financial viability over the long term.

**Expected outcome:** A financial plan that is reliable and provides for the long-term financial viability of the services.

**Overall Adequacy/Performance rating:** Adequately defined (A) / Performing effectively (1)

Effectiveness Criteria Findings			
10.1 The financial plan states the financial objectives and identifies strategies and actions to achieve the objectives	its financial objectives and strategies that are driven by it electricity	dget that is prepared on a rolling five-year basis, reflecting is contractual agreements for generation and supply of the plant's operations to reflect its financial viability over the out to FY2040	
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
10.2 The financial plan identifies the source of funds for capital expenditure and	Through consideration of Alinta's asset and financial planning processes and inspection of the AMP, we determined that operational cash flows are retained for budgeted maintenance and capital expenditure, based on retained funds or by submission through the Alinta Group corporate structure for non-budgeted expenditure.		
recurrent costs	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
10.3 The financial plan provides projections of operating statements (profit and loss) and statement of financial position (balance sheets)	<ul> <li>Through consideration of Alinta's asset and financial planning processes and inspection of Alinta's five-year plan, profit and loss report and the AMP, we determined that:</li> <li>Alinta's financial plan constitutes a summary of budgeted income and expenses from the supply of electricity under its contractual agreements, which is prepared and updated annually and includes a rolling forecast for the next five years</li> <li>Alinta's business planning process analyses and forecasts the lifecycle cost of owning and operating assets until FY2040</li> <li>An income statement and a position statement are prepared as part of statutory financial statements on a sixmonthly and annual basis</li> <li>A monthly Profit and Loss report is generated which provides a detailed breakdown of financial projections.</li> </ul>		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
10.4 The financial plan provides firm predictions on income for the next five years and	Through consideration of Alinta's asset and business planning lifecycle models, we determined that Alinta forecasts generat predictions forecast over a five-year period.		
reasonable predictions beyond this period	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	

Effectiveness Criteria	Findings		
10.5 The financial plan provides for the operations and maintenance, administration and capital expenditure requirements of the services	<ul> <li>Through consideration of Alinta's asset and financial planning processes and inspection of Alinta's annual budget and AMP, we determined:</li> <li>The profit and loss statement provide a detailed monthly view of operational expenditure i.e. operations maintenance and administration expenses for the financial year</li> <li>Includes a summary of current and planned capital expenditure projects over the following five years, with a brief description of each project's purpose and assumptions.</li> </ul>		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	
10.6 Large variances in actual/budget income and expenses are identified and corrective action taken where necessary	<ul> <li>D.6 Large variances in tual/budget income and planning mechanisms, we observed that:</li> <li>On a monthly basis, a variance analysis report is produced in a management packator of the second sec</li></ul>		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)	

## 4.11 Capital expenditure planning

**Key process:** The capital expenditure plan provides a schedule of new works, rehabilitation and replacement works, together with estimated annual expenditure on each over the next five or more years. Since capital investments tend to be large and lumpy, projections would normally be expected to cover at least 10 years, preferably longer. Projections over the next five years would usually be based on firm estimates

**Expected outcome:** A capital expenditure plan that provides reliable forward estimates of capital expenditure and asset disposal income, supported by documentation of the reasons for the decisions and evaluation of alternatives and options.

#### **Overall Adequacy/Performance rating:** Adequately defined (A) / Performing effectively (1)

Effectiveness Criteria	Effectiveness Criteria Findings			
11.1 There is a capital expenditure plan covering works to be undertaken, actions proposed, responsibilities and dates	<ul> <li>Through discussions with the Financial Manager – Projects and consideration of Alinta's capital planning procedures and examination of the capital expenditure plan and the AMP, we determined:</li> <li>A capital expenditure plan is included in the annual financial plan</li> <li>Capital expenditure planning is undertaken along with financial planning on a rolling five-year basis and is included in the AMP</li> <li>The annual plan provides information on the amount, purpose and description of budgeted capital expenditure</li> <li>The plan does not provide information on roles and responsibilities, but they can be found in Alinta's business plans and work orders.</li> </ul>			
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)		
11.2 The capital expenditure plan provides reasons for capital expenditure and timing of expenditure	Through discussions with the Financial Manager – Projects and consideration of Alinta's asset and business planning processes and inspection of Alinta's AMP, Capital Expenditure Plan and supporting asset lifecycle models, we determined the annual AMPs outline capital expenditure requirements, including reasoning and timeframes for relevant refurbishment or upgrade activity.			
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)		
11.3 The capital expenditure plan is consistent with the asset life and condition identified in the asset management plan	<ul> <li>Through discussions with the Financial Manager – Projects, constraints on of the capital expenditure plan, we determined:</li> <li>Alinta's procedures require life cycle costs of assets to be equipment, including key life cycle issues, critical outages</li> <li>The capital expenditure plan concurs with the assessed life</li> </ul>	assessed and recorded in the AMP for each major and operating & maintenance philosophy		
	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)		
11.4 There is an adequate process to ensure that the capital expenditure plan is	Through discussion with the Head of Operations and consider inspection of Alinta's Capital Expenditure Plan, AMP and supp capital expenditure requirements are reviewed and updated w	orting asset lifecycle models, we determined that Alinta's		
regularly updated and implemented	Adequacy Rating: Adequately defined (A)	Performance Rating: Performing effectively (1)		

#### 4.12 Review of AMS

**Key process:** The AMS is regularly reviewed and updated.

**Expected outcome:** Review of the AMS to ensure the effectiveness of the integration of its components and their currency.

**Overall Adequacy/Performance rating:** Requires some improvement (B) / Opportunity for improvement (2)

Effectiveness Criteria	Findings		
12.1 A review process is in place to ensure that the asset management plan and the asset management system described therein are kept current	<ul> <li>Asset Management system documentation, we observed:</li> <li>The AMP, which is the main reference to the asset management system and the support of an asset of Asset Management have the primary responsibility responsible for approving the revised version. However, the a draft iteration</li> </ul>	is the main reference to the asset management system, has been reviewed and updated (where an annual basis. With the support of an assigned Mechanical Engineer, the Asset Engineer and the lanagement have the primary responsibility for that annual review, with the Head of Operations approving the revised version. However, the AMP has sections that remain incomplete and remains in Asset Management Framework provides for asset management activities to be subject to performance I continuous improvement.	
	Adequacy Rating: Requires some improvement (B)	Performance Rating: Opportunity for improvement (2)	
internal audit) are performed of response to Recommendation 4/2016 of the p		t to regular review and update as noted in section 12.1. In Ninta has had an independent review of its asset nt review of Alinta's Asset Management Framework issued by	
	However, Alinta have not established a register or record to capture the reviews conducted on its asset management system and the independence of the associated reviewer. Alinta are currently compliant as they are performing independent reviews of the AMS, however a register or record would improve the documentation in relation to the external reviews.		
	Adequacy Rating: Adequately defined (A)         Performance Rating: Performing effectively		

# 5 Follow-up of previous review action plans

Reference (no./year)	(Asset management effectiveness rating/ AMS Component & Criteria / details of the issue)	Reviewer's recommendation or action planned	Further action required		
A. Resolv	. Resolved at end of current review period				
n/a	n/a	n/a	n/a		
B. Unreso	olved at end of current review period		1		
1/2016	Asset Planning 1.8 Plans are regularly reviewed and updated 2.5 Ongoing legal / environmental / safety obligations of the asset owner are assigned and understood Although the Newman Power Station and Roy Hill Transmission Line SAMP and supporting AMP generally reflect AETRH's expectations and requirements for managing the relevant facilities' assets, they can be further improved.	<ul> <li>Recommendation and action plan 1/2016</li> <li>AETRH explicitly incorporate the following elements of its Asset Management Framework and EIRL obligations into the Newman Power Station and Roy Hill Transmission Line SAMP and supporting AMP:</li> <li>Contingency plans</li> <li>Known and significant risks relating to the key assets</li> <li>Legal and compliance requirements.</li> <li>Status</li> <li>Alinta has added risk and compliance recommendations to the AMP and SAMP in July 2018.</li> <li>The contingency arrangements haven't been added to the Asset Management Plan</li> </ul>	Yes. Refer to Recommendation and Action Plan 1/2019		
2/2016	<ul> <li>Asset management and Risk maintenance</li> <li>6.5 Risk management is applied to prioritise maintenance tasks</li> <li>8.1 Risk management policies and procedures exist and are being applied to minimise internal and external risks associated with the asset management system</li> <li>8.2 Risks are documented in a risk register and treatment plans are actioned and monitored</li> <li>Alinta had not retained clear evidence of some of those risk management activities to demonstrate that</li> </ul>	<ul> <li>Recommendation and action plan 2/2016</li> <li>Alinta will establish a clear:</li> <li>Timeframe for completing its program of populating risk assessments within the SPM Asset software</li> <li>Approach and timeframe for assessing risks, implementing treatment plans and monitoring status on a more frequent basis than the annual review of the AMP.</li> <li>Status</li> <li>Alinta had completed its program of populating its risk assessments into SPM by October 2017.</li> </ul>	Yes. Recommendations were provided directly to AETRH		

Reference (no./year)	(Asset management effectiveness rating/ AMS Component & Criteria / details of the issue)	Reviewer's recommendation or action planned	Further action required
	its risk management philosophies and approach are consistently applied.	However, it is not clear that they regularly review the risk register.	
3/2016	Asset Disposal	Recommendation and action plan 3/2016	Yes.
	<i>9.1 Contingency plans are documented, understood and tested to confirm their operability and to cover higher risks</i>	1. Establish a formal process for ensuring that contingency arrangements in place for all key risks to the Power Station's operations and availability are rigorously	Recommendations were provided directly to AETRH
	As Alinta's contingency plans and arrangements are currently maintained/described in different processes and documents, Alinta has the opportunity to further ensure the completeness and consistency of its contingency planning arrangements by capturing all of its plans and processes in one single reference.	<ul> <li>challenged and tested</li> <li>2. Prepare a clear over-arching "umbrella" document to capture all contingency plans in place for each of the key risks to each Unit's operations and availability.</li> <li>Status</li> </ul>	
	Such an approach would be consistent with Alinta Energy's Asset Management Framework.	Alinta has completed the umbrella document, however it is not clear that this has been tested regularly, or that records have been kept.	
4/2016	Review of AMS	Recommendation and action plan 4/2016	No.
	12.2 Independent reviews (e.g. internal audit) are performed of the asset management system	• The requirement for its asset management system to be subject to an independent review on a regular basis	Recommendations were provided directly to AETRH
	Although components of Alinta's asset management system are subject to regular review and update, Alinta has not applied a formal process for ensuring a	• A register or record to capture the reviews conducted on its asset management system and the independence of the associated reviewer.	
	sufficient degree of independence in any regular review of the asset management plan and underlying asset management system.	Status	
		As disclosed in the January 2018 Post Review Implementation Plan Update to the ERA, Alinta engaged an external company to perform an audit of Alinta's AMF, with a register created to captured details of the audit conducted. The January 2019 Post Review Implementation Plan Update showed these as closed out.	
		However, Alinta has not shown us that they have developed a register	

## Appendix A - Review plan

## Appendix B - References

Alinta staff participating in the review

- Head of Operations Power Generation
- Regulatory Compliance Manager
- Finance Manager Projects
- Plant Manager Newman Power Station
- Senior Analyst, Finance Merchant Energy

Deloitte staff participating in the review

Hours

Vincent Snijders	Partner	11
Maria Moreano	Senior Manager	7
Lyle Stewart	Senior Analyst	24
Morgan Jones	Analyst	70
Alexis Lefebvre	Analyst	27
Ben Fountain	Technical QA Director	3
Peter Rupp	Partner (Quality Assurance Review)	2

Sites visited by the auditor during the review

- Alinta Energy's Perth Head Office
- Newman Power Station

#### Key documents and other information sources examined

- Newman FY2019 Asset Management Plan
- Newman Strategic Asset Management Plan
- Asset Management Policy
- Asset Management Framework
- Project Management Framework
- Alinta Energy Risk Management Framework
- Roy Hill Purchase Agreement
- Newman five year plan
- Newman Capex FY2021-FY2024
- Asset Modelling to FY2040
- Newman SIB CapEx
- Request for Commitment process screenshots
- Ellipse Screenshots of CapEx and task prioritisation
- Newman Detailed Profit and Loss
- Procurement Standards
   Delegations of Authority
- Delegations of Authority
- Wave International AM Framework Audit Report 2018
- Outage Management Framework
- Management of Change
- List of maintenance tasks Ellipse
- Newman equipment list
- Newman fixed asset register
- Maintenance Work Process Manual
- Maintenance Standards

- Health and Safety Policy
- Alinta Energy OHS Management Framework
- Environmental Management Framework
- AETRH Annual Environmental Report
- AETRH FY19 Emissions Testing
- Newman Station Environmental License
- InControl Risk Management System
- Newman Performance Reports
- Cybersecurity policies
- Identity and Access Management Standards
- Newman Risk Register and samples
- Newman Emergency Response Plan
- Alinta Sites Business Continuity Plan
- Business Continuity Management Standard
- Alinta Energy Australia Training Matrix
- Alinta Energy Position Descriptions
- Power Generation Operational Plan