Entity name: Rio Tinto (Hamersley Iron) Water Compliance Manual Datasheet - Potable Water Providers NOT subject to NWI Reporting

Water Resources	Nater Resources						
Indicator	Reference	Description	Number	Percentage	Comments		
	W1	Volume of water sourced from surface water (ML)					
	W2	Volume of water sourced from groundwater (ML)	3029.0				
	W3	Volume of water sourced from desalination (ML)	0.0				
Sources of water	W4	Volume of water sourced from recycling (ML)	0.0				
	W5	Volume of water sourced from bulk supplier (ML)	720.0				
	W6	Volume of bulk recycled water purchased (ML)	0.0				
	W7	Total sourced water (ML)	3749.0				
Uses of water supplied	W11	Total urban water supplied (ML)					
uses of water supplied	W12	Average annual residential water supplied (kL/property)	0.0				

Asset Data					
Indicator	Reference	Description	Number	Percentage	Comments
Other water assets	A2	Length of water mains (km)	106.0		
Other water assets	A3	Properties served per km of water main	22.7		
Water main breaks	A8	Number of water main breaks	16.0		
	Ao	Water main breaks (per 100km of water main)	15.1		

The Customers					
Indicator	Reference	Description	Number	Percentage	Comments
Connected properties and population		Total number of customers (connected properties)	2402		
Unplanned water supply interruptions	C15	Average duration of an uplanned interruption - water (minutes)	175.0		
Customer interruption	C17	Number of unplanned interruptions	286.0		
frequency		Average frequency of unplanned interruptions - water (per 1,000 properties)	119.1		
Customer interruptions	Licence Sch 4, Cl. 2.2/3.1	Number of connected properties that did NOT experience an interruption to water supply exceeding 1 hour in duration (12 month data)	1569		
		Percentage of connected properties that did NOT experience an interruption to water supply exceeding 1 hour in duration (12 month data)		65.3%	
Water pressure and flow	Licence Sch 4, Cl. 2.1/3.1	Number of connected properties that have been supplied at a pressure and flow that meets the standards set out in the licence (12 month data)	2401		
		Percentage of connected properties that have been supplied at a pressure and flow that meets the standards set out in the licence (12 month data)		100.0%	

Indicator	Reference	Description	Number	Percentage	Comments
	H1	Water quality guidelines	Provide details specified in the		
	H2	Number of zones where microbiological compliance was achieved (e.g. 23/24)	3/3		
	H3	Percentage of population where microbiological compliance was achieved		100.0%	
Vater quality compliance	H4	Number of zones where chemical compliance was achieved (e.g. 23/24)	3/3		
	H5	Risk based drinking water management plan assessed externally (yes/no)	Yes		
	H6	Risk based drinking water management plan (please specify plan in place, i.e ISO9001, HACCP) (yes/no)	Yes		Water Quality Management manual - based on framework of 2004 ADWG
	H7	Public disclosure of drinking water performance (yes/no)	Yes		

Entity name: Rio Tinto (Hamersley Iron)

Water Compliance Manual Datasheet - Sewerage Service Providers NOT subject to NWI Reporting

Water Resourc	Vater Resources						
Indicator	Reference	Description	Number	Percentage	Value (\$)	Comments	
Sewage collected	W18	Total sewage collected (ML)	531				
Sewage collected	W19	Sewage collected per property (kL/property)	221.1				
Uses of recycled	W26	Total recycled water supplied (ML)	0.0				
water	W27	Recycled water (percent of effluent recycled)		0.0%			

Asset Data	isset Data						
Indicator	Reference	Description	Number	Percentage	Value (\$)	Comments	
Sewerage assets	A5	Length of sewerage mains and channels (km)	85				
Sewerage assets	A6	Properties served per km of sewer main	28.3				
Sewer main breaks and chokes	A14	Number of sewer breaks and chokes	9				
		Sewer breaks and chokes (per 100km of sewer main)	10.6				

The Customers						
Indicator	Reference	Description	Number	Percentage	Value (\$)	Comments
Connected		Total connected properties - sewerage				
properties and			2402			
population						

Environment						
Indicator	Reference	Description	Number	Percentage	Value (\$)	Comments
	E1	Percentage of sewage treated to a primary level		100.0%		
Sewage treatment levels	E2	Percentage of sewage treated to a secondary level		100.0%		
	E3	Percentage of sewage treated to a tertiary level		0.0%		
Biosolids reuse	E8	Percentage of biosolids reused		0.0%		
Sewer overflows	E13	Number of sewer overflows reported to environmental regulator	0			
		Sewer overflows reported to environmental regulator (per 100km of sewer main)	0.0			
Sewer overflows	Licence Sch 4, Cl.3.1/7.1	Number of connected properties experiencing a wastewater overflow	9			This is the number of overflows, however not every overflow affects a property directly.
		Percentage of connected properties NOT experiencing a wastewater overflow		99.6%		

Entity name: Rio Tinto (Hamersley Iron) Water Compliance Manual Datasheet - Complaints

Complain	ts Handling					
Indicator	Reference	Description	Number	Percentage	Value (\$)	Comments
CH 1	C9	Water quality complaints (per 1,000 properties				
CH 2	C10	Water service complaints (per 1,000 properties)				
CH 4	C11	Sewerage service complaints (per 1,000 properties)				
CH 5	C12	Billing and account complaints - water and sewerage (per 1,000 properties)				
CH 6		Other complaints (per 1,000 properties)				
CH 7	S.8	Irrigation customer service delivery complaints (per 100 customers)				
CH 8	Licence Sch. 4, Cl. 1.2/2.1	Percentage of customer complaints resolved within 15 business days		59.0%		

Entity name:Rio Tinto (Hamersley Iron)Water Compliance Manual Datasheet - Contact Centre

Call Centr	e Performance					
Indicator	Reference	Description	Number	Percentage	Value (\$)	Comments
-	C14 (Water Corporation only)	Percentage of calls answered by an operator within 30 seconds				
	Licence Sch. 4, Cl. 2.1 (Water Corporation only)	Percentage of calls that were abandoned after 5 seconds				
TS 3	1.1	Percentage of customers who, within 1 hour of reporting an emergency, were advised of the nature and timing of the action to be undertaken by the licensee		100.0%		



RioTinto



WATER AND WASTE WATER SERVICES

WATER QUALITY

- We will supply you with drinking water to the standard determined by the Water Services Operating Licence.
- We continually monitor and assess the quality of drinking water supplied.

RELIABLE WATER SUPPLY AND SEWERAGE SERVICE

- We aim to provide water supply and sewerage service to you 24 hours of every day.
- In the event of an interruption to your water supply or sewerage service we will be on call 24 hours, 7 days a week please call **1800 992 777** and a decision maker will return your call within an hour.
- We will make every effort to limit any interruption to your water supply or sewerage service to six hours.
- If a water interruption exceeds six hours, drinking water will be available from a nominated point.
- We will respond within two hours for sewerage overflow problems.
- When we have a need to undertake planned service interruptions we will provide at least 48 hours notice to our domestic and at least 7 days notice to our commercial or industrial customers.
- In case of an emergency such as sewer overflow call 1800 992 777.

YOUR RIGHTS TO ASSISTANCE, REDRESS & COMPENSATION

 If Rio Tinto's activities have caused serious damage to your property or disruption to you, such as sewer overflow, Rio Tinto shall deal with the matter in a fair and business like manner, whether or not a complaint is received. Rio Tinto may rectify damage and, as necessary, refer any compensation claims to its insurers for assessment and necessary action.

WATER PRESSURE AND FLOW

 We will ensure each property service is provided with pressure ranges and flow rates in line with recommended industry standards, being 20 litres per minute flow, a minimum pressure of 15m, and a maxium pressure of 100m.

TREATMENT AND DISPOSAL OF WASTEWATER

- We are committed to environmentally sound practices in the treatment and disposal of wastewater.
- We will operate all wastewater treatment plants according to licence conditions set by the Department of Environment and Conservation.

CUSTOMER ENQUIRIES

 We will endeavour to address all enquiries on the same day they are received, and if we are unable to do so we will contact and advise you.
 We will be available weekdays between 8:00am and 3:30pm. Please call 1800 992 777.

CUSTOMER COMPLAINTS

We aim to resolve complaints as quickly as possible, at least within 15 business days. For complex issues, we will maintain a free and accessible dispute resolution process. Please call **1800 992 777**. You may raise the complaint to a higher level within Rio Tinto's Management structure if you are not satisfied with the initial response. If you are not satisfied with the outcome, you can refer the complaint to the Department of Water at

> Customer Services Officer The Department of Water Water Industry Support Branch PO Box K822 Perth WA 6842 Phone: (08) 6364 7600 Website: www.water.wa.gov.au Email: WISBcomplaints@water.wa.gov.au



The Water Services Planning Branch provides a reconciliation service and will provide explanations and recommendations.

AUDIT OF PERFORMANCE

- The charter sets out the broad philosophy of Rio Tinto in supplying water supply services and waste water services in accordance with the operating licence issued by the Economic Regulation Authority under the Water Services Licensing Act 1995.
- The charter informs you, the customers of Rio Tinto, of your rights in accordance with the provisions of the operating licence, including service interruptions, levels of service and complaints procedures. If you would like a copy of the operating licence please contact Rio Tinto on **1800 992 777** or ERA on 9213 1900.

CUSTOMER OBLIGATIONS

• When you move into a property and vacate a property, you will need to complete either an application form or a termination form for the water supply. The form must be returned to: Rio Tinto, within 7 days of occupying the property.



Rio Tinto account terms are strictly 30 days.
 Failure to pay within theses terms may result in restriction or disconnection of your water supply.

CONDITIONS OF CONNECTION

- From time to time, we will need to enter your property to undertake maintenance on our systems. Except in an emergency, we will provide 48 hours notice. In an emergency, we will leave a card advising you of our presence on your property.
- Your water meter must be accessible at all times to Rio Tinto staff and their contractors.
- If the water meter is damaged, Rio Tinto reserves the right to recover the cost from you for reinstatement.
- Rio Tinto reserves the right to list you as a default debtor with Credit Advantage Australia should you fail to pay your account. Please call 1800 992 777 for any queries relating to your account.

DISCONNECTION

 If the water supply service and the waste water services is no longer required by you, a disconnection from the Rio Tinto services may be approved provided that:-

1. Rio Tinto is first notified of the intention; and the property has no further water supply services and waste water disposal requirement; and

2. The disconnection is carried out by a licensed plumber who must be provided by Rio Tinto.

- In most circumstances, disconnection of water supply services and waste water services does not terminate this charter. Rio Tinto will continue to charge water supply services and waste water services rates to the owner of the land/ tenant (including vacant land) where water supply services and waste water services are available for connection. The charter is void if there were no services available and no charges levied.
- Rio Tinto shall reconnect its services at your request and on compliance with the terms and conditions of this charter. A reconnection fee shall apply.

FUTURE WATER NEEDS

- We continue to identify new water source requirements associated with likely future growth.
- We plan to ensure our infrastructure and systems are developed to cater for projected growth.

YOU'RE RIGHTS - WATER AND SEWERAGE SERVICES

ITEM	REQUIREMENT
Provision of minimum notice for planned works (Residental properties affected)	48 Hours
Provision of minimum notice for planned works (commercial/industrial properties affected)	7 Days
Time for provision of advice in response to a complaint/service query	Within 1 hour from the receipt of complaint/ enquiry
Interruption to water supply or sewerage services	Every effort to be made to limit to a maximum of 6 hours
Provision of drinking water for water supply interruption	To be provided after 6 hours
Response to serious water supply bursts and leaks	Respond within 1 hour Commencement of work within 1.5 hours of notification Completion of work within 6 hours
Response to moderate water supply bursts and leaks	Respond within 1 hour Commencement of work within 3 hours of notification Completion of work within 6 hours
Response to minor water supply bursts and leaks	Respond within 24 hours Rectification within 3 days of notification

YOUR RIGHTS TO CONSULTATION AND INFORMATION

- We provide customer information and consultation by two methods: by conducting annual surveys and by the publication of magazines and newsletters.
- Rio Tinto will publish and make available at its premises information on matters relating to its water and waste water supply services and on other aspects such as complaints handling. Rio Tinto company representatives will provide their name and section in business discussions with customers.

FEES AND CHARGES

- Property owners will receive an annual fixed service charge (referred to as "water & sewerage rates"). The sewerage service charge isn't the same for everyone; it depends on the rateable value of your property.
- Property tenants receive a charge for the water they use. The rate begins at a lower rate per kilolitre and goes up in steps as you use more water. This is the normal water regulation pricing system for North West Country areas.

SEWERAGE SPILLS

- Rio Tinto will make every reasonable effort to minimise sewerage spills on customer's properties, due to failure of Rio Tinto sewerage systems.
- Where Rio Tinto is responsible for a sewerage spill on a customer's property, it will ensure that:-
- The spill is contained within 1 hour of notification if the spill is in the customer's house; all other spills are contained within 4 hours.
- Inconvenience to the customer is minimised and
- The areas are cleaned up as quickly as possible in such a manner to ensure the risk to human health is peoligible

SEWER BLOCKAGES

- If a customers sewer becomes blocked Rio Tinto can be contacted on 1800 992 777 to arrange repairs.
- If the blockage is in a Rio Tinto sewer pipe, Rio Tinto will pay for the clearance.
- If the blockage is in the customers sewerage pipe the customer can contact Rio Tinto on 1800 992 777 to arrange repairs at the customers own cost.

MAINTENANCE

- Rio Tinto's water supply services and waste water services are provided from the point where the pipes serving your property connect to Rio Tinto's water supply main and wastewater reticulation main.
- Water supply mains and wastewater reticulation mains and associated fittings
 remain the property of Rio Tinto whether or no they are located in the private
 property. The location of these structures can be obtained from Rio Tinto's
 office. You are required to ensure that Rio Tinto's pipelines and structures
 are reasonably accessible and, are not interfered with, covered, built close to,
 built over or damaged.
- Prior to undertaking building or construction activity on land connected or capable of being connected, it is a requirement to gain approval from Rio Tinto. In the first instance, you should contact the Rio Tinto office. Unauthorised property improvements, which interfere with the Rio Tinto's assets, may be required to be removed at your cost.
- It is also required that you DIAL BEFORE YOU DIG on: 9143 5662 - Dampier 9143 3211 - Tom Price 9143 4501 - Paraburdoo
- Rio Tinto is responsible for the maintenance of water supply connections and waste water connections (sewer connections) where they are unable to be cleared or repaired from the inspection shaft – provided the fault in the property is outside the property concerned.
- You are responsible for all plumbing, pipes and fixtures on or serving your property to the point where the pipes connect to the Rio Tinto water supply connections.

OUR COMMITMENT TO SERVICE

 Rio Tinto will provide its services in a manner which is fair, courteous and timely – with a focus on consultation with our customers, respecting your rights, and meeting your reasonable expectations.

LIMITATION OR WITHDRAWAL OF SERVICES

- Rio Tinto may discontinue its water supply services and waste water services in the following circumstances:-
- If you do not comply with the terms and conditions of this charter
- If there is a public health, environment and/or safety risk to Rio Tinto's services from your service connection (e.g. backflow risk or unauthorised industrial waste discharge); and/or
- If you do not pay, or meet and make arrangements to pay overdue charges for the services.

PROVIDING NEW SERVICES

• Where the reticulation main is available, we will provide a connection to the water reticulation system within 10 days of receiving your application subject to charge.

CUSTOMER SUGGESTIONS

 If you have any suggestions relating to water and sewerage service please call 1800 992 777.

SERVICE INTERRUPTIONS

- Rio Tinto's water supply and waste water supply services are designed to be available 24 hours a day. However, Rio Tinto may interrupt, postpone or limit its water supply services and sewerage services to customers:-
- If any part of works is damaged, by bursting, blockages or breakdowns: or
- It is necessary to inspect, maintain, repair or replace any part of works: or
- · For connection of new works or services: or
- If an event beyond Rio Tinto's control, including acts by others, sabotage, flood cyclone, earthquake, power or water shortage or industrial action.

LIABILITY

- Rio Tinto is liable for any loss or damage that you may suffer:-
- As a result of this charter by Rio Tinto, its servants or agents;
- As the result of a negligent act or omission by Rio Tinto its servants or agents; and /or
- As a result of the failure to meet standards prescribed by its operating licence or regulations (if any).

DISCHARGE OF UNAUTHORISED SUBSTANCES

- It is your responsibility to ensure that stormwater (including roof runoff) and other unauthorised substances are not discharged into Rio Tinto's sewers. Certain waste products are not suitable for disposal in the Rio Tinto waste water system because of their nature and ability to pollute. Specialised procedures for disposal are required for substances such as:-
- Cooking oil and grease these should be placed in a container or wrapped and placed in a rubbish bin;
- Paint, paint thinners, dry cleaning fluids, engine oil, solvents, acids, alkalis, laboratory chemicals, kerosene, garden poisons, polishes or cleaning fluids; and
- Products like disposable nappies, panty hose, sanitary napkins, tampons, cotton buds, syringes, toilet deodorant packs and razors

 these should be wrapped and placed in a rubbish bin



FOR ALL ENQUIRIES


Rio Tinto Parker Point, Dampier PO Box 21 Dampier WA 6713 Freecall: 1800 992 777 Facsimile: (08) 9143 5280 Office Hours: 8.30am - 4.00pm Rio Tinto Pty Ltd ABN 35 107 210 248 October 2008 Website: www.riotinto.com.au Email: picc@riotinto.com EMERGENCY CONTACT 1800 992 777 (Available 24 hours per day)


010	
AND 2	
TION PL	
YAC	
SURVE	
OMER	
CUST	

.


Теат	¥	csu	CSL CSL	CSU	······	55 55 58 58	er en el tratta en en	SSU	CSU	csu
Action to be taken		1.1.2.1. Provide RTIO Catander with all relevant infromation.	 1.1.1. Provide information about standards in quartery. Water Wisdom newsletter. 2.1.1.2. Provide motestink on water invoices in relation to standards and where to find into. 2.1.1.3. Provide RTIO Calander with all relevant information. 	2.1.2.1. Create a pamphtet summarising the standards and where to locate more into about them.		3.1.1.1. Provide information about standards in quartery. Water Wiscom newsletter each year. 3.1.1.2. Provide notes/firk on water invoices in relation to standards and where to find info. 3.1.2.1. Create a pamphet summarising the standards and where to focate more into about them.		4.1.1.1. Condrive to provide all new customer with charter in their "Welcome" letter, 4.1.1.2. Conditive to provide all customer swith a copy of the charter at least every tyree years.	4.1.2.1. Provide notes on water invoices about where to boate online charter. 4.1.2.2. Provide infromation about online charter in Water Wisdom newsletter once each year.	4.2.1.1. Frovide new customers with a copy with "Welcome" letter. 4.2.1.2. Include summary/diagram in Water Wiscom newletter once each year.
Resolution/Commitment	1.1.1. Improve RTIO branding on involces, corresepondence, etc.	1.1.2. Increase general information from RTIO to customers.	2.1.1. Increase information provided to customers about standards to expect.	2.1.2. Provide information about stanards to new customers with their "Welcome" letter.	2.2.1. Increase infromation/education to customers about causes of water issues	 1.1. Increase information provided to customers about standards to expect. 3.1.2. Provide information about stanards to new customers with their "Welcome" letter. 		4.1.1. Continue to provide all customers with charter.	4.1.2. Increase metrods of informing customers about charter.	4.2.1. Provide customers a summary/diagram of complaints procedure and review process.
Issue	1.1.1 in 4 customers do not know RT10 is their water and severge provider.		2.1. Low awareness in customers of the mimimun standards of service.		2.2. Customets feit water quality needed improvement.	 Low awareness in customers of mirimum standards of service. 	3.2. Customers key concerns - servage odours, blockages & overflows.	4.1. Very few customers actually aware of charter.		4.2. Very few customers aware of complaints procedures available.
Category		Provider	2. Water Services			3. Sewage Services		4. Customer Complaints	Procedure	



































Awareness of Customer Charter & Customer Complaints Procedure







WATER WISDOM

NEWSLETTER | ISSUE 3 - QUARTER 1 2010

WATER CONSERVATION

The water supply for our towns comes from groundwater from underground bores.

This is a limited resource that is only recharged by rainfall. With limited rainfall this summer, water use at work and at home affects future water supplies.

A number of water conservation initiatives have been completed across the sites including:

- Tom Price repairs to leaking hoses and pipes around the plant, water truck level indicators, automation of stockpile water sprays, vacuum pump water recycling;
- Paraburdoo pipework repairs, stockpile water recycling, water reuse for dust suppression;
- Dampier Port Operations installation of new washdown facility which recycles water for washdown use; and
- Dampier, Paraburdoo and Tom Price towns - leak detection programme.

Conservation of water also saves you money. Rio Tinto customers in Dampier, Paraburdoo and Tom Price are charged a low tariff for every kilolitre of water that they use. However the more you use, the quicker you move up the sliding scale to a higher tariff level.

TOWN SEWER UPGRADE

Rio Tinto Networks is continuing the town sewer upgrade programme in Paraburdoo and Tom Price. This work is designed to extend the life of key sewer assets, and ensure that blockages and sewer overflows do not occur.

As part of the programme, vitreous clay and cast iron sewer pipes are being replaced with PVC pipes.

Manager Networks Services Paul White said that using PVC pipes meant that the assets have a greater capacity and resistance to corrosion and chemicals.

"They are easier to handle than clay or steel pipes, and therefore safety on the job is improved," he said.



OUR FIVE TOP TIPS TO SAVE WATER

- Water your garden wisely before 9am or after 6pm.
- 2. Fix leaking taps, hoses and pipes a tap dripping at one drop per second wastes 50L of water per day.
 - . Take a shower instead of a bath a short shower uses about a third as much water as a bath.
- 4. Don't use the washing machine until it is full.
- . Wash your car on the lawn and use a bucket, not a running hose.

Rio Tinto Utilities Customer Services Parker Point, PO Box 21, Dampier WA 6713 Freecall: 1800 992 777

WATERING DAYS - NORTH OF KALBARRI AND KALGOORLIE

Cross reference the **last digit** of your house number to find out your watering days.

egaliji - Yun wate mi saya

																																		11	

- 2 2nd 4th, 6th, 5th, 10th, 12th, 14th, etc
- 3 Ist. 1nt.5th.7th.9th.1th.11h.etc
- s Int. Jid. 516, 716, 916, 11th, 19th air.
- 6 2nd 405 605 805 1005 1205 1405 est
- 7 Ist, 3rd, 5th, 7th, 9th, 11th, 13th, 9th
- 8 2nd 4th 6th 8th 10th 12th 14th m
- 9 Ist, Ird 5th, 7th, 9th, 11th, 12th, atr
- d 💫 2mi 4th 6th 8th 10th 12th 14th 4th

Where a house number is not available, it defaults to the last digit of your lot number. You may water only once either before 9am or after 6pm.

CUSTOMER COMPLAINTS

We aim to resolve complaints as quickly as possible, at least within 15 business days.

For complex issues we maintain a free and accessible dispute resolution process, please contact:

Rio Tinto Utilities Customer Services Parker Point, PO Box 21

Dampier WA 6713

Freecall: 1800 992 777

You may raise the complaint to a higher level within Rio Tinto's management structure if you are not satisfied with the initial response.

If you are not satisfied with the outcome, you can also refer the complaint to the Department of Water at:

Customer Services Officer

The Department of Water Water Industry Support Branch PO Box K822 Perth WA 6842

Phone: (08) 6364 7600

Email: WISBcomplaints@water.wa.gov.au

Website: www.water.wa.gov.au

IMPORTANT INFORMATION

WATER CONSUMPTION & WATER RATES

There are two costs for water

- Property owners will receive an annual fixed service charge (referred to as "water & sewerage rates"). The sewerage service charge isn't the same for everyone; it depends on the rateable value of your property.
- 2. Property tenants receive a charge for the water you use. The rate begins at a lower rate per kilolitre and goes up as you use more water. This is the normal water regulation pricing system for North Country areas. It aims to encourage water conservation and discourage excessive use of water (and it works!).

WATER REBATE

A water rebate is paid to compensate for the extra watering demands of gardens in the Pilbara. It is paid according to the table below and will be paid to all Iron Ore staff tenants through the payroll in July each year. You will receive a pro rata rebate in your first and final year.

		;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;;	

The Water Rebate is based on the requirements of a house or duplex and is not applicable to other types of dwellings such as town houses, flats and home units.

 \mathbf{O}

WATER CONSUMPTION - YEAR TO DATE

Water consumption is charged on a Year to Date basis. You are charged on a tier level according to what level of consumption you are using.

Nige energy and the second
Ip+: 150
liner Palentine 20 - 2023
and the second
Liene 220 feel conduct 520 D. D. D. S. M. S. M
Than Gelma and Gell Stitle
fan hyfner mae Thi Salfal
teer termeren trette statte
Exam 1150 by repeated 1530
than the first state of the second state of th
Chan 1550 Luciandar 1951 - \$1,377
rux lash

ACCOUNTS

You will be sent water-usage accounts in the months following our quarterly reads: meters are read at the end of February, May, August and November.

GENERAL INFO

િષ

Sometimes our meter readers may not be able to access your meter – for example if there is a dog on the property, or you have locked gates etc. If you receive a card saying 'We could not access your meter today' please call us on **1800 992 777** as soon as possible so we can obtain an accurate reading, and you can avoid an assessed consumption.



ုပ္ပ

RioTinto



WELCOME TO THE 2009 EDITION OF WATER WISDOM.

As we are all aware, water is a precious and limited resource we must use it wisely and be responsible for our impact on the environment. Mining is the second biggest consumer of water in Western Australia.

In the Pilbara, summer temperatures are hot, evaporation is high, and recent rainfall has been lower than average.

Reducing water consumption defers the need for new water sources and groundwater schemes, and reduces environmental impacts.

We have implemented a number of water conservation initiatives within the business including active leakage management and appreciate your support in helping us achieve a water wise operation.


In this issue of Water Wisdom we provide some important information on water operations in the Pilbara and what you need to know, and offer some tips on how you can help save water in your home and at work.

I hope you find the information useful.

Bennie Smith General manager - Utilities

Rio Tinto Customer Service Parker Point PO Box 21 Dampier WA 6713 Freecall: 1800 992 777





WHAT CAN YOU DO?

AT HOME?

- WATER YOUR GARDEN WISELY
- USE A SOIL WETTING AGENT
- USE EFFICIENT WATERING SYSTEMS
- WATER EARLY IN THE MORNING AND USE A WATERING CAN (NOT A HOSE) FOR POT PLANTS
- NEVER WATER IN THE HEAT OF THE DAY OR WHEN VERY WINDY
- MULCH YOUR GARDEN
- USE WATER EFFICIENT APPLIANCES
- FIX LEAKING TAPS, HOSES AND PIPES
- DON'T WASH DISHES UNDER A RUNNING TAP
- DON'T USE THE DISHWASHER UNTIL IT IS FULL
- DON'T USE THE WASHING MACHINE UNTIL IT IS FULL
- ADJUST THE WATER LEVEL IN THE WASHING MACHINE TO SUIT THE LOAD
- WASH YOUR CAR ON THE LAWN AND USE A BUCKET (NOT A RUNNING HOSE)
- TAKE A SHOWER INSTEAD OF A BATH A SHORT SHOWER USES ABOUT A THIRD AS MUCH WATER AS A BATH.

AT WORK?

- REPORT LEAKING HOSES AND TAPS TO YOUR SUPERVISOR
- TURN OFF TAPS AND HOSES WHEN NOT IN USE
- DON'T OVERFLOW WATER TRUCKS WHEN FILLING UP
- ONLY PLACE WATER WHERE NEEDED
- DON'T OVER WATER THE ROADS
- WATER THE ROAD AT A SPEED THAT SUITS
 THE CONDITIONS
- MINIMISE THE USE OF WATER AND DETERGENT IN THE WORKSHOP AND FUEL BAY
- MINIMISE SPILLS THAT REQUIRE WATER TO CLEAN UP.

SEWER SYSTEM MAINTENANCE

In 2010, the Rio Tinto Utilities Network will be continuing the sewer cleaning programme.

Works will continue to clean out roots and other objects from sewer mains in Paraburdoo, Tom Price and Dampier, and inject a root removal agent to prevent tree roots from breaking into the mains in the future.

These works are designed to reduce the incidence of sewer blockages and overflows that occur, and improve the capacity of the sewer main system.

You can help — see 'Protecting the wastewater system' on this page.

OPERATING THE WATER AND WASTEWATER SYSTEMS

Rio Tinto's Iron Ore group operates water and wastewater systems in Tom Price, Paraburdoo and Dampier under an operating licence issued by the State Government, and regulated by the Economic Regulation Authority.

This licence and its associated Water Services Customer Charter outlines the levels of service that we are required to provide for water and wastewater systems.


These include

- Pressure at customers water meter = greater than 15 metres
- Flow at customers water meter = minimum of 20 litres per minute
- Time for provision of advice in response to a complaint / service enquiry = within one hour
- Response to sewer overflows = within two hours
- Provision of minimum notice for planned works (residential properties affected) = 48 hours
- Provision of minimum notice for planned works (commercial / industrial properties affected) = seven days.

We have internal targets to reduce water use and increase water efficiency.

- - n sen anna ann ann ann ann ann ann ann ann Than ann ann ann ann ann ann ann ann Thanna ann an Allandara

 - n an an an an ann an an an an ann an an Tha Bol North an an an an an ann an Ann an A



IMPORTANT INFORMATION

WATER CONSUMPTION & WATER RATES

There are two costs for water

- Property owners will receive an annual fixed service charge (referred to as 'water & sewerage rates'). The sewerage
 service charge isn't the same for everyone, it depends on the rateable value of your property.
- Property tenants receive a charge for the water used. The rate begins at a lower rate per kilolitre and goes up as you use more water. This is the normal water regulation pricing system for North Country areas. It aims to encourage water conservation and discourage excessive use of water (and it works!).

WATER REBATE

A Water Rebate is paid to compensate for the extra watering demands of gardens in the Pilbara. It is paid according to the table below and will be paid to all Iron Ore staff tenants through the payroll in July each year. You will receive a pro-rata rebate in your first and final year.

	Kls / annum
Dampier	300
Tom Price	350
Paraburdoo	450
Karratha	377.4

The Water Rebate is based on the requirements of a house or duplex and is not applicable to other types of dwellings such as town houses, flats and home units.



CONTACT DETAILS

Rio Tinto Customer Service Parker Point PO Box 21 Dampier WA 6713 Freecall: 1800 992 777

WATER CONSUMPTION - YEAR TO DATE

Water consumption is charged on a Year to Date basis. You are charged on a tier level according to what level of consumption you are using.

(KL)	(\$/kL)
Up to 150	\$0.392
Over 150 but under 350	\$0.634
Over 350 but under 550	\$0.634
Over 550 but under 650	\$0.715
Over 650 but under 750	\$0.891
Over 750 but under 1150	\$1.435
Over 1150 but under 1550	\$2.063
Over 1550 but under 1950	\$2.377
Over 1950	\$2.763

Rio Tinto's Iron Ore group reserves the right to vary these rates, subject to the approval of the Economic Regulation Authority.

ACCOUNTS


You will be sent water-usage accounts in the months following our quarterly reads. Meters are read at the end of February, May, August and November.

WE NEED YOUR FEEDBACK

Our annual customer questionnaire will be coming to your letterboxes shortly so keep your eye out. The survey allows you to provide comment on the water and sewerage systems currently provided in your town. Please take the time to fill this out and return it as your feedback is very valuable in ensuring we efficiently manage these systems.

GENERAL INFORMATION

Sometimes our meter readers may not be able to access your meter — for example if there is a dog on the property, or you have locked gates etc. If you receive a card saying 'We could not access your meter today' please call us on 1800 992 777 as soon as possible so we can obtain an accurate reading, and you can avoid an assessed consumption.



Received

Rio Tinto

WATER AND SEWERAGE SERVICES QUESTIONNAIRE

You are invited to provide comment on the water and

sewerage services currently provided to you. This information will only be used to assess customers' expectations of levels of customer service, and to allow customers to notify the supplier of any water and sewerage service problems that they may be experiencing. Please note that the information will remain confidential.

WATER SERVICES

- Do you know which organisation supplies you with water? (please tick)
 - Water Corporation
 - Rio Tinto (Hamersley Iron)
 - Water Authority
 - Other (please specify)

Don't know

 Which of the following statements best describes how much you know about your water supplier's minimum standards of service? (please tick)

I know nothing about my water supplier's minimum standards of service

- I am aware of the standards of service but know very little about them
- I know some of the aspects of the standards of service

I know a lot about the standards of service

Rio Tinto Customer Service Parker Point PO Box 21 Dampier WA 6713 Freecall: 1800 992 777

•	Do you have any issues or concerns supply in your area? (tick as many as			iter
lual		requi	iieu)	
	Dirty water/ Color			
	Bad smell			
	Bad taste			
	Hardness			
	Too much sediment			
	Other (please specify)			
res	sure and Flow			
	Water pressure			
	Water flow			
nter	Other (please specify) rrupted supply			
	Prime time interruption			
	Lack of notification			
the	Other (please specify) er (please specify)			
•	Has your water service been below of the following matters during the (please tick)			
	Y	'ES	NO	DON'T KNOW
	ter quality - cloudiness, taste, our etc			
odo	• •			

Reliability of supply

Have unrestricted access and usage

The cost of your water

Easy to understand accounts

Helpful and courteous staff

Dealing with the problem promptly

SEWERAGE SERVICES

- 5. Do you know which organisation supplies you with sewerage services? (please tick)
 - Water Corporation
 - Rio Tinto (Hamersley Iron)

Other (please specify)

Water Authority

Don't know

 Which of the following statements best describes how much you know about your sewerage supplier's minimum standards of service? (please tick)

I know nothing about my sewerage supplier's minimum standards of service

I am aware of the standards of service but know very little about them

I know some of the aspects of the standards of service

I know a lot about the standards of service

- 7. Do you have any issues or concerns over the sewerage supply in your area? (tick as many as required)
 - Sewerage odours
 - Sewerage overflow
 - Sewerage pipe blockage
 - Pollution of natural waterways
 - Concerns over where sewerage ends up

Treatment and disposal of sewerage wastes

Problems with sewerage system at your premises (leaks etc)

Problems in getting connected to sewerage/supply interruptions

Other (please specify) ____

 Has your sewerage service been below expectations ' on any of the following matters during the last six months? (please tick)

	YES	NO	DON'T KNOW
Overflows			
Blockages			
Odours			

CUSTOMER SERVICES

- 9. Do you know if your water / sewerage service provider has a Customer Charter? YES / Nu-
- 10. Do you know if your water / sewerage service provider has a Customer Complaints procedure? YES / NO

RESPONSE

To make sure we have responses from a good cross section of the community could you please answer the following:

SEX (please tick)	MALE	FEMALE	
AGE (please tick)	18 – 25	26 – 35	36 - 45
	46 - 60	60+	

NAME (optional):

ADDRESS (optional):

Thank you for your time. Please return this questionnaire in the return envelope provided.



WATER CONSUMPTION TIER RATES

Dampier, Paraburdoo and Tom Price 2001/2002

(kL)	(\$/kL)
Up to 150	\$0.392
Over 150 but under 350	\$0.634
Over 350 but under 550	\$0.634
Over 550 but under 650	\$0.715
Over 650 but under 750	\$0.891
Over 750 but under 1150	\$1.435
Over 1150 but under 1550	\$2.063
Over 1550 but under 1950	\$2.377
Over 1950	\$2.763

Hamersley Iron reserves the right to vary these rates, subject to the approval of the Office of Water Regulation.

Dampier

Hamersley Iron Utilities PO Box 21 DAMPIER WA 6713 Ph: 1800 992 777 Fax: (08) 9143 5280

Perth-Accounts Receivable

Hamersley Iron Accounts Receivable GPO Box K829 PERTH WA 6843 Ph: 1800 992 777 Fax: (08) 9327 2422







USING OUR CUSTOMER TELEPHONE SYSTEM

Dial – 1800 992 777

Welcome to the Hamersley Iron Utilities Telephone System

Press 1: for Service Difficulties and Faults (24 Hours) Make this choice when you have a water or sewerage service fault or difficulty.

> *Please remember, if a water service problem appears to be on your side of the water meter then the fault is your responsibility.

Press 2: for Bill Enquiries (Mon-Fri 8.00am – 3.30pm)

Make this choice if you require assistance with the amount charged on your bill and for late payments. Your call will be directed to Accounts Receivable, Perth.

Press 3: for Other Enquiries (Mon-Fri 8.00am – 3.30pm) Make this choice for all other enquiries except complaints. Your call will be directed to Customer Services, Dampier.

Press 4: for Customer Complaints (Mon-Fri 8.00am – 3.30pm)

Make this choice if you wish to make a complaint regarding your service. Your call will be directed to Customer Services, Dampier.

Press 5: for Account Payments (24 Hours)

Make this choice if you wish to make a payment by Australia Post Bill Payment System.

Please keep this brochure for your records.

Things like grease, fat and food scraps aren't meant to go down kitchen sinks. They can cause blockages that require costly repairs, as well as have a negative impact on the environment. By binning these items instead, you'll ensure the community's wastewater system keeps running without a problem.

RioTinto

You'd be surprised what some people flush down the toilet.

Disposable nappies, toys, cotton buds and sanitary products are just some of the items that congest our sewerage system. Not only can these blockages require costly repairs, they can impact the health of our community and environment. Remember: bag and bin these items and only flush human waste down the loo.

> RIO TINTO



Conditions for Connection

Version 2 – June 2009

Rio Tinto Utilities - Your Local Water Utility

Water Service Connections

If our water main is available to your property and has enough capacity, we will install your new water service connection within 10 business days after receiving your application and payment.

In all other cases, applications for water service connections will be considered subject to engineering and financial assessment. An outcome will be provided within 10 business days of your application.

Applications for water services can be made at our Dampier Customer Services Office.

The following notes apply to your application:

- The area where the water meter is to be installed is to be clear of obstructions.
- The water service connection will be installed 500mm from the side boundary that you nominate on your application.
- Where the main is located on the far side of any road, the water supply connection will not be installed opposite a tee junction or private driveway.
- If you wish to relocate your service (and if it is possible to do so), all costs will be charged to you.

Wastewater Connections

If our sewer main is available to your property and has enough capacity, we will install your new sewer service connection within 10 business days after receiving your application and payment.

Applications for wastewater connections can be made at our Dampier Customer Services Office.

The following notes apply to your application:

• You will need a licenced plumber to carry out your plumbing work.


Commercial / Industrial Wastewater

If you wish to discharge industrial or commercial wastewater, you will need to contact the Dampier Customer Services Office.

Rio Tinto will enter into an agreement with you, which will ensure that the wastewater complies with regulations.

Contact Details

Rio Tinto Utilities Customer Service Parker Point PO Box 21 Dampier WA 6713 Freecall: 1800 992 777



UTILITIES DIVISION

WATER SERVICES ASSET MANAGEMENT SYSTEM

WATER QUALITY MANAGEMENT MANUAL

Document Control

Issue	Revision	Prepared By	Reviewed By	Approved By	Signed	Date	Reason for Changes
A	0	H Bennett	P Promuitz	A Mughal		16/3/05	First Print Draft
А	1	H Bennett	P Proinnitz	P Promuitz		26/8/05	Brockman, Marandoo, Rhodes Ridge and Yandi information inserted
В	. 0	H Bennett	D Stevens	D Stevens		14/9/06	Cape Lambert / Pannawonica added
С	0	H Bennett	D Stevens	D Stevens		29/12/06	Annual review - Laboratory details amended
D	0	H Bennett	D Stevens	D Stevens		18/12/07	 Substitute Dept of Water for Waters and Rivers Commission at Clause 4.2.4.2.
							 Substitute House 699 for House 700 for Paraburdoo in sampling points (page 15)
E	0	H Bennett	P White	P White		30/9/08	Complete revision for full adoption of 2004 Australian Drinking Water Guidelines
F	0	H Bennett	P White	P White _		4/1/2010	Revise sampling regime 4.7.1

CONTENTS

Page No

Distribution List	3
1.0 INTRODUCTION	4
1.1 Purpose	4
2.0 OBJECTIVES	
2.1 Plan objectives	5
2.2 Framework for management of drinking water quality	5
3.0 COMMITMENT TO DRINKING WATER QUALITY MANAGEMENT	6
3.1 Drinking water quality objectives	6
3.2 Regulatory and formal requirements	7
3.3 Key stakeholders	8
4.0 SYSTEM ANALYSIS AND MANAGEMENT	9
4.1 Assessment of drinking water supply systems	9-16
4.2 Risk assessment	17-20
4.3 Preventative measures	21-23
4.4 Critical control measures	24
4.5 Operational criteria, monitoring and corrective action	25
4.6 Materials and chemicals	26
4.7 Drinking water quality monitoring plan	27-29
4.8 Incident and emergency response protocols	30
5.0 SUPPORTING REQUIREMENTS	31
5.1 Reporting	31
5.0 REVIEW	32

APPENDIX 1 - Safe working procedures for water sampling

APPENDIX 2 - Chain of custody form

APPENDIX 3 – PRT's

Value of

ALC: NO.

Ę

APPENDIX 4 - Microbiological monitoring

APPENDIX 5 - Amoeba response protocol

APPENDIX 6 – Health related chemicals / pesticides response protocol

APPENDIX 7 - Water Quality Sampling Parameter Matrix

APPENDIX 8 - Training package

WATER QUALITY MANAGEMENT PLAN

DISTRIBUTION LIST

General Manager Utilities

Manager Networks

ĺ

ł.

Superintendent Networks Inland Superintendent Networks Coastal Supervisor Networks Dampier Supervisor Networks Paraburdoo Supervisor Networks Tom Price Supervisor Networks Pannawonica Supervisor Networks Cape Lambert Planner Networks Dampier Planner Networks Paraburdoo Planner Networks Tom Price Jones and Paull Plumbers Dampier Byblos Construction Tom Price / Paraburdoo Specialist Reliability Engineer Networks Specialist HSE Utilities

WATER QUALITY MANAGEMENT PLAN

1.0 INTRODUCTION

The Water Quality Management Manual has been developed as part of the requirements of the Water Services Operating Licence (town water supply systems) and Asset Management Plan, for compliance with the Mines Inspectors directives with regard to Mine site potable water quality, and for control of Legionella in accordance with Rio Tinto Standard B8.

This manual was prepared to provide guidance information on characteristics which are to be tested, sampling procedures and frequencies, testing regimes and water quality monitoring procedures required to comply with the requirements of the 2004 Australian Drinking Water Guidelines.

1.1 Purpose

- Caper

and a

الدور

The purpose of the manual is to ensure that a safe and reliable water quality supply is provided to town customers within Utilities Networks licence area, and to mine and ports supplied by Utilities Networks.

4.3 Preventative measures

4.3.1 Existing measures / multiple barriers

Multiple barriers are used for the progressive reduction of risk to the water source and to prevent contamination of the water supply. Each barrier commences at the water source and progresses through abstraction, treatment, and distribution.

The selection of barriers is dependent on risk assessment, practicality, potential cost and benefits and impacts on other stakeholders. A number of barriers are used by Rio Tinto Utilities as follows:

1. Catchment management

All raw water is abstracted from groundwater bores, where the risk of contamination is low.

2. Groundwater management

Groundwater management is controlled by the Department of Water.

Groundwater management is administered by Rio Tinto by 'Groundwater Operating Strategies', which are agreements between Pilbara Iron and Department of Water detailing abstraction and monitoring requirements, and reporting by both parties (refer IEMS system and Appendix I0).

New water sources are determined by testing by hydrogeological consultants or Rio Tinto hydrogeological staff.

All bores are constructed by experienced drilling contractors.

Bores are constructed so as to prevent contamination of the water supply and aquifers.

3. Water treatment processes / disinfection

Water treatment in Tom Price, Paraburdoo and Pannawonica is limited to disinfection by chlorine, with the exception of Paraburdoo bore PTP9, which uses pressure filters for the removal of iron and manganese.

The water supply to Dampier and Cape Lambert is treated and disinfected by the Water Corporation.

Levels of chlorine in the water are monitored using online instrumentation and regular testing.

Marandoo water supply is disinfected by ultraviolet light.

4. Detention in protected storage tanks

Following disinfection, water is temporarily stored in roofed storage tanks.

Access to storage tanks is controlled. Unauthorised access is controlled by security fences and locked gates.

Tanks are sealed to prevent access by birds and vermin.

5. Protection and maintenance of the distribution system

The structural integrity and cleanliness of water mains are managed using the SAP system, and includes procedures for preventative and corrective maintenance (eg chlorine system effectiveness – refer PMO1).

The disinfection process imparts a residual level of disinfection in the water mains, and this is monitored through regular testing. Chlorine testing is carried out on water taken from the designated sample points on a weekly basis. The testing is carried out in-house on equipment held at the Paraburdoo, Tom Price and Dampier offices. Two test methods exist; a simple colour test based upon addition of an indicator, and an electronic analyser and can be used for cross checking purposes. In addition, continuous online monitoring of chlorine levels is recorded on CITECT at Paraburdoo and Tom Price.

This testing indicates the effectiveness of the disinfection process.

Operational and maintenance manuals are available for all chlorination sites.

A dedicated team of Rio Tinto Maintainers is responsible for operational monitoring and maintenance at Pannawonica, Paraburdoo and Tom Price. Contract Maintainers are responsible for operational monitoring and maintenance at Cape Lambert and Dampier.

Annual leak detection programs are used to determine potential leaks and bursts in the town mains systems.

Diesel backup pumps are being purchased to prevent outages in the case of a power failure.

New mains are disinfected following construction.

6. Consumers

High risk services (as identified by the requirements of AS3500) are fitted with RPZD (reduced pressure zone device) backflow prevention devices, which are tested annually (refer Backflow Prevention file and PMO1).

Safe Work Procedure





Title: POTABLE WATER SAMPLING (MICROBIOLOGICAL)					Page: 2
Doc	ctrl N	lo: W&S 6.03	vision:1	Date: 18.5.2008	
2.		Aims and Objectives	The aim of this SWP is to provide an accurate method for the sampling of Potable Water (Microbiological)		
3.		Safety Notes			
	3.1	Safety	Australian Standards 5667		
	3.2	PPE Requirements	Safety Glasses, Steel Toe Cap Boots, Long Sleeve Shirt, Long Pants, Sun Hat, Chlorine Tester (with DPD Tablets), 2 Foam Eskies, 3 Custody Forms (1 per Esky, 1 Rio Tinto Copy) 1 Roll of masking Tape, Sample Bottles (2 per sample point) Ballpoint Pen (not felt tip), Propane heating Torch, 2 Plastic Bags, 1 Freezer Brick (wrapped in paper towel), I Airfreight Con Note, PathWest label		
4.	3.3	<i>Training Required</i> Procedure	HWP/ Driver Awareness		

Procedure

RioTinto

		Job Steps	Critical Safety/ Environmental/ Efficiency Steps
	1.	Prior to commencing ensure enough	Sampling to be carried out only on Mondays, Tuesday or Wednesdays. (to ensure samples are analysed next day)
	2.	Check sample bottles have the correct sample ID	Sample ID with the suffix "A" is for Amoeba & Naegleria
	3.	Run the tap for 3 minutes	
•	4.	Flame sterilise sample point (tap)	Direct the flame around the outside and inside of the outlet. To ensure complete sterilisation.
;	5.	Run the tap for 3 minutes	
(6.	Measure total Chlorine level	
-	7.	If total chlorine level is less than 0.2ppm, run sample tap for 2 minutes, and then repeat step 5. Continue running tap and measuring chlorine until minimum chlorine readings of 0.2ppm is achieved	
Ę	8.	Record chlorine level on custody form	

P.__edures.doc

Safe Work Procedure

UTILITIES NETWORKS



Title: POTABLE WATER SAMPLING (MICROBIOLOGICAL)

Page: 3

	Revision: 1	Date: 18.5.2008
ייים האפשמה המהוג המשמה או האינו איני איני המהוג או המלומי איני איני מושמר איני איני איני איני איני איני איני א איני איני	n management (" " alexandres ("), son and an	

4. Procedure Continued.....

(10) Int

	Job Steps	Critical Safety/ Environmental/ Efficiency Steps
	9. Draw off sample immediately	Fill the sample bottle leaving a small air space in the bottle. Do not over flow the bottle as this may
ľ	10. Pack all coliform samples in Esky with freezer brick	displace the sodium thiosulphate
	11. Pack all amoeba / naeglaria samples in Esky <u>without</u> freezer brick	
	12. Fill out custody forms, seal in plastic bag and place one in each Esky	Custody forms must be protected from moisture
	13. Seal up both eskies with masking tape	Tape Eskies together to prevent loss in transit
	14. Fix self adhesive label and con note to sides of each Esky	
	15. Deliver eskies to Airfreight agent	Return 3 rd custody form and con note copy to team administrator
-		
See.		

U ...lities Division/Utilities/Utilities - Networks/Networks Inland/Paraburdoo/Paraburdoo Safe Work Procedure Register/Networks Safe Work Procedures.doc

Safe Work Procedure





Title: POTABLE WATER SAMPLING (MICROBIOLOGICAL

Page: 4

Doc Ctrl No:W&S 6.03		Revision:1	Date:18.5.2008
5.	Reference	AS/NZS 5667.5: 1998 Water quality – S 1987 NHMRC Guidelines for Drinking V	
		1996 Australian Drinking Water Guideli Water Sampling doc. <i>U: Utilities/Water</i> Water Sampling Program doc. <i>U: Utilities/Water/Water Sampling progr</i> Water Quality Management Manuel	
		(infrastructure) Issue D 18.12.07	

6. Appendices

6

(

U:\Utilities Division\Utilities\Utilities - Networks\Networks Inland\Paraburdoo\Paraburdoo Safe Work Procedure Register\Networks Safe Work Procedures.doc

Potable Water Microbiological Testing Guidelines

Parameter to test for	Guideline limits	Who is to be notified of the results	Who is to be notified if the results exceed the guidelines
Total coliforms. Thermo tolerant coliforms. Amoeba. Naegleria. Legionella Colour Turbidity	Total coliforms = <1 Thermo tolerant coliforms = <1 Amoeba = 0 Naegleria = 0 <10	Specialist Reliability Engineer – Utilities Networks Quarterly – Economic Regulation Authority (ERA) & Health Department of WA (HDWA)	Superintendent Utilities Networks. Dependent on characteristics – ERA & HDWA

Collect samples and prepare for transportation as follows:

Cape Lambert

Collect the samples on a Tuesday and prepare for transportation, drop off at the Main Warehouse prior to 13:30 for pickup by TNT Express for delivery to the Karratha airport.

Attach an orange TNT Domestic Prepaid consignment document to the esky's using a Rio Tinto Service Order number as the Customer Reference, enter 21375897 (Rio Tinto account number) in the Account Number section of the document.

Dampier

Attach an orange TNT Domestic Prepaid consignment document to the esky's using a Rio Tinto Service Order number as the Customer Reference, enter 21375897 (Rio Tinto account number) in the Account Number section of the document.

Deliver the esky's to the Dampier Post Office before 14:00 hours on the day the samples were collected, the esky's must be on the first available flight to Perth for the samples to be tested the next day.

Pannawonica

The method of transportation between Pannawonica and Karratha is to be determined.

Attach an orange **TNT** Domestic Prepaid consignment document to the esky's using a Rio Tinto Service Order number as the Customer Reference, enter 21375897 (Rio Tinto account number) in the Account Number section of the document.

The samples are to be on the first available flight to Perth on the day the samples are taken for testing the next day.

Paraburdoo

Attach an Australian Air Express consignment document to the esky's using a Rio Tinto Service Order number as the Customer Reference, enter 21375897 (Rio Tinto account number) in the Account Number section of the document.

Deliver the esky's to the Paraburdoo Post Office before 14:00 hours on the day the samples were collected, the esky's must be on the first available flight to Perth for the samples to be tested the next day.

Tom Price

Attach a TNT consignment document to the esky's using a Rio Tinto Service Order number as the Customer Reference.

Deliver the esky's to the Lestok yard in the LIA, before 14:00 hours on the day the samples were collected, as the esky's must be on the first available flight to Perth for the samples to be tested the next day.

Further information can be found in the Pathwest Microbiology document attached at Appendix 1.

Sample locations are listed below.

Residual chlorine data is to be entered on the Pathwest Chain of Custody Sheet.

Colour and turbidity results are to be analysed in accordance with attached Appendix 3 and 4.

Sample Locations – all sites

Site	ID	Sample Location
Cape Lambert	CL01	Main Administration
	CL02	Control Room
	CL03	Power Station
	CL04	Ore Wharf
3	CL05	Gatehouse
	CL06	F Troop
Dampier	DAMOI	n.t. n.: :
Dampier	DAM01 DAM02	Parker Point main
	DAM02	Parker Point dumper
		Town Training centre
	DAM06 DAM07	EII Dumper 7 Mile
	DAM07 DAM08	
	DAMU8	Dampier town main
Pannawonica		11 Maitland St
		7 Harding Way
		27 Peedamulla Way
		Town Office
		Town Workshop
		Mine Admin
		Mine Warehouse
		Mine Alpha 16
-		Laydown area
		Luydown area
Paraburdoo	1	Collector tank 1
		Town tanks
		Robe Ave
		House 699
		Airport
		PS2 outlet
		Gas turbine office
		ER main tank
		Channar collector fank
		Channar MOC pre filter
		Channar MOC post filter
		Turee Creek collector tank
P		
fom Price		Southern Fortescue collector tank
		Town tanks
		Golf Club
		Area W
		Hardy River collector tank 1
		Mine Tank
		Mine – Utilities
		Mine – MOC
		Mine – Concentrator
		Mine – BME camp
	1	Turee Creek collector tank
Arrandoo		Manan Jan Lana
larandoo		Marandoo bore
		Main tank
		Crib room
e new state of the second state of the	· · · · · · · · · · · · · · · · · · ·	Lab sink
		Workshop kitchen

Document in mydocs\$ heath.bennett\WATER QUALITY\Water Quality Management Manual Issue E 2008 Final.doc Pg 3 of 17

ISOLATIONS: None

PPE REQUIREMENTS:

SAFETY NOTES:

Clear flammable materials from around the sample point before using the blowtorch.

MATERIALS:

First aid kit Gas blowtorch Hot work permits Sample bottles Esky Freezer bricks

Document in mydocs\$heath.bennett\WATER QUALITY\Water Quality Management Manual Issue E 2008 Final.doe Pg 4 of 17

b) Chlorine

Test the disinfection free chlorine levels at the test points as below and as shown on the Maintenance Order.

Tests are to be completed every week (fortnightly at Cape Lambert and Pannawonica).

Sample locations are as follows:

Site	ID	Sample Location
Cape Lambert	CL01	Main Administration
	CL02	Control Room
	CL03	Power Station
	CL04	Ore Wharf
	CL05	Gatehouse
	CL06	F Troop
Dampier	DAM01	Parker Point main
	DAM02	Parker Point dumper
	DAM03	Town Training centre
	DAM06	EII Dumper
	DAM07	7 Mile
4	DAM08	Dampier town main
Pannawonica		11 Maitland St
		7 Harding Way
		27 Peedamulla Way
		Town Office
1		Town Workshop
		Mine Admin
	1	Mine Warehouse
		Mine Alpha 16
		Laydown area
Paraburdoo		T
Paraburdoo		Town tanks
	÷	Robe Ave
		House 699
		Airport
		PS2 outlet
		Gas turbine office
		Channar PS outlet
		Channar MOC
Tom Price		Town tanks
101111100		Golf Club
		Area W
		Mine Tank
		Mine – Utilities
		Nine - Moc
		Mine – Concentrator
		Mine – BME camp

Carry out the test using the Palintest Pooltest 3 Photometer test instrument, or other approved device. Refer Appendix 2.

The test results are to be sent to:

Specialist Reliability Engineer Pilbara Iron PO Box 114 Paraburdoo WA 6754

 Ph
 08 91434410

 Mob
 0409 291013

 Fax
 08 91434976

 Email
 heath.bennett@riotinto.com

See Table 2 for licence limit values, contacts for the notification of routine test results or of results which exceed licence limits/guidelines.

Contact for ordering Pooltest 3 equipment and tablets:

D4 Data Pty Ltd >/29 Parrs Road .roydon Vic 3136 Phone +61 3 9725 6637 Fax +61 3 9723 7283 web d4data.com.au email@d4data.com.au

LOCATION

Refer to Site map if unsure of location.

MATERIALS:

First Aid Kit Key WSR202 Palintest Pooltest 3 Photometer Test Instrument Palintest DPD No 1 Tablets – Photometer Grade Round Test Tubes, 10ml glass (PT 515) White rod for crushing the tablet

Table 2 Potable Water Chlorine Testing Guidelines							
Parameter to test for	Guideline limits	Who is to be notified of the results	Who is to be notified if the results exceed the guidelines				
Disinfection free chlorine	Range 0.5 – 2.0ppm at point of treatment.	Specialist Reliability Engineer	Superintendent Utilities Networks.				
	Minimum at consumer outlet 0.2ppm.						

Appendix 1

PATHWEST LABORATORY MEDICINE WA INSTRUCTION SHEET

1.0 INTRODUCTION

All water samples for microbiological analysis must be collected in the bottles supplied by PathWest, unless the sample is of commercial prepackaged water or a similar product.

When collecting samples for different parameters (i.e. chemical, physical etc) from the same sampling point, always collect the samples for microbiological examination first. Prelable bottles with a waterproof pen prior to sampling and keep bottles unopened until sample collection is performed.

To assist in the sorting of samples at the laboratory, the letter "A" should be placed after the sender number on the amoebae bottle. (See W-A request form)

.0 COLLECTION

NOTE: At no time should the sampler's hand come into contact with the cap or neck of the bottle.

The following sample types are collected into a 250ml plastic bottle.

Samples requiring analysis for:

- Total Coliforms
- Thermotolerant Coliforms
- Thermophillic Amoeba
- Thermophillic Naegleria



All samples must be transported in eskies. If samples are suspected to have a high bacterial count (i.e. sewerage, drains, effluents etc) they must be transported in separate eskies to drinking and pool water samples.

Samples for bacteriological analysis are to be transported with ice brick(s). One or more ice bricks need to be added depending on the climatic conditions as the sample MUST maintain a temperature of $4*C \pm 2*C$. This is to prevent the multiplication of bacteria which may result in false bacterial counts.

For samples requiring analysis for amoebae, the samples must be sent at ambient (room) temperature. The esky must not contain an ice-brick as the chilling of the sample will kill any viable amoebae.

PATHWEST LABORATORY MEDICINE WA INSTRUCTION SHEET

Whenever possible, samples should arrive at the laboratory on the day of collection, preferable before PM. Whilst this is possible for samples collected in the vicinity of the metropolitan area, it is clearly not always feasible if samples are from country areas. Samples form country areas must arrive <u>no later than</u> the day after collection, i.e. within 24 hours.

3. DOCUMENTATION

Samples are to be accompanied by a correctly filled out and appropriate request form as detailed below:

- i) Green (WA) form, which is used when samples are to be tested for amoebae and bacteria, or amoebae only. (The letter "A" indicates Amoebae).
- ii) Blue (WB) form, which is used when samples are to be tested for bacteria only. (The letter "B" indicates Bacteriology).

INFORMATION REQUIRED ON REQUEST FORM	INFORMATION REQUIRED ON THE BOTTLE
The boxes on the top of the request form must be ticked.	Sender No. or Sender's own reference number.
Senders Authority and address in full.	Site Code (if given)
Any relevant senders comments or fax number	Point of Collection/Source
Tests required	Description of site and source of water
Date collected	Site location details (e.g. name of swimming pool)
Signature	Date & Time of Collection
Site code (if given)	Transportation Temperature (4* C or ambient)
Point of collection	Sender's Name (Shire, City council etc.)
Treatment, temperature and pH (if relevant)	

NOTE:

- a) Separate forms must accompany samples from each swimming location.
- b) Potable waters and effluents must not be written on the same request form.
 - c) The information on the bottle must be the same as on the request form.

4. EQUIPMENT

Sample bottles, eskies and ice bricks can be obtained by sending a facsimile transmission to PathWest Supply Department [Fax No. (08) 9224 7036]. Please state the number of each item required, a return postal address (as a post office box number is not sufficient), with your name and phone number and the Courier company you wish to use. Request forms can be obtained by writing a message on a request form accompanying sample delivery.

Alternatively, sampling equipment and documentation may be collected directly from the laboratory.

5. CONTACT PERSON

For a full set of instructions or assistance please contact the Senior Scientist in charge of the laboratory on (08) 9346 2583.

CHAIN OF CUSTODY FORM

(

(

U:\Utilities Division\ Utilities\Utilities - Netv M

Document in mydocs\$/heath.bennett/WATER QUALITY/Water Quality Management Manual Issue E 2008 Final.doc

GHASP	PULL N) 65	00 482 St	ини и о b J		ILNL	A A 11 to noi	eivid A	
		69	2 562 00	0 17 NS	the structure of the st	E Cole I	AT lo noi	aivid A	
	3 PATH CENTRE	ONER HOSP K BLOK	Sate Postcode	^{thone} 08 93462583	Saturday or weekend delivery or after hours pick up services are only available using "Sameday Upgrade". Please complete precial instructions. Additional charges will appy for light bulky items (cubit 250m ³) and items exceeding weight limit.	Received in good driver, Receiver's Signature	2 1 3 7 5 8 9 7	Delivery car no. Time INT Australia Pty Limited ABN 41 200 455 269	Product No. 833952
	Receiver WATER EXAM//LAB	CHARLES GAIRDENER	ay MEDLANDS	CONTECH IN CHOE	SAMEDAY SAMEDAY UPGRADF Items (ubic 2)	Receiver's Name (Print)	Date Time Time Trime Thr USE ONLY	Pick up car no. Time k govern this Contract. TNT Exprest, a division of	
Decvenes. SKG	South Transmission of the first free from the first of th		Party of the second static framework and static framework and static framework and static	FICUR 88 91 43 5556 01		DANGERCUS GOODS: This contignment note MUST NOT be used for hipping DANGEROUS OR HAZARDOUS goods. Contact your nearest TNT office for further. Information. Anternearth We submit the good is described above for sample above for standard Terron. And Condition of Contract overflast and TNT's facto Agreement (fr applicable) apply to the carriage of these good.	Professional and the second	I Cuble Measurement cmX cmX cm ² m ³ Pick up car no. Time Delivery car no. Time Time Time The Nort COMMON CARRIERS. The Standard Terms and Conditions of Contract on the lack govern this Contract. TNT Express. 2 division of TNI7 Australia & Py Limited ABN 41 000 453 269	
E	Peril-BARA	20 20 20		B CONTRANSA		DANGEROUS GOODS: This content note MUST NOT be used for hipping DANGEROUS OR HAZARDOUS goods. Appendent We automit the goods destribut and Conditions of Contracts overflast and TNI carriage of these goods.	Service's Signature.	Total Cubic Measurement WE ARE NOT COMMON	

• •••

Document in mydocsSheath.bennett\WATER QUALITY\Water Quality Management Manual Issue E 2008 Final.doc

Pg 10 of 17

i.

1

SENDER'S INSTRUCTION AND ADDITIONAL INFORMATION ON SUBMISSION OF SAMPLES

- 1. This request form W-A is to be used for all samples that require investigation for amoebae. Samples for bacteriological analysis only should be submitted on form W-B.
- 2. Please write clearly in black biro.
- 3. Forward samples in insulated containers to arrive at the laboratory no later than 16.00 hours Monday-Friday. Samples for amoebae investigations must be submitted at ambient temperature. The corresponding samples for bacteriological analysis must be submitted chilled (below 5*C). This can be achieved by using ice-bricks. Samples must not be frozen.
- 4. Whenever possible the elapsed time between collection and microbiological analysis should not exceed 6 hours. Where problems with sample collection and transport exist, the elapsed time may exceed 6 hours but should not exceed 24 hours.
- 5. Samples with potentially high bacterial counts (e.g. sewage, effluent and drains) must not be transported in the same container as drinking water or swimming pool samples.
- 6. For routine analysis, the range of tests undertaken will be based on existing standards or guidelines, information provided by the sender and previous laboratory findings. Any non-routine test parameter required must be requested in writing in 'Sender's Comments,' or by direct communication with a scientist at the laboratory.
- 7. If the water or effluent has received any disinfection treatment, please specify the method or combination of methods used, i.e. chlorine, chloramines, bromine, ozone, UV, etc, in the space provided on the form.
- 8. For samples of treated and untreated drinking water, the laboratory may report background counts of non-coliform organisms that proliferate into visible colonies on the culture medium. The bacteria enumerated in this way may represent only a small fraction of the total bacteria likely to be present and should not be confused with heterotrophic/standard plate count. Background counts per 100 ml are reported according to the following key:
 - = 0 ±= 1-50 + = 50-125 ++ = 125-250 +++ = >250 * = Due to a high background the count may be underestimated.
- 9. For repeat samples, or where unsatisfactory laboratory results have been obtained, please indicate previous laboratory numbers, dates or sampling and site codes in 'Senders Comments' space.
- 10. Please use correct site codes/reference numbers whenever possible. This speeds up the processing of the samples and reduces the chance or errors.
- 11. If the water or effluent contains high levels of copper, zinc, or is thought to contain high levels of heavy metals please advise the laboratory so that a chelating agent may be incorporated in the sampling bottle.



PRT1 - FOR WEEKLY WATER QUALITY SAMPLING

REVISION	WRITTEN BY	CHECKED BY	DATE	REASON FOR CHANGES
0	J Taylor	W Power	Jan03	Original
1	J Taylor	D Pampano	Dec05	Change contact details
2	H Bennett	J Taylor	Sept 08	Revision for 2004 ADWG

INSTRUCTIONS

a) Microbiological

Refer to SJP W&S 6.03 - Potable Water Sampling Microbiological.

Collect the water samples for testing from the locations shown below and on the Maintenance Order.

The samples are to be collected weekly (fortnightly for Cape Lambert and Pannawonica).

Collect the samples as detailed in SJP W&S6.03 Potable Water Sampling, ideally on the 1st working day of the week, as samples are to be tested by PathWest within 24 hrs of them being collected.

If the samples are taken later than Wednesday PathWest will need to be contacted directly to allow them make arrangements for the testing to be carried out in the required time frame.

Issue a Hot Work Permit before applying heat to the sample point piping, ensure all flammable materials have been cleared from the sample point site.

See Table 1 for licence limit values, contacts for the notification of routine test results or of results which exceed licence limits/guidelines.

Attach the printed PathWest address document to the esky's.


fhe test results will be sent to the "Specialist Reliability Engineer" in Paraburdoo by PathWest. The test results will be entered into the database by the engineer.

Cross out any items not required when reordering water sampling equipment from PathWest using the standard fax form.

PathWest Stores contact details: Phone: 08 9346 2167 Fax: 08 9381 7092

PathWest Technologist in Charge phone number is: 08 93462583.

Table 1





RIO TINTO UTILITIES NETWORKS

ASSET MANAGEMENT IMPROVEMENT PLAN

WATER AND WASTEWATER SERVICES

2010

Document Control – Change Register

1

Issue	Revision	Prepared By	Reviewed By	Approved By	Approver sign	Date	Description of Change
A	0	D Piotto	P Promnitz	G Will		28/9/01	First print
B	0	H Bennett	P Promnitz	P Promnitz		11/6/04	Update to Section 4.2, 5.1, Insert Section 8.0
с 	0	H Bennett	P Pronnitz	P Promnitz		18/11/04	Insert Section 4.3, Appendix D, Appendix E
D	0	H Bennett	A Mughal	A Mughal		15/3/05	Insert Asset Effectiveness flowcharts - Section 4.1
E	A	H Bennett	D Stevens / A Nuttman	D Stevens		17/9/06	Complete Revision to Pilbara Iron Asset Management Manual format
E	A - Q1	H Bennett	P White	D Stevens		27/4/07	2007 Quarter 1 review completed
E	A - Q2	H Bennett	P White	D Stevens	· · · · · · · · · · · · · · · · · · ·	29/6/07	2007 Quarter 2 review completed
E	A – Q3	H Bennett	P White	D Stevens		4/10/07	2007 Quarter 3 review completed
E	A – Q4	H Bennett	PWhite	D Stevens	·······	3/1/2008	2007.Quarter 4 review completed
E	A – Q1 2008	HBennett	P White	D Stevens		2/4/08	2008 Quarter 1 review completed
E	A – 2009/10	H Bennett	P White	PWhite		2/2/09	Annual revisions to be completed
E	B	H Bennett	P White	P White		4/1/2010	Annual review and update for 2010

.

Table of Contents

' i _ .

Introduction	3 - 4
A) Health and Safety	5
B) Environment	6
C) People	7
D) Training & Development Plan	8
E) Asset Planning	9
F) Equipment Maintenance Strategies	10
G) Budget and Manage Costs	11
H) Maintenance Work Management	12
I) Materials Management	13
J) Reliability	14
K) Performance Measurement	15
L) Capital Expenditure Plan	16
M) Audit and Review	17

Appendix 1 - Asset Management Process Flowchart

. . .

Appendix 2 – System Description Appendix 3 – Hazard Identification and Risk Estimation summary Appendix 4 - References

Distribution List

Position	Location
Manager Networks Services	Dampier
Networks Superintendent – Inland	Tom Price
Networks Superintendent – Coastal	Dampier
Specialist Reliability Engineer	Paraburdoo
Networks Supervisor (Water / CMS)	Dampier
Networks Supervisor	Pannawonica
Networks Supervisor	Paraburdoo
Networks Supervisor	Tom Price
Planner	Dampier
Planner	Paraburdoo
Planner	Tom Price
Asset Management Team	Perth

......

INTRODUCTION

.

Rio Tinto Networks - Strategic Asset Management Plan for Water Services

The Utilities Networks division was formed in 2008 from the former divisions of the old Utilities MRU, and is responsible for the provision of water, wastewater, electricity, air services, site communications, hydrocarbon management, housing and customer relations for the following sites:

- Cape Lambert Port
- Channar mine
- Dampier town
- Dampier ports (Parker Point and East Intercourse Island)
- Eastern Ranges mine
- Pannawonica town
- Paraburdoo mine
- Paraburdoo town
- Tom Price mine
- Tom Price mine
- Wickham town (not water and wastewater services)

The regulation of water and wastewater services for town services is provided by the Economic Regulation Authority (ERA), by a Water Services Operating Licence which was issued to Hamersley Iron in 2003.

The regulation of water and wastewater services for mines and ports, and for Pannawonica town conducted under the Mines Act.

The regulation of water and wastewater services for Wickham town is by the ERA, by a Water Services Operating Licence issued to the Water Corporation.

Operating Environment

The provision of mine and port water and wastewater services is required to maintain the operation (mineral processing, dust suppression etc) of Rio Tinto's iron ore mining activities. The maintenance of town services is required to provide appropriate levels of service to Rio Tinto employees and other residents who are housed in the towns.

Utilities Networks operates its water and wastewater services under two key performance areas:

- 1) Health, Safety and Environment (HSE)
- 2) Reliability

In relation to water and wastewater services, the HSE area covers water quality, wastewater quality, safe operation and maintenance of water and wastewater assets for customers, employees and other persons, the control of discharge to the environment, and the management of water services in a manner that does not adversely affect the environment.

The reliability area relates to the provision of water and wastewater services of a high standard of quality and continuity, with a minimum of breakdowns.

In this operating environment, Utilities Networks manages its systems to achieve these two goals, while not affecting the cost of water and wastewater services to its customers.

3

RIO TINTO NETWORKS ASSET REGISTER @ 2/1/2010

Major Asset	Area	Category	Asset description / type	Installation / upgrade date	Material	Condition	Planned replacement		
Paraburdoo Township	Northern borefield / CT1 / PS1	Water Supply	Northern borefield bores incl pumps / motors (x 11)						
	Northern borefield / CT1 / PS1		PTP1	1970					
	Northern borefield / CT1 / PS1		PTP2 - redrill	1988					
	Northern borefield / CT1 / PS1		PTP3	1970					
	Northern borefield / CT1 / PS1		PTP4	1970					
	Northern borefield / CT1 / PS1		PTP5 - redrill	1988					
	Northern borefield / CT1 / PS1		РТР7	1970					
	Northern borefield / CT1 / PS1		PTP8	1970					
	Northern borefield / CT1 / PS1		PTP9	1970					
	Northern borefield / CT1 / PS1		PTP10	1970					-
	Northern borefield / CT1 / PS1		PTP11	1970					-
									+
	Northern borefield / CT1 / PS1		Chlorination facility - PTP2	2009					+
	Northern borefield / CT1 / PS1		Chlorination facility - PTP9	2009					+
	Northern borefield / CT1 / PS1		PTP9 air compressor	2009					+
	Northern borefield / CT1 / PS1		PTP9 pressure filters	1982					+
	Northern borefield / CT1 / PS1		Northern borefield collector mains - 200mm / 350mm dia steel - 5km	1970	MSCL				+
	Northern borefield / CT1 / PS1		Bore electrical control cubicles	1970	MICOL				+
	Northern borefield / CT1 / PS1		Power supply to bores - pole / cables / TX	1970					+
	Northern borefield / CT1 / PS1		Collector tank 1 (CT1) - 650m3	1970	Steel				+
				1970	31661		2010 / 2011		
	Northern borefield / CT1 / PS1 Northern borefield / CT1 / PS1		Pump station 1 (PS1) - 2 x 200hp Power supply to PS1	1970			2010 / 2011		+
									_
	Northern borefield / CT1 / PS1		Chlorination facility - CT1	2009	11001				
	Northern borefield / CT1 / PS1		Trunk main PS1 to Town Tanks - 350mm dia steel - 3.3km	1970	MSCL				_
									_
	Town tanks		Town Tanks - 2 x 9ML	1970	Steel				_
	Town tanks		Power supply to town tanks	1970					_
	Town tanks		Chlorination facility - Town Tanks	2009					_
	Town tanks		Trunk main - Town Tanks to town - 500mm dia steel - 2.7km	1970	MSCL				_
	Town tanks		Trunk main - Town Tanks to mine - 350mm dia steel - 3.1km	1970	MSCL				_
	Town		Trunk main - town - 375mm dia steel - 2.7km	1970	MSCL				
	Town		Town reticulation mains - 200mm, 150mm, 100mm dia, incl associated valves and hydrants - 29km	1970	MSCL/AC/PVC		2010 = valves, 201	1 = mains	
	Town		Service connection pipework and water meters	1970					
	Town		Comms system for bores, PS, tanks etc	1970					
Paraburdoo Airport	Paraburdoo Airport	Water Supply	Bore PAP1 incl pump / motor	1973					
	Paraburdoo Airport		Bore collector main - 100mm dia steel - 0.5km	1973					
	Paraburdoo Airport		Bore electrical control cubicle	1973					
	Paraburdoo Airport		Power supply to bore - pole / cables / TX	1973					
	Paraburdoo Airport		Collector / fire tank - 132m3	2004					
	Paraburdoo Airport		Pump station - 3 x 2.2kw	2004					
	Paraburdoo Airport		Fire pump	1973					
	Paraburdoo Airport		Distribution pipework - to terminal etc - 100mm steel / PVC - 0.2km	2004	MSCL / PVC				
	Paraburdoo Airport		Fire system pipework - 200mm dia polyethylene	2006					
	Paraburdoo Airport		Chlorination facility	2006					1
	Paraburdoo Airport		Control system for bores, PS, tanks etc				2011		1
Paraburdoo Township	Para town sewer system	Sewerage	Sewer mains - gravity - 19km	1970 - 2009	VC / PVC / PE		Ongoing		1
	Para town sewer system		I/O property connections	1970 - 2009			Ongoing		+
	Para town sewer system		Sewer pump station No 2 (SPS2)	1970					1
	Para town sewer system		SPS2 controller	2009					+
	Para town sewer system		Power supply to SPS2	1970	1				+
	Para town sewer system		Sewer pump station No 1(SPS1)	1970	1		2010		+
	Para town sewer system		SPS1 controller	2008	1				+
			Power supply to SPS1	1970					+
	Para town sewer system	1	Pressure main - SPS1 to WWTP	1970					+
	Para town sewer system			1970	-		I		+
	Para town sewer system Para town sewer system								1
	Para town sewer system			1070					
	Para town sewer system Para town WWTP		Town wastewater treatment plant - Imhoff tank + 3 x waste stabilisation ponds	1970			0014		_
	Para town sewer system Para town WWTP Para town WWTP		Town wastewater treatment plant - Imhoff tank + 3 x waste stabilisation ponds Chlorination facility - WWTP	1980			2011		-
	Para town sewer system Para town WWTP Para town WWTP Para town WWTP Para town WWTP		Town wastewater treatment plant - Imhoff tank + 3 x waste stabilisation ponds Chlorination facility - WWTP Power supply to WWTP	1980 1970 / 2009			2011		
	Para town sewer system Para town WWTP Para town WWTP		Town wastewater treatment plant - Imhoff tank + 3 x waste stabilisation ponds Chlorination facility - WWTP	1980			2011		

Location	Major Asset	Area	Category	Asset description / type	Installation / upgrade date	Material	Condition	Planned replacement		
		Turee Creek borefield system		PBO1	1996					
		Turee Creek borefield system		PBO2	1996					
		Turee Creek borefield system		PBO3	1996					
		Turee Creek borefield system		PBO4	1996					
		Turee Creek borefield system		PBO5	1996					
		Turee Creek borefield system		PBO7	1996					
		Turee Creek borefield system		Bore electrical control cubicles	1996					
		Turee Creek borefield system		Power supply to bores - pole / cables / TX	1996					
		Turee Creek borefield system		Trunk main - Turee Creek borefield to Fines Plant - 37km	1996			2010		
		Turee Creek borefield system		Turee Creek collector tank	1996					
		Turee Creek borefield system		Turee Creek pump station	1996					
		Turee Creek borefield system		Power supply to Turee Creek pump station	1996					
		Turee Creek borefield system		Turee Creek surge tanks x 2	2005 / 2006					
		4W / Southern borefield system		Southern borefield - PMP5 bore - redrill	1988					
		4W / Southern borefield system		Bore electrical control cubicle						
		4W / Southern borefield system		Power supply to bore - pole / cables / TX						
		4W / Southern borefield system		Southern borefield collector mains - 0.3km	2004					
		4W / Southern borefield system		Trunk main - Southern borefield / 4W to Collector tank 6 - 3.1km	2006					
		4W / Southern borefield system		Collector tank 6 (CT6)	2006					
		4W / Southern borefield system		Trunk main - CT6 to CT2 - 1.3km	2006					
		4W / Southern borefield system		Trunk main CT6 to branch ST6A/B - 0.5km	2006					
		CT2 / PS2		Collector tank 2 (CT2)	1985					
		CT2 / PS2		Pump station 2 (PS2)	2009					
		CT2 / PS2		Power supply to PS2	2009					
		CT2 / PS2		Chlorination facility - PS2	2004					
		CT2 / PS2		Trunk main - PS2 to plant areas - 0.6km	2006					
					4000					
		PS3 / ST3		Pump station 3 (PS3)	1988					
		PS3 / ST3		Power supply to PS3	1988					
		PS3 / ST3 PS3 / ST3		Storage tank 3 (ST3)	1988					
		PS3 / ST3		Main from PS3 to ST3 - 0.7km	1988 1988					
Greater		PS37 ST3		1480 waterstand	1988					
Paraburdoo		ST6 / PS6 / Fines Plant area		Collector tanks ST6A/B - 2 x 1ML	2006					
		ST6 / PS6 / Fines Plant area		Pump station 6 (PS6)	2006					
		ST6 / PS6 / Fines Plant area		Power supply to PS6	2006					
		ST6 / PS6 / Fines Plant area		Fines Plant interconnection pipework, control valves etc	2006					
		ST6 / PS6 / Fines Plant area		Mains - ST6A to Process water tank - 0.2km	2006					
		STO/FOO/Filles Fiant alea			2000					
		Para Plant area		Plant area distribution / reticulation mains, hydrants - 5.1km	1970					
					10/0					
		Para comms		Comms system for bores, PS, tanks etc	1					
					1					1
Par	raburdoo Mine	Para mine sewer system	Sewerage	Sewer mains - gravity - 1km	1970-2009					1
		Para mine sewer system	Concidye	I/O building connections	1970-2009					1
		Para mine sewer system		Sewer pump station No 3 (SPS3)		<u> </u>				1
		Para mine sewer system		SPS3 controller	2009					1
		Para mine sewer system		Power supply to SPS3	1					1
		Para mine sewer system		Sewer pump station No 4(SPS4)	1					1
		Para mine sewer system		SPS4 controller	2009					
		Para mine sewer system		Power supply to SPS4	1					1
		Para mine sewer system		Sewer pump station No 5 (SPS5)	1			2010		1
		Para mine sewer system		SPS5 controller	2009					1
		Para mine sewer system		Power supply to SPS5	1					1
		Para mine sewer system		Pressure main - SPS5 to pit	1					1
		-			1	1			1	1
		Para mine sewer system		Pressure main - SPS4 to pit						

Major A	Asset Area	Category	Asset description / type	Installation / upgrade date	Material	Condition	Planned replacement		
				4000					
	Para mine WWTP SDU		Sewage disposal unit (WWTP) - extended aeration activated sludge package plant	1969					+
	Para mine WWTP SDU		Chlorination facility - WWTP - tablet feeder	2005					+
	Para mine WWTP SDU		Power supply to WWTP	1969					
<u> </u>	Plant MOC WWTP		Plant MOC WWTP sewage PS	2009					
	Plant MOC WWTP		Plant MOC WWTP	2009					
Channar Mine	Channar borefield	Water Supply	Channar bores x 3 incl pumps / motors	1000					+
	Channar borefield		CMP1 CMP2	1986 1986					+
	Channar borefield Channar borefield		CMP2 CMP3	1986					+
				1000					
	Channar borefield		Bore collector mains - 4.2km	1986					
	Channar borefield		Bore electrical control cubicles	1986					
	Channar borefield		Power supply to bores - pole / cables / TX	1986					
	Channar borefield		Trunk main - Turee Creek main to Collector tank (emergency backup) - 0.25km	2006					-
			Channer collector tank 200m2	4000					
<u> </u>	Channar collector / PS Channar collector / PS		Channar collector tank - 200m3 Channar pump station	1989 2008				<u> </u>	
	Channar collector / PS Channar collector / PS		Power supply to PS	2008					
<u> </u>	Channar collector / PS		Chlorination facility - Channar PS	2009					+
	Channar trunk main		Trunk main - Channar PS to main tank - 2.3km	1989					
	Channar main tank		Channar main tank - 4,200m3	1989					
	Channar main tank		Power supply to main tank	1989					+
	Channar plant pipework		Distribution pipework - to Plant, offices, workshops etc - 2.2km	1989					-
	Channar plant pipework		Plant areas pipwork - crusher, conveyors	1989					-
<u> </u>	Channar plant pipework		Fire system pipework	1989					1
	Channar plant pipework		Channar break tank - 22m3	2008					
	Channar 1 waterstand		Main to Channar 1 waterstand - 0.5km	1989					\square
	Channar 1 waterstand		Channar 1 waterstand - 60m3	1989					
	Channar 3 waterstand		Main to Channar 3 waterstand - 1km						+
	Channar 3 waterstand		Channar 3 waterstand - 60m3						
<u> </u>	Channar 3 waterstand		Main to Channar from Channar 3 to 94E waterstand - 3.5km						
	Channar 94E		Channar 94E waterstand	2008					
	Channar 94E		Comms system for bores, PS, tanks etc						
	Ndide - int la sur		Mideoist here CMDE	4000					-
	Midpoint bore Midpoint bore		Midpoint bore CMP5 Main to CMP5 - 0.6km	1986 1986				<u> </u>	
	Midpoint bore		Midpoint water / fire tank	2009					
<u> </u>	Midpoint bore		Midpoint pump station	2009					+
	Midpoint bore		Distribution main to midpoint conveyors / transfer station - 0.1km	1986					
	Midpoint bore		Power supply to CMP5 and midpoint PS	1986					
Channar Mine	Channar mine sewer system	Sewerage	Sewer mains - gravity - 600m	1989 - 2007					+
<u> </u>	Channar mine sewer system		I/O building connections	1989					+
	Channar WWTP SDU		Sewage disposal unit (WWTP) - extended aeration activated sludge package plant	1989					+
<u> </u>	Channar WWTP SDU		Chlorination facility - WWTP - tablet feeder	1989					+
	Channar WWTP SDU		Power supply to WWTP	1989					
Eastern Range Mi		Water Supply	Trunk main - Turee Creek main to Transfer tank - 0.66km	2005					
	ER trunk main system		Transfer tank	2005					
	ER trunk main system		Transfer tank PS	2005					-
	ER trunk main system ER trunk main system		Power supply to Transfer tank PS Trunk main - Transfer tank to break tank - 1.3km	2005 2005					
				2005					+
<u> </u>	ER break tank / PS		Break tank (incl fire water)	2007					+
<u> </u>	ER break tank / PS		Process Plant PS	2007		To be replaced wit	h PRV		
1									1

ocation.	Major Asset	Area	Category	Asset description / type	Installation / upgrade date	Material	Condition	Planned replacement	
		ER break tank / PS		Fire PS	2007				
	_	ER break tank / PS		Power supplies to PS's	2007				
		ER plant main		Main to Process Plant - 0.2km	2007				
				Main to Turkeye next (new tenk) 0 dlan	2000				
·		ER Turkeys nest ER Turkeys nest		Main to Turkeys nest (now tank) - 2.1km Turkeys nest tank	2008 2008				
-					2000				
-		ER Plant mains		Reticulation mains - Crib rooms, crusher - 0.2km	2005				
		ER Plant mains		UV disinfection - crib room	2005				
		ER Plant mains		Plant mains - sprays, waterstand, etc	2005				
		ED and and a set		ED studed	0000				
·		ER waterstand		ER waterstand	2008				
·		ER Comms		Comms system for bores, PS, tanks etc	2005				
·									
	Tom Price Township	Southern Fortescue borefield system	Water Supply	Southern Fortescue borefield bores (x 10) incl pumps / motors					
		Southern Fortescue borefield system		SFP2	1969				
		Southern Fortescue borefield system		SFP4	1969				
		Southern Fortescue borefield system		SFP5	1969				
		Southern Fortescue borefield system		SFP6	1969				
		Southern Fortescue borefield system		SFP7	1969				
		Southern Fortescue borefield system		SFP8	1969				
		Southern Fortescue borefield system		SFP9	1969				
		Southern Fortescue borefield system Southern Fortescue borefield		SFP10	1969				
		Southern Fortescue borefield		SFP11	1969				
•		system		SFP12	1969				
		Southern Fortescue borefield system		Southern Fortescue borefield collector mains - 200mm / 300mm dia steel - 1.6km	1969	MSCL			
		Southern Fortescue borefield system		Bore electrical control cubicles	1969				
		Southern Fortescue borefield system		Power supply to bores - pole / cables / TX	1969				
		Southern Fortescue borefield system Southern Fortescue borefield		Trunk main to Southern Fortescue Collector - 350mm dia steel - 11km	1969	MSCL		2011 ?	
		Southern Fortescue borefield		Southern Fortescue Collector Tank - 2,300m3		Steel			
	_	Southern Fortescue borefield		Southern Fortescue Collector Pump Station - 5 x 156kw	1969				
		system Southern Fortescue borefield		Chlorination facilities - SF collector	2008				
·		system Southern Fortescue borefield		Power supply to Collector PS Trunk main to Southern Fortescue Booster - 350mm dia steel - 15.2km	1969 1969	MSCL		2011 ?	
		system Southern Fortescue borefield		Southern Fortescue Booster Tank - 2,300m3		Steel		2011 !	
·		system Southern Fortescue borefield		Southern Fortescue Booster Pump Station - 4 x 156kw	1969				
		system Southern Fortescue borefield		Power supply to Booster PS	1969				
		system Southern Fortescue borefield system		Trunk main to Town Tanks - 350mm dia steel - 21km		MSCL			
ļ		TP Town tanks	+	Town Tanks - 2 x 9ML		Steel			
ľ		TP Town tanks TP Town tanks		Power supply to town tanks Chlorination facility - Town Tanks	1969 2008				
ł		TP Town tanks		Chlorination facility - Town Tanks Trunk main - Town Tanks to town - 300mm dia steel - 1km		MSCL			
		TP Town tanks		Trunk main - Town Tanks to mine - 300mm dia steel - 5km	1969				

Location	Major Asset	Area	Category	Asset description / type	Installation / upgrade date	Material	Condition	Planned replacement	
-		TP Town mains		Trunk main - town - 250mm dia steel - 1km	1969	MSCL			
-		TP Town mains		Town reticulation mains - 200mm, 150mm, 100mm dia, incl associated valves and hydrants - 48km	1969	MSCL/AC/PVC			 +
-		TP Town mains		Service connection pipework and water meters	1969				1
-									
-		TP Comms		Comms system for bores, PS, tanks etc				2010 - IP	
-	Tom Price Township	TP town Sewer system	Sewerage	Sewer mains - gravity - 43km	1969 - 2009	VC / PVC		Ongoiong	
_		TP town Sewer system		I/O property connections	1969 - 2009			Ongoing	
_		TP town Sewer system		Sewer pump station No 2 (SPS2)	1969				
_		TP town Sewer system		Power supply to SPS2	1969				
-		TP town Sewer system		Sewer pump station No 1(SPS1)	1969				
-		TP town Sewer system		Power supply to SPS1	1969				
-		TP town WWTP		Teurs une teurste standardet ele st. 2 une sta statuite statuite ele	1000				
-		TP town WWTP		Town wastewater treatment plant - 3 x waste stabilisation ponds	1969				
-		TP town WWTP		Chlorination facility - WWTP	2005 1969				
-				Power supply to WWTP	1909				+
	Mount Tom Drice Mine	Hardy/Mt Lional barafield system	Water Supply	Hardy River borefield bores (x 14) incl pumps / motors					
	Mount Tom Price Mine	Hardy/Mt Lionel borefield system	Water Supply	HRP1	1969				
_		Hardy/Mt Lionel borefield system		HRP2	1969	1			+
-		Hardy/Mt Lionel borefield system		HRP3	1969				
-		Hardy/Mt Lionel borefield system		HRP4	1969				
-		Hardy/Mt Lionel borefield system							
		Hardy/Mt Lionel borefield system		HRP5	1969				
-		Hardy/Mt Lionel borefield system		HRP6	1969				
Tom Price		Hardy/Mt Lionel borefield system		HRP7	1969				
Tom Price		Hardy/Mt Lionel borefield system		HRP8	1969				
		Hardy/Mt Lionel borefield system		HRP9	1969				
_		Hardy/Mt Lionel borefield system		HRP10	1969				
		Hardy/Mt Lionel borefield system		HRP11	1969				
		Hardy/Mt Lionel borefield system		MLP3	1969				
		Hardy/Mt Lionel borefield system		Sec 10A	2008				
		Hardy/Mt Lionel borefield system		Sec 10B	2008				
Ľ									
		Hardy/Mt Lionel borefield system		Hardy River borefield collector mains - 200mm dia steel - 4.8km	1969				
		Hardy/Mt Lionel borefield system		Bore electrical control cubicles	1969				
		Hardy/Mt Lionel borefield system		Power supply to bores - pole / cables / TX	1969				
		Hardy/Mt Lionel borefield system		Trunk main to Hardy River Collector 3 - 200/250NB - 1.5km	1969				 1
-		Hardy/Mt Lionel borefield system		Hardy River Collector Tank 3 - 1136m3	1969				+
		Hardy/Mt Lionel borefield system		Hardy River Collector 3 Pump Station	1969				 <u> </u>
-				Power supply to HRC3 PS	1969				
_		Hardy/Mt Lionel borefield system		Trunk main to Hardy River Collector 1 - 392NB - 7.8km	1969			2010	+
_		Hardy/Mt Lionel borefield system		Hardy River Collector Tank 1 - 1136m3	1969				+
-		Hardy/Mt Lionel borefield system		Hardy River Collector 1 Pump Station	1969			2010	+
-		Hardy/Mt Lionel borefield system						2010	<u> </u>
		Hardy/Mt Lionel borefield system		Chlorination facilities - Hardy River Collector 1	2008	l		_	

'n	Major Asset	Area	Category	Asset description / type	Installation / upgrade date	Material	Condition	Planned replacement	
		Hardy/Mt Lionel borefield system		Power supply to HRC1 PS	1969				
		Hardy/Mt Lionel borefield system		Trunk main to Mine Tank - 392NB - 14.2km	1969				
		Southern Ridge system		Southern Ridge pump station	1969 ?			2010 ?	
		Southern Ridge system		Main to Southern Ridge tank - 315NB - 2km	1969 ?			2010 !	
					1000 .				
		TP Mine tank		Mine Tank - 4,200m3	1969				
		TP Mine tank		Trunk main - Mine Tank to CMUST - 392NB - 2.2km	1969				
		TP CMUST		CMUST - 8,500m3	1969				
		TP CMUST		Main CMUST to Clarified water tank - 315NB - 0.4km	1969				
		TP CMUST		Main CMUST to 3APS - 300mm - 1km	2008				
		TP 2APS system		Trunk main - Town Tanks to 2APS - 392NB - 3.3km	1969				
		TP 2APS system		2A pump station (2APS) - 2 x 185kw	1969				-
		TP 2APS system		Trunk main - 2APS to Mine Tank - 392NB - 1.8km	1969				
				Tauch and a Mine Taul to (ADD, 200ND, 2.01 a	4070				
		TP 4APS trunk main		Trunk main - Mine Tank to 4APS - 392NB - 2.3km	1978 1979			2010	
		TP 4APS trunk main		4A pump station - 2 x 185kw, 2 x 70kw, 2 x 30kw	1919			2010	 -
		TP Box Cut system		Main - 4APS to Box Cut tank - 315NB polyethylene - 1km	2				
		TP Box Cut system		Box Cut tank - 2 x 200m3	?	L			
		TP Prongs system		Main - 4APS to Prongs tank - 315NB polyethylene - 0.5km	1986				
		TP Prongs system		Prongs tank - 2270m3	1986				
		TP 1120 system		Main - 4APS to 1120 tank - 315NB polyethylene - 1km	?				
		TP 1120 system		1120 tank	?				
		TP 1120 system		1120 waterstand	?				
		TP Mine pipework		Mine reticulation mains - 200mm, 150mm, 100mm dia, incl associated valves and hydrants	1969				
		TP 3A PS		3A pump station - 4 x 30kw (Plant ???)					
		TP 3B PS		Main North Deposit to 3B pump station (Mine Ops ???)					
		TP 3B PS		3B pump station Main 3BPS to 4APS outlet - 1km	2006				
		TP 3B PS			2006				
		TP PS2		PS2 Plant (Crusher)					
		11 1 32							
		TP Reclaim dam		Reclaim dam (25ML) and associated supply and return pipework					
		TP Comms		Comms system for bores, PS, tanks etc				2010	
		TP Chlorine store		Central chlorine store					Ĺ
Mou	nt Tom Price Mine	TP mine Sewer system	Sewerage	Sewer mains - gravity - 800m	1969				
				I/O building connections	1969				
		TP MOC WWTP		Mine MOC WWTP - extended aeration activated sludge package plant	1977				
				Chlorination facility - MOC WWTP (tablet feeder)	2009				
				Power supply to MOC WWTP	1977				
		TP Concentrator WWTP		Mine Concentrator WWTP - extended aeration activated sludge package plant	1979				 -
				Chlorination facility - Concentrator WWTP	1979				 -
				Power supply to Concentrator WWTP	1980				
			<u> </u>						
Mara	andoo mine	Marandoo bore	Water supply	Supply bore x 1 incl pump / motor / control					
			·····	Power supply to bore					
									1
Dam	npier Township	Dampier town water mains	Water Supply	Trunk main - town - 1km	1968	MSCL			
				Town reticulation mains - 200mm, 150mm, 100mm dia, incl associated valves and hydrants - 28km	1968	MSCL / PVC			
				Service connection pipework and water meters	1968				1

Location	Major Asset	Area	Category	Asset description / type	Installation / upgrade date	Material	Condition	Planned replacement		
				Standby tank - Kangaroo Hill	1968					
-		-								
-	Dampier Township	Dampier town sewer system	Sewerage	Sewer mains - gravity - 21km I/O property connections	1968 - 2006 1968 - 2006	MSCL / PVC/ VC		2011 onwards		
-				Sewer pump station No 3 (SPS3)	1968					
-				SPS3 controller	2006					
				Power supply to SPS3	1968					
-				Sewer pump station No 2 (SPS2)	1968					-
-				SPS2 controller	2006 1968					+
-				Power supply to SPS2 Sewer pump station No 1(SPS1)	1968					
-				SPS1 controller	2006					
-				Power supply to SPS1	1968					
				Pressure main - SPS1 to pit	1968					
-										
-		Dampier town WWTP		Town wastewater treatment plant - 2 x Imhoff tanks, 3 x trickling filters	1968					
-				Chlorination facility - WWTP	2009 1968					
ŀ				Power supply to WWTP	1900				L	+
ŀ	Dampier Ports	Dampier PP Water mains	Water Supply	Trunk main - Parker Port - 1km	1968					<u> </u>
ŀ				Reticulation mains Parker Point - 200mm, 150mm, 100mm dia, incl associated valves and hydrants - 5km	1968					
ľ				Process water / fire tank - Parker Point	1968					
[Process water tank pump station - Parker Point	1968					
-				Fire pump system - Parker Point	1968					
-				Power supply to PS - Parker Point	1968					<u> </u>
-				Plant area pipework - Parker Point Plant area fire mains - Parker Point	1968 1968					
-				Pipework to ore wharf - Parker Point	1968					
Coastal					1000					+
-		Dampier Ell water mains		Trunk main - EII - 2.5km						
				Reticulation mains EII -150mm, 100mm dia, incl associated valves and hydrants - 4km						
-				Process water / fire tank - Ell						ļ
-				Process water tank pump station - Ell						<u> </u>
-				Ell backup tank Ell diesel backup pump						<u> </u>
-				Fire pump system - Ell						+
-				Power supply to PS - Ell						
-				Plant area fire mains - Ell						
				Pipework to 2 Mile Rail - maintenance area / ballast washer						
-	7 Mile	7 Mile water		Storage tank						<u> </u>
				Diesel pump Main supply (from WC main)			Duplicate 2			
-				Distribution mains			Duplicate ?			+
ŀ					1					<u> </u>
ŀ	Dampier Ports	Dampier ports WWTP	Sewerage	Aerobic treatment units x 12	2000					
ľ			-	Septic tanks						
ŀ	7 Mile	7 Mile Sewer system		Pump stations	1979					
F				Sewer mains WWTP - Imhoff tank / oxidation ponds	1979					+
ŀ					13/3					+
	Cape Lambert Port	CL Water mains	Water Supply	Trunk main - 400mm dia - 4.5km						+
F	espo manisorer ore			Distribution mains to various site areas	1					1
ļ			<u> </u>	Water / fire storage tank						
				Water pump station						
				Fire pump system	 					
ŀ				Power supply to PS	-					<u> </u>
ŀ	Cane Lambert Port	CL Septic systems	Septic	Septic tanks x 12	+					<u> </u>
	Cape Lambert Port Pannawonica Township	Panna town borefield	Water Supply	Septic tanks x 12 Town bores x 4 incl pumps / motors	+	1				+
ŀ			vvalei Suppiy	Bore 24	1971					<u> </u>
-				Bore 26	1971					
ļ			<u> </u>	Bore 35	1971					
ľ				Bore 36	1971					

1	Major Asset	Area	Category	Asset description / type	Installation / upgrade date	Material	Condition	Planned replacement		
				Borefield collector mains - 7km	2009					
				Bore electrical control cubicles	1971					_
				Power supply to bores - pole / cables / TX	1971					_
					13/1					+
		Pann town tanks		Town tanks x 2	1971					
				Chlorination facility - Town tanks						
		Deen town mains		Turn references and a second	1971					
		Pann town mains		Town reticulation mains - 200mm, 150mm, 100mm dia, incl associated valves and hydrants - 12km						
				Service connection pipework and water meters	1971					
		Panna town water comms		Comms system for bores						
Par	nnawonica Township	Pann town sewer system	Sewerage	Sewer mains - gravity	1971					
				I/O property connections	1971					
				Sewer pump station No 1(SPS1)	1971					
				Power supply to SPS1	1971					
				Pressure main - SPS1 to pit	1971					
		Panna town WWTP		Town wastewater treatment plant - sequencing batch reactor /ponds	2007					
	Power supply to WWTP		Power supply to WWTP	2007						
Der	nnawonica mine	Panna Mine borefield	Water Supply	Supply bores x 2 incl pumps / motors	1996					
Par	inawonica mine		water Supply	Borefield collector mains - 4.4km	1990					
				Bore electrical control cubicles	1990					
					1990					
		Panna Alpha 16		Alpha 16 storage tank	1978					
				Alpha 16 pump station	1978					
				Chlorination facility - Alpha 16 tank	1978			2010		
		Panna plant pipework		Distribution pipework to Admin, Workshops, Laydown - 6km	1978					_
Par	nnawonica mine Mesa J	Panna mine septic systems	Sewerage	Septic tanks x 4	1978					_
1'al		r anna mine septie systems	Jeweldye		1010				L	
		Panna mine sewer system		Sewer mains - gravity - 200m	1978					
		Panna mine WWTP		WWTP - Admin	1978			2010		
Bor	nnawonica mine Mesa A	Panna Mesa A mine		ТВА	2009					_
Far	mawonica mine wesa A				2003					+
-			1				1	<u> </u>		

-

RIO TINTO NETWORKS ASSET REGISTER @ 2/1/2010

Major Asset	Area	Category	Asset description / type	
Paraburdoo Township	Northern borefield / CT1 / PS1	Water Supply	Northern borefield bores incl pumps / motors (x 11)	
· · ·	Northern borefield / CT1 / PS1		PTP1	
	Northern borefield / CT1 / PS1		PTP2 - redrill	
	Northern borefield / CT1 / PS1		PTP3	
	Northern borefield / CT1 / PS1		PTP4	
	Northern borefield / CT1 / PS1		PTP5 - redrill	
	Northern borefield / CT1 / PS1		PTP7	
	Northern borefield / CT1 / PS1		PTP8	
	Northern borefield / CT1 / PS1		PTP9	
	Northern borefield / CT1 / PS1		PTP10	
	Northern borefield / CT1 / PS1		PTP11	
	Northern borefield / CT1 / PS1		Chlorination facility - PTP2	
	Northern borefield / CT1 / PS1		Chlorination facility - PTP9	
	Northern borefield / CT1 / PS1		PTP9 air compressor	
	Northern borefield / CT1 / PS1		PTP9 pressure filters	
	Northern borefield / CT1 / PS1		Northern borefield collector mains - 200mm / 350mm dia steel - 5km	
	Northern borefield / CT1 / PS1		Bore electrical control cubicles	
	Northern borefield / CT1 / PS1		Power supply to bores - pole / cables / TX	
	Northern borefield / CT1 / PS1		Collector tank 1 (CT1) - 650m3	
	Northern borefield / CT1 / PS1		Pump station 1 (PS1) - 2 x 200hp	
<u> </u>	Northern borefield / CT1 / PS1		Power supply to PS1	
	Northern borefield / CT1 / PS1		Chlorination facility - CT1	
	Northern borefield / CT1 / PS1		Trunk main PS1 to Town Tanks - 350mm dia steel - 3.3km	
	Town tanks		Town Tanks - 2 x 9ML	
	Town tanks		Power supply to town tanks	
	Town tanks		Chlorination facility - Town Tanks	
			Trunk main - Town Tanks to town - 500mm dia steel - 2.7km	
	Town tanks			
	Town tanks		Trunk main - Town Tanks to mine - 350mm dia steel - 3.1km	
	Town		Trunk main - town - 375mm dia steel - 2.7km	
	Town		Town reticulation mains - 200mm, 150mm, 100mm dia, incl associated valves and hydrants - 29km	
	Town		Service connection pipework and water meters	
	Town		Comms system for bores, PS, tanks etc	
Paraburdoo Airport	Paraburdoo Airport	Water Supply	Bore PAP1 incl pump / motor	
	Paraburdoo Airport		Bore collector main - 100mm dia steel - 0.5km	
	Paraburdoo Airport		Bore electrical control cubicle	
	Paraburdoo Airport		Power supply to bore - pole / cables / TX	
	Paraburdoo Airport		Collector / fire tank - 132m3	
	Paraburdoo Airport		Pump station - 3 x 2.2kw	
	Paraburdoo Airport		Fire pump	
	Paraburdoo Airport		Distribution pipework - to terminal etc - 100mm steel / PVC - 0.2km	
	Paraburdoo Airport		Fire system pipework - 200mm dia polyethylene	
	Paraburdoo Airport		Chlorination facility	
	Paraburdoo Airport		Control system for bores, PS, tanks etc	
Paraburdoo Township	Para town sewer system	Sewerage	Sewer mains - gravity - 19km	
	Para town sewer system	Sewelage	I/O property connections	
	Para town sewer system		Sewer pump station No 2 (SPS2)	
	Para town sewer system		SPS2 controller	
	Para town sewer system		Power supply to SPS2	
	Para town sewer system		Sewer pump station No 1(SPS1)	
	Para town sewer system		SPS1 controller	
	Para town sewer system		Power supply to SPS1	
	Para town sewer system		Pressure main - SPS1 to WWTP	
	Para town WWTP		Town wastewater treatment plant - Imhoff tank + 3 x waste stabilisation ponds	
	Para town WWTP		Chlorination facility - WWTP	
	Para town WWTP		Power supply to WWTP	
				1
	Para town WWTP		Wastewater treatment plant - trade waste facility	

Location	Major Asset	Area	Category	Asset description / type	
Loodiioii	inajor / locot		outogoty		
		Turee Creek borefield system		PBO1	
		Turee Creek borefield system		PBO2	
		Turee Creek borefield system		PBO3	
		Turee Creek borefield system		PBO4	
		Turee Creek borefield system		PBO5	
		Turee Creek borefield system		PB07	
		Turee Creek borefield system		Bore electrical control cubicles	
		Turee Creek borefield system		Power supply to bores - pole / cables / TX	
		Turee Creek borefield system		Trunk main - Turee Creek borefield to Fines Plant - 37km	
		Turee Creek borefield system		Turee Creek collector tank	
		Turee Creek borefield system		Turee Creek pump station	
		Turee Creek borefield system		Power supply to Turee Creek pump station	
		Turee Creek borefield system		Turee Creek surge tanks x 2	
		4W / Southern borefield system		Southern borefield - PMP5 bore - redrill	
		4W / Southern borefield system		Bore electrical control cubicle	
		4W / Southern borefield system		Power supply to bore - pole / cables / TX	
		4W / Southern borefield system		Southern borefield collector mains - 0.3km	
		4W / Southern borefield system		Trunk main - Southern borefield / 4W to Collector tank 6 - 3.1km	
		4W / Southern borefield system		Collector tank 6 (CT6)	
		4W / Southern borefield system		Trunk main - CT6 to CT2 - 1.3km	
				Trunk main CT6 to branch ST6A/B - 0.5km	
		4W / Southern borefield system			
		CT2 / PS2		Collector tank 2 (CT2)	
		CT2 / PS2		Pump station 2 (PS2)	
		CT2 / PS2		Power supply to PS2	
		CT2 / PS2		Chlorination facility - PS2	
		CT2 / PS2		Trunk main - PS2 to plant areas - 0.6km	
		PS3 / ST3		Pump station 3 (PS3)	
		PS3/ST3		Power supply to PS3	
		PS3/ST3		Storage tank 3 (ST3)	
		PS3/ST3		Main from PS3 to ST3 - 0.7km	
Greater		PS3 / ST3		1480 waterstand	
Paraburdoo					
		ST6 / PS6 / Fines Plant area		Collector tanks ST6A/B - 2 x 1ML	
		ST6 / PS6 / Fines Plant area		Pump station 6 (PS6)	
		ST6 / PS6 / Fines Plant area ST6 / PS6 / Fines Plant area		Power supply to PS6 Fines Plant interconnection pipework, control valves etc	
		ST6 / PS6 / Fines Plant area		Mains - ST6A to Process water tank - 0.2km	
		STO/ FOO/ Filles Flatt area			
		Para Plant area		Plant area distribution / reticulation mains, hydrants - 5.1km	
	<u> </u>	Para comms		Comms system for bores, PS, tanks etc	
	Paraburdoo Mine	Para mine sewer system	Sewerage	Sewer mains - gravity - 1km	
		Para mine sewer system		I/O building connections	
		Para mine sewer system		Sewer pump station No 3 (SPS3)	
		Para mine sewer system		SPS3 controller	
		Para mine sewer system		Power supply to SPS3	
		Para mine sewer system		Sewer pump station No 4(SPS4)	
		Para mine sewer system		SPS4 controller	
		Para mine sewer system		Power supply to SPS4	
		Para mine sewer system		Sewer pump station No 5 (SPS5)	
		Para mine sewer system		SPS5 controller	
		Para mine sewer system		Power supply to SPS5	
		Para mine sewer system		Pressure main - SPS5 to pit	
		Para mine sewer system		Pressure main - SPS4 to pit	
		Para mine sewer system		Pressure main - SPS3 to pit	

n	Major Asset	Area	Category	Asset description / type	
		Para mine WWTP SDU		Sewage disposal unit (WWTP) - extended aeration activated sludge package plant	
		Para mine WWTP SDU		Chlorination facility - WWTP - tablet feeder	
		Para mine WWTP SDU		Power supply to WWTP	
		Plant MOC WWTP		Plant MOC WWTP sewage PS	
		Plant MOC WWTP		Plant MOC WWTP	
(Channar Mine	Channar borefield	Water Supply	Channar bores x 3 incl pumps / motors	
		Channar borefield		CMP1	
		Channar borefield		CMP2	
		Channar borefield		CMP3	
-					
H		Channar borefield		Bore collector mains - 4.2km	
-		Channar borefield		Bore electrical control cubicles	
F		Channar borefield Channar borefield		Power supply to bores - pole / cables / TX Trunk main - Turee Creek main to Collector tank (emergency backup) - 0.25km	
		Channar boreneid		Trunk main - Turee Creek main to Collector tank (emergency backup) - 0.25km	
╞		Channar collector / PS		Channar collector tank - 200m3	+
╞		Channar collector / PS		Channar pump station	
╞		Channar collector / PS		Power supply to PS	
F		Channar collector / PS		Chlorination facility - Channar PS	
-					
-		Channar trunk main		Trunk main - Channar PS to main tank - 2.3km	
F					
		Channar main tank		Channar main tank - 4,200m3	
F		Channar main tank		Power supply to main tank	
		Channar plant pipework		Distribution pipework - to Plant, offices, workshops etc - 2.2km	
		Channar plant pipework		Plant areas pipwork - crusher, conveyors	
		Channar plant pipework		Fire system pipework	
		Channar plant pipework		Channar break tank - 22m3	
		Channar 1 waterstand		Main to Channar 1 waterstand - 0.5km	
		Channar 1 waterstand		Channar 1 waterstand - 60m3	
_		Channar 3 waterstand		Main to Channar 3 waterstand - 1km	
_		Channar 3 waterstand		Channar 3 waterstand - 60m3	
		Channar 3 waterstand		Main to Channar from Channar 3 to 94E waterstand - 3.5km	
-					
_		Channar 94E		Channar 94E waterstand	
-		Channar 94E		Comms system for bores, PS, tanks etc	
-		Nide sint bana		Nide size have ONDE	
┝		Midpoint bore Midpoint bore		Midpoint bore CMP5 Main to CMP5 - 0.6km	
╞		Midpoint bore		Main to CMP5 - 0.6km Midpoint water / fire tank	
╞		Midpoint bore		Midpoint pump station	
╞		Midpoint bore		Distribution main to midpoint conveyors / transfer station - 0.1km	
┢		Midpoint bore		Power supply to CMP5 and midpoint PS	
ŀ					
C	Channar Mine	Channar mine sewer system	Sewerage	Sewer mains - gravity - 600m	
F		Channar mine sewer system	go	I/O building connections	
F			1		
F		Channar WWTP SDU		Sewage disposal unit (WWTP) - extended aeration activated sludge package plant	
F		Channar WWTP SDU		Chlorination facility - WWTP - tablet feeder	
F		Channar WWTP SDU	1	Power supply to WWTP	
F					
E	Eastern Range Mine	ER trunk main system	Water Supply	Trunk main - Turee Creek main to Transfer tank - 0.66km	
Γ		ER trunk main system		Transfer tank	
Γ		ER trunk main system		Transfer tank PS	
Γ		ER trunk main system		Power supply to Transfer tank PS	
ſ		ER trunk main system		Trunk main - Transfer tank to break tank - 1.3km	
		ER break tank / PS		Break tank (incl fire water)	
Γ		ER break tank / PS		Process Plant PS	
		ER break tank / PS		Turkeys nest tank PS	· · · · · · · · · · · · · · · · · · ·

Location	Major Asset	Area	Category	Asset description / type	
		ER break tank / PS		Fire PS	
		ER break tank / PS		Power supplies to PS's	
		ER plant main		Main to Process Plant - 0.2km	
		ER Turkeys nest		Main to Turkeys nest (now tank) - 2.1km	
		ER Turkeys nest		Turkeys nest tank	
		,			
		ER Plant mains		Reticulation mains - Crib rooms, crusher - 0.2km	
		ER Plant mains		UV disinfection - crib room	
		ER Plant mains		Plant mains - sprays, waterstand, etc	
		ER waterstand		ER waterstand	
		ER Comms		Comms system for bores, PS, tanks etc	
		On these Fortunes have field			
	Tom Price Township	Southern Fortescue borefield system	Water Supply	Southern Fortescue borefield bores (x 10) incl pumps / motors	
		Southern Fortescue borefield system		SFP2	
		Southern Fortescue borefield		SFP4	
		system Southern Fortescue borefield		SFP5	
		system Southern Fortescue borefield		SFP6	
		system Southern Fortescue borefield			
		system Southern Fortescue borefield		SFP7	
		system		SFP8	
		Southern Fortescue borefield system		SFP9	
		Southern Fortescue borefield system		SFP10	
		Southern Fortescue borefield system		SFP11	
		Southern Fortescue borefield system		SFP12	
		Southern Fortescue borefield system		Southern Fortescue borefield collector mains - 200mm / 300mm dia steel - 1.6km	
		Southern Fortescue borefield system		Bore electrical control cubicles	
		Southern Fortescue borefield system		Power supply to bores - pole / cables / TX	
		Southern Fortescue borefield system		Trunk main to Southern Fortescue Collector - 350mm dia steel - 11km	
		Southern Fortescue borefield system		Southern Fortescue Collector Tank - 2,300m3	
		Southern Fortescue borefield		Southern Fortescue Collector Pump Station - 5 x 156kw	
		Southern Fortescue borefield		Chlorination facilities - SF collector	
		Southern Fortescue borefield		Power supply to Collector PS	
		Southern Fortescue borefield		Trunk main to Southern Fortescue Booster - 350mm dia steel - 15.2km	
		Southern Fortescue borefield		Southern Fortescue Booster Tank - 2,300m3	
		Southern Fortescue borefield		Southern Fortescue Booster Pump Station - 4 x 156kw	
		system Southern Fortescue borefield		Power supply to Booster PS	
		system Southern Fortescue borefield		Trunk main to Town Tanks - 350mm dia steel - 21km	
		system			
		TP Town tanks		Town Tanks - 2 x 9ML	
		TP Town tanks		Power supply to town tanks	
		TP Town tanks		Chlorination facility - Town Tanks Trunk main - Town Tanks to town - 300mm dia steel - 1km	
		TP Town tanks TP Town tanks			
		TP Town tanks		Trunk main - Town Tanks to mine - 300mm dia steel - 5km	

Location	Major Asset	Area	Category	Asset description / type	
		TP Town mains		Trunk main - town - 250mm dia steel - 1km	
		TP Town mains		Town reticulation mains - 200mm, 150mm, 100mm dia, incl associated valves and hydrants - 48km	
		TP Town mains		Service connection pipework and water meters	
		TP Comms		Comms system for bores, PS, tanks etc	
	Tara Drias Taurahia	TP town Sewer system	C	Sewer mains - gravity - 43km	
	Tom Price Township	TP town Sewer system	Sewerage	I/O property connections	
		TP town Sewer system		Sewer pump station No 2 (SPS2)	
		TP town Sewer system		Power supply to SPS2	
		TP town Sewer system		Sewer pump station No 1(SPS1)	
		TP town Sewer system		Power supply to SPS1	
		TP town WWTP		Town wastewater treatment plant - 3 x waste stabilisation ponds	
		TP town WWTP		Chlorination facility - WWTP	
		TP town WWTP		Power supply to WWTP	
	Mount Tom Price Mine	Hardy/Mt Lionel borefield system	Water Supply	Hardy River borefield bores (x 14) incl pumps / motors	
		Hardy/Mt Lionel borefield system		HRP1	
		Hardy/Mt Lionel borefield system		HRP2	
		Hardy/Mt Lionel borefield system		HRP3	
		Hardy/Mt Lionel borefield system		HRP4	
		Hardy/Mt Lionel borefield system		HRP5	
		Hardy/Mt Lionel borefield system		HRP6	
Tom Driag		Hardy/Mt Lionel borefield system		HRP7	
Tom Price		Hardy/Mt Lionel borefield system		HRP8	
		Hardy/Mt Lionel borefield system		HRP9	
		Hardy/Mt Lionel borefield system		HRP10	
		Hardy/Mt Lionel borefield system		HRP11	
		Hardy/Mt Lionel borefield system		MLP3	
		Hardy/Mt Lionel borefield system		Sec 10A	
		Hardy/Mt Lionel borefield system		Sec 10B	
		Hardy/Mt Lionel borefield system		Hardy River borefield collector mains - 200mm dia steel - 4.8km	
		Hardy/Mt Lionel borefield system		Bore electrical control cubicles	
		Hardy/Mt Lionel borefield system		Power supply to bores - pole / cables / TX	
		Hardy/Mt Lionel borefield system		Trunk main to Hardy River Collector 3 - 200/250NB - 1.5km	
		Hardy/Mt Lionel borefield system		Hardy River Collector Tank 3 - 1136m3	
		Hardy/Mt Lionel borefield system		Hardy River Collector 3 Pump Station	
		Hardy/Mt Lionel borefield system		Power supply to HRC3 PS	
		Hardy/Mt Lionel borefield system		Trunk main to Hardy River Collector 1 - 392NB - 7.8km	
		Hardy/Mt Lionel borefield system		Hardy River Collector Tank 1 - 1136m3	
		Hardy/Mt Lionel borefield system		Hardy River Collector 1 Pump Station	
		Hardy/Mt Lionel borefield system		Chlorination facilities - Hardy River Collector 1	

'n	Major Asset	Area	Category	Asset description / type	
		Hardy/Mt Lionel borefield system		Power supply to HRC1 PS	
		Hardy/Mt Lionel borefield system		Trunk main to Mine Tank - 392NB - 14.2km	
		Southern Ridge system		Southern Ridge pump station	
		Southern Ridge system		Main to Southern Ridge tank - 315NB - 2km	
		TP Mine tank		Mine Tank - 4,200m3	
		TP Mine tank		Trunk main - Mine Tank to CMUST - 392NB - 2.2km	
		TP CMUST TP CMUST		CMUST - 8,500m3 Main CMUST to Clarified water tank - 315NB - 0.4km	
		TP CMUST		Main CMUST to 3APS - 300mm - 1km	
		TP 2APS system		Trunk main - Town Tanks to 2APS - 392NB - 3.3km	
		TP 2APS system		2A pump station (2APS) - 2 x 185kw	
		TP 2APS system		Trunk main - 2APS to Mine Tank - 392NB - 1.8km	
		TP 4APS trunk main		Trunk main - Mine Tank to 4APS - 392NB - 2.3km	
		TP 4APS trunk main		4A pump station - 2 x 185kw, 2 x 70kw, 2 x 30kw	
		TP Box Cut system		Main - 4APS to Box Cut tank - 315NB polyethylene - 1km	
		TP Box Cut system		Box Cut tank - 2 x 200m3	
		TP Prongs system		Main - 4APS to Prongs tank - 315NB polyethylene - 0.5km Prongs tank - 2270m3	
		TP Prongs system			
		TP 1120 system		Main - 4APS to 1120 tank - 315NB polyethylene - 1km	
		TP 1120 system		1120 tank	
		TP 1120 system		1120 waterstand	
		TP Mine pipework		Mine reticulation mains - 200mm, 150mm, 100mm dia, incl associated valves and hydrants	
		TP 3A PS		3A pump station - 4 x 30kw (Plant ???)	
		TP 3B PS TP 3B PS		Main North Deposit to 3B pump station (Mine Ops ???)	
		TP 3B PS		3B pump station Main 3BPS to 4APS outlet - 1km	
		TP PS2		PS2 Plant (Crusher)	
		TP Reclaim dam		Reclaim dam (25ML) and associated supply and return pipework	
		TP Comms		Comms system for bores, PS, tanks etc	
		TP Chlorine store		Central chlorine store	
Mou	Int Tom Price Mine	TP mine Sewer system	Sewerage	Sewer mains - gravity - 800m	
				I/O building connections	
		TP MOC WWTP		Mine MOC WWTP - extended aeration activated sludge package plant	
				Chlorination facility - MOC WWTP (tablet feeder)	
				Power supply to MOC WWTP	
		TP Concentrator WWTP		Mine Concentrator WWTP - extended aeration activated sludge package plant	
_				Chlorination facility - Concentrator WWTP	
				Power supply to Concentrator WWTP	
Mar	andoo mine	Marandoo bore	Water supply	Supply bore x 1 incl pump / motor / control	
inart			Trate: ouppiy	Power supply to bore	
Deer	npier Township	Dampier town water mains	Water Supply	Trunk main - town - 1km	
Dam				Town reticulation mains - 200mm, 150mm, 100mm dia, incl associated valves and hydrants - 28km	

Location	Major Asset	Area	Category	Asset description / type	
				Standby tank - Kangaroo Hill	
	Dampier Township	Dampier town sewer system	Sewerage	Sewer mains - gravity - 21km	
				I/O property connections	
				Sewer pump station No 3 (SPS3)	
				SPS3 controller Power supply to SPS3	
				Sewer pump station No 2 (SPS2)	
				SPS2 controller	
				Power supply to SPS2	
				Sewer pump station No 1(SPS1)	
				SPS1 controller	
				Power supply to SPS1 Pressure main - SPS1 to pit	
		Dampier town WWTP		Town wastewater treatment plant - 2 x Imhoff tanks, 3 x trickling filters	
		· · · · · · · · · · · · · · · · · · ·	<u> </u>	Chlorination facility - WWTP	
				Power supply to WWTP	
				Te al avia Dada Dada Al a	
	Dampier Ports	Dampier PP Water mains	Water Supply	Trunk main - Parker Port - 1km	
				Reticulation mains Parker Point - 200mm, 150mm, 100mm dia, incl associated valves and hydrants - 5km Process water / fire tank - Parker Point	
				Process water / life tank - Parker Point Process water tank pump station - Parker Point	
				Fire pump system - Parker Point	
				Power supply to PS - Parker Point	
				Plant area pipework - Parker Point	
				Plant area fire mains - Parker Point	
				Pipework to ore wharf - Parker Point	
Coastal		Demains Ell water mains			
		Dampier Ell water mains		Trunk main - EII - 2.5km Reticulation mains EII -150mm, 100mm dia, incl associated valves and hydrants - 4km	
				Process water / fire tank - Ell	
				Process water tank pump station - Ell	
				Ell backup tank	
				Ell diesel backup pump	
				Fire pump system - Ell	
				Power supply to PS - Ell	
				Plant area fire mains - EII Pipework to 2 Mile Rail - maintenance area / ballast washer	
	7 Mile	7 Mile water		Storage tank	
				Diesel pump	
				Main supply (from WC main)	
				Distribution mains	
	Dampier Ports	Dampier ports WWTP	Sewerage	Aerobic treatment units x 12 Septic tanks	
1					
	7 Mile	7 Mile Sewer system		Pump stations	
				Sewer mains	
				WWTP - Imhoff tank / oxidation ponds	
	Cape Lambert Port	CL Water mains	Water Supply	Trunk main - 400mm dia - 4.5km	
				Distribution mains to various site areas	
				Water / fire storage tank Water pump station	+
				Fire pump system	
		1		Power supply to PS	
		<u> </u>	<u> </u>		
	Cape Lambert Port	CL Septic systems	Septic	Septic tanks x 12	
	Pannawonica Township	Panna town borefield	Water Supply	Town bores x 4 incl pumps / motors	
				Bore 24	
				Bore 26	
				Bore 35 Bore 36	
	L	1	1	-	L

n	Major Asset	Area	Category	Asset description / type	
				Borefield collector mains - 7km	
				Bore electrical control cubicles	
				Power supply to bores - pole / cables / TX	
		Pann town tanks		Town tanks x 2	
				Chlorination facility - Town tanks	
		Pann town mains		Town reticulation mains - 200mm, 150mm, 100mm dia, incl associated valves and hydrants - 12km	
				Service connection pipework and water meters	
		Panna town water comms		Comms system for bores	
Pan	nawonica Township	Pann town sewer system	Sewerage	Sewer mains - gravity	
				I/O property connections	
				Sewer pump station No 1(SPS1)	
				Power supply to SPS1	
				Pressure main - SPS1 to pit	
		Panna town WWTP		Town wastewater treatment plant - sequencing batch reactor /ponds	
				Power supply to WWTP	
Pan	nnawonica mine	Panna Mine borefield	Water Supply	Supply bores x 2 incl pumps / motors	
1 an	inawonica mine		Water Ouppry	Borefield collector mains - 4.4km	
				Bore electrical control cubicles	
		Danna Alpha 16			
		Panna Alpha 16		Alpha 16 storage tank	
				Alpha 16 pump station Chlorination facility - Alpha 16 tank	
		Panna plant pipework		Distribution pipework to Admin, Workshops, Laydown - 6km	
Pan	nnawonica mine Mesa J	Panna mine septic systems	Sewerage	Septic tanks x 4	
		Panna mine sewer system		Sewer mains - gravity - 200m	
		Panna mine WWTP		WWTP - Admin	
Pan	nnawonica mine Mesa A	Panna Mesa A mine		ТВА	
					I

-

Back 2009 Capital Planning Template

Division: Water Utilities

GM: Momcilo Andric

Plan Co-ordinator:

Glenn McRobb

Refer to the Company Decision Tool Worksheet.

What Company?

							Project	Estimated Approval Dat
ompany	Division (GM resp)	Site	Investment Reason		Priority Ranking	Project Sponsor	Originator	Mth/Year
	Bennie Smith	Dampier	Capacity Increase	WWTP Dampier - Construct New Treatment Plant	High	Bennie Smith	Paul White	Jan-09
	Bennie Smith	Tom Price	Capacity Increase	WWTP Tom Price - Construct New Treatment Plant	High	Srewart Beckman		Jun-09
	Stewart Beckman	Tom Price	Capacity Increase	Connect Section 10 Bores to MLP3 Collector Main	Critical	Stewart Beckman		Jan-09
	Stewart Beckman	Tom Price	Capacity Increase	Redrill HRP2 Bore	High	Stewart Beckman	The manufacture of the second se	Jan-09
	Mark Eaglesham	Paraburdoo	Capacity Increase	Upgrade Turee Creek Main PARA - ? Check with Don	High		Heath Bennett	Jan-09
	Stewart Beckman	Tom Price	Capacity Increase	Upgrade 4A Pump Station	High	Stewart Beckman		Jan-09
	Stewart Beckman	Tom Price	Replacement	Upgrade Hardy River Mains and Pump station	High	Stewart Beckman		Jan-09
	Bennie Smith	Dampier	Capacity Increase	Upgrade Water Main from WC Tank to Parker Point	High	Bennie Smith	Heath Bennett	Mar-09
	Bennie Smith	Cape Lambert	Replacement	Cape Lambert Replace Remainder of Water Trunk main	Moderate	Bennie Smith	Heath Bennett	Jan-09
	Mark Eaglesham	Paraburdoo	Capacity Increase	Upgrade Turee Creek Main Stage 2 - ? Check with Don	High	Mark Eaglesham	Heath Bennett	Jan-09
	Bennie Smith	Dampier	Environmental	Dampier Stormwater Drainage - Culvert Replacement	High	Bennie Smith	Heath Bennett	Jan-09
	Mark Eaglesham	Paraburdoo	Capacity Increase	Construct Turee Syncline/4EE Water Storage Dam - EP	High		Clive Samuals	Jan-09
	Stewart Beckman	Tom Price	Capacity Increase	Construct Marandoo Water Storage Dam at TP - EP	High	Stewart Beckman	Doug Marshall	Jan-09
)	Bennie Smith	Cape Lambert	Capacity Increase	Construct Water Storage Tanks at Cape Lambert - John	High	Bennie Smith	Heath Bennett	Jan-09
	Mark Eaglesham	Paraburdoo	Capacity Increase	Upgrade Paraburdoo Town Trunck Main ? Check with	High	Mark Eaglesham	Heath Bennett	Jun-09
	Mark Eaglesham	Paraburdoo	Replacement	Upgrade Paraburdoo Town Isolation Valves	High		Heath Bennett	Aug-09
	Stewart Beckman	Tom Price	Cost Benefit	Develop CITECT System for Dampier Water/Waste water	Moderate	Stewart Beckman		May-09
	Mark Eaglesham	Paraburdoo	Capacity Increase	Paraburdoo Minesite - Water main upgrades	High	Stewart Beckman		Jan-09
	Bennie Smith	Multiple Sites	Health & Safety	Upgrade Fire Hydrants - Para, TP, Dmpr, Panna - Check	High	Bennie Smith	Heath Bennett	Jan-09
	Bennie Smith	Multiple Sites	Health & Safety	Sewer Main Replacement/Upgrades Various towns -	High	Bennie Smith	Heath Bennett	Jan-09
	Bennie Smith	Multiple Sites	Health & Safety	Water Main Replacement/Upgrades	Critical	Bennie Smith	Heath Bennett	Jan-09
	Bennie Smith	Pannawonica	Capacity Increase	Pannawonica borefield collector main	Critical	Bennie Smith	Heath Bennett	Mar-09
		-						

Approval Date

This date is taken to be the date that the CEA is fully approved in CAPS.

* Please Enter in Whole Dollars (ie not millions of dollars or thousands of dollars) * Please Enter in Whole Dollars (ie not millions of dollars or

Total Project														
Value	Jan-09	Feb-09	Mar-09	Apr-09	May-09	Jun-09	Jul-09	Aug-09	Sep-09	Oct-09	Nov-09	Dec-09	Total FY2009	Jan-10
14,000,000	100,000	100,000	1,000,000	2,000,000	3,000,000	3,000,000	4,000,000	800,000					14,000,000	
14,000,000						100,000	100,000	1,000,000	2,000,000	3,000,000	3,000,000	4,000,000	13,200,000	800,000
1,600,000	800,000	800,000				71							1,600,000	
1,000,000	1,000,000												1,000,000	
15,000,000	200,000	300,000	500,000	2,000,000	2,000,000	2,000,000	2,000,000	2,000,000	2,000,000	2,000,000			15,000,000	
1,000,000	100,000	300,000			200,000	4,000,000							1,000,000	
4,500,000	200,000	300,000	500,000	1,000,000	2,000,000	500,000							4,500,000	
1,200,000			200,000	500,000	300,000	200,000							1,200,000	
10,000,000	200,000		100,000	200,000	2,000,000	2,000,000	2,000,000	2,500,000	1,000,000				10,000,000	
20,000,000	100,000	100,000	200,000	10,000,000	2,000,000	2,000,000	2,000,000	2,000,000	1,600,000				20,000,000	
1,600,000		200,000	200,000	200,000	200,000	200,000	200,000	200,000	200,000				1,600,000	
20,000,000	500,000	500,000	500,000	500,000	6,000,000	6,000,000	6,000,000						20,000,000	
20,000,000				500,000	500,000	500,000	500,000	6,000,000	6,000,000	6,000,000			20,000,000	
3,000,000	100,000	100,000			2,000,000	800,000							3,000,000	
3,000,000						100,000	400,000	1,000,000	1,500,000				3,000,000	
1,200,000								200,000	300,000	300,000	400,000		1,200,000	
1,000,000					300,000		100,000	200,000	100,000	100,000	200,000		1,000,000	
1,000,000	100,000	200,000	500,000	200,000									1,000,000	
4,000,000	400,000	200,000	400,000	2,000,000	1,000,000								4,000,000	
60,000,000	500,000	500,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	2,000,000	12,000,000	1,000,000
60,000,000	500,000	500,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	2,000,000	12,000,000	1,000,000
2,500,000	100,000	100,000	100,000	1,800,000	400,000								2,500,000	
													_	
-														
-													- a fille a be-	
N FLORE - FLORE													- Mail See 19 19	
-														
													a dhadha Ba k <mark></mark>	
Relative Statist													and the second	
													-	
											······		_	
K-mail sub-th-													and the Parent	

thousands of dollars) *

.

Please Enter in Whole Dollars (ie not millions of de * Please Enter in Whole Dollars (ie not millions of dollars or thousand

Feb-10	Mar-10	Apr-10	May-10	Jun-10	Jul-10	Aug-10	Sep-10	Oct-10	Nov-10	Dec-10	Total FY2010		FY2012	FY2013
											800,000			
											-			
											-			
									4. 					
1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	12,000,000	12,000,000	12,000,000	12,000,00
1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	1,000,000	12,000,000	12,000,000	12,000,000	12,000,00
											-			
											-			

7	All LME Replacements to be planned by Asset Management. Contact Murray Penno or Shawn Greene.	Refer to the IS&T Deicsion Tool Worksheet.	
	Î	Ť	
s of dolla	rs)		
Later Years	Is this an LME Replacement?	Does this project have an IS&T Component?	Comments
	No	No	
	No No	No No	
	No	No	
	No No	No	
	No	No No	
	No	No	
	_		

2010 ASSET MANAGEMENT REVIEW

5.2

Risks are assessed in Site Reliability Plans, Water Quality Management manual, and IEMS risk registers, and then used to prioritise operational tasks ie

07 (2)

High priority / regularity

- Water quality testing
- Chlorine checks
- Sewer video and jetspray program
- Sewer run
- Sewer manhole replacement

Medium priority / regularity

- Water mains inspections
- Greasing runs
- Sewer root foaming (depending on risk)

Low priority / regularity

Valve checks

CONTRACTOR INFORMATION PACK WATER SERVICES OPERATING LICENCE

REVISION 5 DECEMBER 2008

Document Control – Change Register

Issue	Revision	Prepared	Reviewed By	Approved	Date	Description of Change
		By		By		
А	1	H Bennett	P Promnitz	P Promnitz		First print
	2	H Bennett	P Promnitz	P Promnitz	May 2006	
	3	H Bennett	P Promnitz	P Promnitz	April 2007	No changes
	4	H Bennett	P Promnitz	P White	August 2007	Update customer consultation and water sampling information
	5	H Bennett	R Mullins	P White	Dec 2008	Update to Rio Tinto format, insert outage proforma's, delete SJP for water sampling

Contents

Item Section 1 – General Information Section 2 – Key Performance Indicators Attachments – Outage proforma's Page

1

2

RIO TINTO

CONTRACTOR INFORMATION PACK

WATER SERVICES OPERATING LICENCE

SECTION 1 – GENERAL INFORMATION

Rio Tinto (Networks) is responsible for the delivery of water supply and sewerage services to Dampier, Paraburdoo and Tom Price. These services are provided under an Operating Licence, which is issued and monitored by the Economic Regulatory Authority (ERA) Water Division.

Under the licence, Rio Tinto (Networks) must comply with a number of requirements in relation to levels of services provided to customers. These levels of service are currently as follows:

- Pressure at customers meter = Greater than 15 metres
- Flow at customers meter = Minimum of 20 litres per minute
- Time for provision of advice in response to a complaint / service enquiry = Within 1 hour
- Response to sewer overflows = Within 2 hours
- Provision of minimum notice for planned works (residential properties affected) = 48 hours
- Provision of minimum notice for planned works (commercial / industrial properties affected) = 7 days

In accordance with Schedule 3 of the Licence, Rio Tinto has developed a Customer Charter, which details customer's rights, and Rio Tinto's responsibilities with regard to levels of service to be provided to customers.

In accordance with Clause 6 of the Licence, Rio Tinto (Networks) can engage persons to provide water services which are the subject of the Licence. This practice is currently in place for the provision of contract services for water and wastewater system maintenance. Rio Tinto has a responsibility to ensure that those contractors employed are aware of the requirements under the Licence, and operate accordingly.

To ensure compliance with the Licence requirements, contractors who undertake water supply and sewerage system maintenance works which directly affect customers, and which are provided under service agreements, must comply with the performance indicators shown in the table shown overleaf.

SECTION 2 - KEY PERFORMANCE INDICATORS

Item	Requirement	Comment
Provision of minimum notice	48 hours	1. Written notices to be provided – by
for planned works (residential		Rio Tinto(Networks)
properties affected)		2. Addresses of affected properties and
FF,		outage times are to be recorded and
		provided to Rio Tinto Networks
		following completion of works.
Provision of minimum notice	7 days	1. Written notices to be provided – by
for planned works	/ days	Rio Tinto (Networks)
(commercial / industrial		2. Addresses of affected properties and
•		outage times are to be recorded and
properties affected)		
		provided to Rio Tinto Networks
		following completion of works.
Provision of notice for	As determined by job – contact Rio Tinto	1. Verbal notification is to be provided.
unplanned / emergency works	(Networks) and advise type and estimated	2. Addresses of affected properties and
	outage / interruption period, and number of	outage times are to be recorded and
	affected properties	provided to Rio Tinto Networks
		following completion of works.
Time for provision of advice	Within 1 hour from receipt of complaint /	Customer charter requirement
in response to a complaint /	enquiry	
service enquiry		
Interruption to water supply or	Every effort to be made to limit to a	
sewerage service	maximum of 6 hours	
Provision of drinking water	To be provided after 6 hours	
for water supply interruption	ro be provided unter o nours	
Customer complaints	Must be submitted within 24 hours to the	
Customer complaints	contracting companies Rio Tinto	
	representative or Customer Services	
Reporting of incidents	Incident Report must be submitted within	Standard format available from Rio
	24 hours to the contracting companies Rio	Tinto
	Tinto representative for:	
	1) Overflows from wastewater / sewerage	
	infrastructure	
	2) Major incidents which have a significant	
	impact on the delivery of water or sewerage	
	services	
Response to serious water	Respond within 1 hour	
supply bursts and leaks	Commencement of work within 1.5 hours	
	of notification	
	Completion of work within 6 hours	
Response to moderate water	Respond within 1 hour	
supply bursts and leaks	Commencement of work within 3 hours of	
	notification	
	Completion of work within 6 hours	
	r r r r r r r r r r r r r r r r r r r	
Response to minor water	Respond within 24 hours	
supply bursts and leaks	Rectification within 3 days of notification	
Interruption during peak times	No plans to interrupt supply between 5am	
	to 7am, and 6pm to 11pm	

Attached for your information are copies of Rio Tinto's Water Services Customer Charter and Operating Licence.

If you have any questions in relation to the Customer Charter, Operating Licence, or levels of customer service, please contact your Rio Tinto Networks Contractor Management representative.

ATTACHEMENTS

PLEASE CONTACT OUR FRIENDLY OFFICE STAFF AT LYONS & PEIRCE FOR FURTHER INFORMATION. WE ARE ALWAYS MORE THAN

Brett Hardingham—Manager

Senior Administrator – Emily Giles

Supervisor – Kane Wilson Administrator – Shari Callum

Plumber – Dale Warren Plumber – Simon Mahady Plumber – Darren Blake Plumber – Aldo Gobo Plumber – Mathew Solly Plumber – Anthony Fawcett Plumber – Nathan Donegan Carpenter – Greg McFarlane

Apprentice – Brad Ciancotti Apprentice – Tom Giles



Lyons & Peirce Karratha Tom Price Branch Lot 35 Boonderoo Rd, Tom Price W.A 6751

Phone: (08) 9189 3709 Fax:: (08) 9189 3712 E-mail: brett.hardingham@lpk.com.au



201

The partnership of Lyons and Peirce consists of: Pervisor of all works and coordinapervisor of all works and coordinator of all major plumbing works. Revy Samson is the office manager and the Occupational Health, Safety and Puvironment Coordina-

·sınoy

Lyons and Peirce was established in April 1993 after being purchased from the Vac Tech Group. Mead Office is situated in Karratha together with the Raratha, Northwest, Asset Management and Pump Out Division branch's. The Tom Price Branch was opened in 2004. It is a 24 hour, 7 day a week operation, however normal office hours are 0730—1600 Monoffice hours are 0730—1600 Monday to Friday. The office phone is diverted to a mobile phone after

TROTSIH PYONS AND PEIRCE


- Airdrifl (246 Bobcat)
 - Buippointa pilo?
 - 091 ләрзәтқуод
- Rockbreaker (25T Excavator)
 - Concrete Batchmixer
 - Pront end loader IT25B
 - HII trader 12H
 - 1pogoG
 - P8.1 rotavator 1.8P
 - ૱૦૫ૢ૽ૺ૱ૹૡ

0

- P22 rotovacy.
- doL КвлL/ившsəpвлL L+
 - doL (bil To
 - daiH/19qqiPPL1
 - rsbool—wol P22

:məf v 1snl ərv

ssan . and of now not insimilar in the second s



по-шог Эдэдшиувигрлоу 11219 :Jiom-Д 212E 6816 (80) :ХоД 602E 6816 (80) :ЗиоуД

Дуопз & Peirce Кагаанда Пот Price Branch Lot 35 Boonderoo Rd, Tom Price

mitter in action



mətsks rətoW toH a gnillatenI

